TECHNOLOGY DEPT.

AVIATION WEEK

DEC. 12, 1949

A McGRAW-HILL PUBLICATION

PUBLIC LIBRARY
AUG 4 1950
DETROIT

It is our responsibility
to merit continually
the confidence which the
aircraft industry
has placed in Honeywell
Aeronautical Controls.



CREATIVE ENGINEERING

MINNEAPOLIS
Honeywell
AERONAUTICAL CONTROLS

Makers of the Famous M-H Electronic Autopilot, Fuel Gage, and Turbo Supercharger Controls, Standard on Many Types of AAF Aircraft

NEW DEPARTURE

BALL BEARINGS

NEW DEPARTURE • DIVISION OF GENERAL MOTORS CORPORATION • BRISTOL, CONNECTICUT

Deltabeston®
triple-silicone-treated
AIRCRAFT WIRE

gives
extra heat protection
in limited space

because it's built to beat the heat



Where wiring space is limited and ambient temperatures are high, use Deltabeston and get the extra heat protection of this small-diameter, triple-silicone-treated aircraft wire.

Two layers of silicone-impregnated, felted-asbestos insulation plus silicone-impregnated glass braid and an over-all silicone-varnish finish make Deltabeston extra tough, extra high in moisture resistance. Triple-silicone treating also gives Deltabeston a remarkably high degree of immunity from the effects of flame and heat... gives unusual abrasion resistance, because the glass braid has the extra protection of silicone varnish.

The famous heat-beating Deltabeston line includes wires and cables designed for power, lighting, and communication systems, and for instrument wiring. If you'd like to know more about this famous, high-quality line, just address Section W43-1292, Construction Materials Department, General Electric Company, Bridgeport 2, Connecticut.

GENERAL ELECTRIC

Aviation Week

Volume 51 **December 12, 1949** **Number 24**

Headline News
Planes USAF Will Buy in 1950.....11
CAB Okays Coast-to-Coast Coach.....12
Constitution Use Poses Problems.....14
Sikorsky's H-19 Helicopter.....15
Canada Testing Tailless Glider.....16

Financial
Airline Dividends Seen Increasing.....17

Aviation Sales & Service
British Bid in Lightplane Market.....18

Avionics
What Does Rain Do to Radar?.....21

Aeronautical Engineering
Chromium Plate and Fatigue Limit....25
Liftmaster Freight Lift.....28
Caltech Tunnel Exceeds Mach 10.....30

Production
Pressure Welding Being Studied.....36

New Aviation Products
Power Supply for Large Aircraft.....43

Air Transport
How Fair is PAA-AOA New Deal?....46
Nonskeds After Atlantic Traffic.....47

Departments
Who's Where 7
Industry Observer 7
Aviation Calendar 8
News Digest 9
Briefing for Dealers.....18
Engineering Forum 34
AF Bid Awards.....38
Shortlines 53
CAB Schedule 53
Strictly Personal 56
What's New 56
Letters 58

Robert H. Wood
EDITOR

Merlin H. Mickel.....MANAGING EDITOR

William Kroger.....Assistant Managing Editor
Robert B. Hotz.....News Editor
Irving Stone.....Technical Editor
Alexander McSurely.....Manufacturing Editor
Charles L. Adams.....Transport Editor
Robert McLarren.....Engineering
Stanley L. Colbert.....Assistant News Editor
Marie Adams.....Editorial Assistant
Scott H. Reiniger.....Editorial Assistant
Victoria Giaculli.....Editorial Assistant
Erwin J. Bulban.....Editorial Assistant
Henry Lefer.....Editorial Makeup

Executive and Editorial Offices: 330 West 42nd St., New York 18, N. Y., Phone Longacre 4-3035; National Press Bldg., Washington 4, D. C., Phone National 3414

Domestic News Bureaus: Atlanta 3, Rhodes-Haverty Bldg.; Chicago 11, 520 N. Michigan Ave.; Cleveland 15, Hanna Bldg.; Detroit 26, Penobscot Bldg.; Los Angeles 14, 621 S. Hope St.; San Francisco 4, 68 Post St.; Houston, 514 South St. *Correspondents* in more than 60 major cities.

Foreign News Bureaus: London, Paris, Frankfurt, Tokyo, Bombay, Melbourne, Rio de Janeiro. Mexico City. *Correspondents* in more than 45 major cities.

ROBERT F. BOGER
PUBLISHER

J. G. Johnson, *Business Manager*; R. W. Martin, Jr., *Sales Manager*; Sales Representatives; J. C. Anthony, New York; M. J. Storz, Philadelphia; V. K. Dissette, Cleveland; L. J. Biel, Chicago; W. E. Donnell, St. Louis; J. H. Allen, Dallas; R. C. Maultsby, Atlanta; J. W. Otterson, San Francisco; C. F. McReynolds, Los Angeles. Other sales offices in Pittsburgh, Detroit, Boston, London.

Member of Associated Business Publications, Inc., and the Audit Bureau of Circulations

Aviation Week December 12, 1949 Vol. 51, No. 24

McGRAW-HILL PUBLISHING CO., Inc., James H. McGraw (1860-1948), Founder. Printed at 99-129 N. Broadway, Albany, N. Y. JAMES H. McGRAW, Jr., President; CURTIS W. McGRAW, Vice-President and Treasurer; EUGENE DUFFIELD, Senior Vice-President, Publications Division; NELSON BOND, Vice-President and Director of Advertising; JOSEPH A. GERARDI, Secretary; J. F. BLACKBURN, Jr., Vice-President and Director of Circulation . . . Published Weekly in U. S. A., price 50¢ a copy, 50¢ in Canada. Subscription rates—United States and possessions, $6 a year, $9 for 2 yr., $12 for 3 yr. Canada, $8 for 1 yr., $12 for 2 yr., $16 for 3 yr., payable in Canadian currency at par. Pan American countries, $10 for 1 yr., $16 for 2 yr., $20 for 3 yr. All other countries, $20 for 1 yr.; $30 for 2 yr.; $40 for 3 yr. Address all communications about subscriptions to Director of Circulation, 330 W. 42nd St., New York 18, N. Y. Please indicate position and company connection on all subscription orders. Allow at least ten days for change of address . . . Entered as second class matter, July 16, 1947, at Post Office, Albany, N. Y., under Act of March 3, 1879. Copyright 1949, McGraw-Hill Publishing Co. Cable address "McGraw-Hill New York." Publications combined with AVIATION WEEK are AVIATION, AVIATION NEWS, AIR TRANSPORT, AERONAUTICAL ENGINEERING AND AIRCRAFT JOURNAL. All rights to these names are reserved by McGraw-Hill Publishing Co.



Amazing AiResearch device mathematically computes and helps you solve unusual problems in precise control of temperature...position...and pressure!

Originally created to maintain aircraft cabin and engine temperatures at *pre-selected* levels—regardless of outside temperature—this ingenious electronic "brain" may well possess wide applications in other industrial fields.

Operating with electronic sensitivity and speed, the AiResearch regulator can be used to control temperatures of gases, liquids, and solid materials and as a mathematical computer for similar problems. It can also be used for the exact *positioning* of controls—remote or otherwise. And it promises unusual abilities in solving problems of pressure, ducting, and safety control. We invite inquiries on its use in your field.

The Electronic Regulator is another example of the ability of AiResearch to design and *manufacture* specialized equipment for hard-to-do jobs. It indicates why nearly every type of high-altitude and jet aircraft produced in the U. S. carries AiResearch equipment.

Whatever your field—AiResearch engineers—designers and manufacturers of rotors operating in excess of 100,000 rpm—invite your toughest problems involving high speed wheels. Specialized experience is also available in creating compact turbines and compressors; actuators, with high speed rotors; air, gas and liquid heat exchangers; air pressure, temperature and other automatic controls.

AiResearch
DIVISION OF
THE GARRETT CORPORATION

An inquiry on your company letterhead will receive prompt attention.
AiResearch Manufacturing Company,
Los Angeles 45, California.



Making all Weather.... Good Flying Weather

● The greater number of flights being completed on schedule today reflects the advances being made in year-round weather control. Airlines, through their skilled meteorologists, now know more about the weather than ever before, and with the use of the most modern facilities and equipment are making their service increasingly independent of the weather.

● Before he takes off, the airline pilot knows the weather fronts to avoid along the flight route... and the tail-winds that will help him make up time consumed in flying above or around storm areas. A pre-flight weather analysis... based on the Weather Bureau's and the airline's own meteorological studies . . . gives him this valuable information.

● To help the pilot utilize to the utmost the information he has at his finger tips, airlines are supplying him with the latest in facilities and equipment—the best in ships, engines and instrumentation. Another contributor, the C.A.A., now operates approximately 100 beam landing-approach systems in major airports throughout the country. These systems have lowered the weather ceiling for the airlines... allow more "flying" days.

● Sperry *has been* and *is* contributing to all-weather flying... flight instruments for attitude and direction...the A-12 Gyropilot* for smoother flying even in turbulent air... the Automatic Approach Control for bringing sky giants to less than 100 feet of the runway no matter what the weather. And Sperry research pilots at the controls of Sperry's flying laboratories are taking off, day and night, when flying weather is at its worst, to study, perfect and devise new means of making all weather good flying weather.

*Trademark Reg. U. S. Pat. Off.

SPERRY GYROSCOPE COMPANY

DIVISION OF THE SPERRY CORPORATION
GREAT NECK, NEW YORK

NEW YORK • CLEVELAND • NEW ORLEANS • LOS ANGELES • SAN FRANCISCO • SEATTLE

WHO'S WHERE

Changes

► **New Appointments**—Board of directors of Sabena Airlines has appointed **William Deswarte** general manager, succeeding **Tony Orta,** who becomes counsellor of the airline with the title of honorary director-general manager. . . . **Ray A. Rugge** has been appointed chief engineer of Lear, Inc. . . . Western Air Lines named **Carl J. Setter** chief cost analyst. . . . **William W. Martenis** is manager of sales engineering for Minneapolis-Honeywell Regulator Co. . . . Accessory Overhaul Industries, Inc., appointed **George E. Campbell** general sales manager. He was formerly with Taca Airways.

Three new appointments in General Electric Co.'s Aviation division: **R. A. Averitt** and **H. T. Hokanson,** now manager and assistant manager, respectively, of the newly-formed Application Engineering division; **E. S. Gallagher,** now manager of sales of the new Sales division.

Walter Macatee, formerly manager of the Airport division of the American Road Builders' Assn., is now with the Civil Aeronautics Administration as highway transportation specialist in the Office of Airport. . . . **Lucien P. Tuckerman** has joined the National Bureau of Standards as liaison engineer in the Guided Missiles Laboratory.

Charles S. Chester has become the new director of the Washington State Aeronautics Commission, replacing **Col. Joseph P. Adams,** recently resigned to resume law practice in Seattle. . . . National Airlines has named **Eugene Lefferts** New York district sales manager.

► **New Board**—LANSA Airlines has elected a new board of directors: **Karl Parrish, Rafael Barvo, Julio Comelin, Jose Fernandez and Jose Gomez.** President of the carrier, **Hernando Padilla,** has resigned. No successor has been named.

► **Resigned**—Menasco Manufacturing Co.'s general sales manager **B. C. McNeill** has resigned. He is replaced by **J. I. Hamilton.** . . . **Dale Armstrong,** formerly public relations for Foote Cone and Belding in Great Britain and Europe, where he handled Lockheed and other accounts, has resigned.

Elections and Honors

Lee Glasgow has been elected assistant treasurer of American Airlines. . . . **Rufus C. Phillips, Jr.,** President of Airways Engineering Corp., has been appointed chairman of the Airport Committee of Washington, D. C., Board of Trade.

Portrait of **T. E. Braniff,** president of Braniff Airways, has been placed in Oklahoma Hall of Fame, Oklahoma City.

American Society of Mechanical Engineers cited **Donald F. Warner,** design engineer for General Electric's aircraft gas turbine divisions, and his associates, for their contributions "to the progress of the jet engine industry in its early days, by undertaking development under conditions of abnormal pressure." The citation was made by ASME's gas turbine power divisions.

INDUSTRY OBSERVER

► **First successful refueling of USAF Republic F-84 jet fighters has been accomplished at the British base of Flight Refueling, Ltd., using an Avro Lancaster as the tanker. Fuel was received in Thunderjet's wingtip tanks. Flight Refueling is also conducting further refueling research with B-29s for USAF at the Tarrant, Rushton base.**

► A new version of the Cierva Air Horse three-rotored British helicopter, is the twin-engined W-11T, designed to carry 32 passengers or 5 tons of cargo. One design version would use conventional Rolls-Royce engines, while another version would use gas turbines. In either case the engines are mounted outside the enlarged fuselage in nacelles, leaving fuselage space clear for cargo or passengers.

► **Sikorsky Aircraft's new H-18 helicopter now in production for the USAF is an enlarged four-place version of the S-52 which was landed inside the Pentagon building court at Washington a year ago. It's an indication of the general trend in the helicopter industry away from two-placers except for helicopter trainers. H-18 can be modified to carry two litters with pilot and attendant.**

► The Canadian twin-jet all-weather fighter, XC-100 (now designated CF-100) is expected to be ready for its first test flights at the Toronto plant of A. V. Roe Canada Ltd., by year's end. Canadian government is spending $7 million on the development of the fighter, the largest allotment assigned to any single project, and a third of the total $21 million being expended for defense research in the fiscal year ending March 31.

► **Ryan Aeronautical Co. has taken the test engine out of the prototype Super Navion and is waiting for the first production Lycoming GO-435-C2 geared engine (260 hp. at takeoff) to begin certification tests. Prototype has been flown several hundred hours, including one coast-to-coast and return trip for demonstrations and shakedown.**

► Look for Aircooled Motors, Inc., at Syracuse, N. Y., to come back into more active aircraft engine competition under a reorganization plan now being developed by trustees for the Tucker Corp. which held controlling interest in the engine company. Since Tucker's financial difficulties, and the cooling off of the lightplane market, Franklin aircraft engines have not been in production except for the 6V4-178-B32 helicopter engine marketed in small quantities to Bell, Sikorsky, and United Helicopters.

► **A new six-cylinder Franklin engine with around 190 takeoff horsepower is going to give Continental and Lycoming some new competition in this power class, if Aircooled Motors reorganization plans work out. The engine, Model 6AG4-185-B13, was developed a year ago but held out of production. Another Aircooled powerplant being planned is a redesign of the 500-cu.-in. displacement engine originally built to power the Republic Seabee amphibian, and now being fitted with a reduction gear, expected to result in 250 to 275 hp. with relatively slow propeller speed.**

► Use of contra-rotating propeller systems in airplane powerplants goes along with growth in the use of turbine-propeller combinations. Problems of turbulence between blades which caused earlier difficulties have been at least partially solved. And there is no other logical solution to provide sufficient blade area to absorb the greatly increased turbine powers. The experimental Aeroproducts six-blade contraprop of advanced design used to test the Allison T-40 5500-hp. turbine is a sample of things to come.

► **A 30-channel oscillog.aph is being installed in a Lockheed F-80 for the USAF at Curtiss-Wright Corp., Columbus division, to record stresses and strains in different parts of the plane's structure for the new USAF flight load test program. Similar instrumentation is planned for a Republic F-84, a North American B-45 and a Boeing B-50 following completion of the F-80 installation.**

WE'RE KNOWN BY THE COMPANY WE KEEP!

The proud emblem of American Overseas Airlines is etched against the skies above every important city in the world. On its overseas routes alone AOA transported over 82,000 passengers during 1948 plus 10,215,150 pounds of vital cargo. American carries responsibility, too! There's responsibility to the United States government, to their air freight clients and to the traveling public. PAC is proud to be a partner in these trusts, and to service the far-flung operations of this great pioneer airline. Here's another evidence of teamwork...PAC and AOA...

"OPERATION EFFICIENCY"



PACIFIC AIRMOTIVE CORP.

Burbank, California

OTHER MAJOR DIVISIONS

LINDEN, N. J. • KANSAS CITY, KANS.

OAKLAND • SEATTLE • ANCHORAGE

AVIATION CALENDAR

Dec. 9-10—First Convertible Aircraft Congress, sponsored by Philadelphia chapter of IAS and American Helicopter Society, in Philadelphia.

Dec. 15-16—Air Transport Assn. board of directors annual meeting, Carlton Hotel, Washington, D. C.

Dec. 16-17—1949 national aviation meeting, organized by the National Aeronautical Assn., Hotel Statler, Washington, D. C.

Dec. 17—Institute of the Aeronautical Sciences 13th annual Wright Brothers lecture, U. S. Chamber of Commerce Building auditorium, Washington, D. C.

Dec. 31-Jan. 7, 1950—"Winter Wing Ding," sponsored by the Mount Plymouth Hotel and Golf Club, Mt. Plymouth, Fla.

Jan. 10-11, 1950—Florida Flying Alligator Club's Annual Rituals & Frolics, Melbourne, Fla.

Jan. 10-27—Fourth annual Air Transportation Institute, conducted by American University in cooperation with CAA and ATA, Washington D. C.

Jan. 13-15—All American Air Maneuvers, Miami.

Jan. 16-17—Miami-Havana Air Cruise for private planes, conducted by Florida Air Pilots' Assn.

Jan. 16-19—Plant Maintenance Show, sponsored by American Society of Mechanical Engineers and the Society for the Advancement of Management, Cleveland Auditorium, Cleveland.

Jan. 17—38th annual dinner of the Traffic Club of Philadelphia, Benjamin Franklin Hotel, Philadelphia.

Jan. 17-19—University of Illinois second annual Custom Spray Operators school, Urbana, Ill.

Jan. 23—IAS annual Honors Night dinner, Hotel Astor, New York, N. Y.

Jan. 23-26—IAS 18th annual meeting, technical sessions, Hotel Astor, New York, N. Y.

Jan. 24—Ninth session, ICAO Council Montreal.

Feb. 18-26—National Sportsmen's Show, Grand Central Palace, New York, N. Y.

Feb. 27-Mar. 3—Spring meeting, American Society for Testing Materials, Hotel William Penn, Pittsburgh.

Mar. 6-9—47th annual meeting, American Road Builders' Assn., Netherlands Plaza Hotel, Cincinnati.

Mar. 28-31—National Plastics Exposition, sponsored by Society of the Plastics Industry, Navy Pier, Chicago.

Apr. 4-6—Engineering and Maintenance conference, Air Transport Assn., Hotel Continental, Kansas City.

Apr. 16-20—Annual business meeting, American Assn. of Airport Executives, Neil House Hotel, Columbus, Ohio.

Apr. 17-19—1950 aeronautic meeting, Society of Automotive Engineers, Hotel Statler, New York City.

June 10-13—National Aeronautic Assn. annual convention, Hotel Statler, St. Louis, Mo.

PICTURE CREDITS

13—Wide World; 15—Sikorsky Aircraft; 16—Howard Levy; 18—Charles Cain; 28—Douglas Aircraft Co.



a unique Sub-contractor

EXPERT FABRICATORS OF METAL AIRCRAFT PARTS

Lavelle invites your investigation of an organization distinguished for specialized engineering and precision work. We are proud of an enviable record of workmanship, service and materials.

BAFFLES and DEFLECTORS • JET ENGINE COMPONENTS
RADAR REFLECTORS • ENGINE MOUNTS
ROCKET COMPONENTS • FIRE WALLS
EXHAUST DUCTS • TAIL PIPES

Lavelle AIRCRAFT CORPORATION
NEWTOWN, Bucks County, PENNA.

NEWS DIGEST

DOMESTIC

Wright Aeronautical Corp. and two locals of the UAW-CIO have reached an agreement on terms for new labor contracts, subject to ratification by union membership. Previously, both unions had threatened to strike (AVIATION WEEK, Nov. 28). New contract will provide for company-paid hospital benefits, and union has agreed to support the company's effort to assure a normal day's work on the part of employes.

Hughes Tool Co. was exonerated of charges claiming misuse of veterans' preference in connection with purchase of five surplus planes in 1946. Federal District Court in Honolulu dismissed the case when the government admitted that neither Howard Hughes nor any other officer of the company had any knowledge of the transaction.

Gen. Carl A. Spaatz (Ret.), former USAF chief of staff, heads a board to select an Air Force Academy site. Recommendations must be in the board's hands by Dec. 31 so that the board can report to Congress in the next session. Other board members are Lt. Gen. Hubert R. Harmon and Maj. Gen. David M. Schlatter.

A CAA committee has recommended to the Budget Bureau that Andrews Air Force Base, Camp Springs, Md., be converted into a civilian air terminal as the most satisfactory method of relieving air traffic congestion at Washington National Airport.

Charles A. Lindbergh is recipient of the annual Wright Brothers Memorial Trophy, to be awarded Dec. 17, 46th anniversary of the first powered flight by the Wrights. Presentation will be made at the annual Aero Club of Washington dinner.

Civil Aeronautics Administration has approved the Dehmel Curtiss-Wright flight simulator for use in giving Pan American Airways pilots refresher and competency checks. Simulator will not entirely replace flying checks; pilots will put in 30-45 min. in the actual craft. Pan American uses the device for its fleet of Stratocruisers.

Eugene E. Wilson, chairman of the board of the National Aeronautics Assn., will be principal speaker at the opening business session of the National Aviation Forum in Washington, Dec. 16. Forum is planned as a successor to the National Aviation Clinic, held in previous years in Oklahoma City, Springfield, Ill., and Detroit.

Ninety-Nines next spring will sponsor a transcontinental air race open to all women flyers, but limited to planes with 250 hp. or less. Race will start in San Diego and finish in South Carolina. Individual race handicaps will be based on advertised cruising speed of each aircraft.

Corps of Engineers has established a Tullahoma (Tenn.) Engineering District to supervise construction of nontechnical facilities at the new Air Engineering Development Center (AVIATION WEEK, Nov. 21). Temporary headquarters will be in the Office of Chief of Engineers in Washington.

Aircraft shipments during September decreased 24 percent from 3,916,900 lb. reported in August, to 2,984,100 lb., according to the Bureau of the Census. September shipments of civil aircraft amounted to 284 planes valued at $14.1 million. Military airframe weight during September amounted to 2,308,100 lb., or 77 percent. Military accounted for 98 percent of September's aircraft engine shipment of 4,721,300 hp. Engine figure was up 26 percent over August's 3,733,800 hp.

CAB has invited certificated carriers and large nonscheduled operators to apply for authority to conduct group charter operations between U. S. and Europe next summer, when Holy Year traffic will be at its peak. The Board will consider applications filed before Mar. 1, 1950, proposing such operations between June 1 and Sept. 30, 1951. A PAA charter arrangement with Felix Roma, a Catholic charitable organization, providing two roundtrips weekly to Rome during off-peak periods next year has already been approved.

FINANCIAL

Garrett Corp. and its divisions, including AiResearch Manufacturing Co., and AiResearch Aviation Service Co., has a backlog of approximately $13 million in manufacturing orders. J. C. Garrett, president, reported that all divisions were operating at a profit; board of directors has voted a 25-cent dividend payable Dec. 26 to stockholders of record Dec. 8, 1949.

FOREIGN

British Ministry of Supply approved the de Havilland Goblin 2 engine for an overhaul life of 600 hr., after exhaustive 12-month tests on the jet powerplant.

Italy is spending about $1.4 million from its current counterpart fund, under agreement with ECA, for improvement of Capodichino Field, near Naples, and Ciampino Field, near Rome.

Revere
THERMOCOUPLE WIRE
in accordance with
ARMY-NAVY STANDARDS

Iron-Constantan
AN-W-8c Specification

TYPE II

8 ohms per 100 feet
Class A.....(Revere WI-2600)
Class B.....(Revere WI-2601)
Class C.....(Revere WI-2602)

TYPE III

8 ohms per 200 feet
Class A.....(Revere WI-2603)
Class B.....(Revere WI-2604)
Class C.....(Revere WI-2605)

Chromel-Alumel
AN-W-29a Specification

TYPE I

7 ohms per 25 feet
Class A.....(Revere WC-2606)
Class B.....(Revere WC-2607)

TYPE II

7 ohms per 50 feet
Class A.....(Revere WC-2608)
Class B.....(Revere WC-2609)

TYPE III

7 ohms per 100 feet
Class A.....(Revere WC-2610)
Class B.....(Revere WC-2611)

* * * * *

As a further protection at elevated temperatures, the above Chromel-Alumel wires are furnished with a silicone impregnant and/or stainless steel flexible braid. Write for further details.

Revere
CORPORATION OF AMERICA
WALLINGFORD 2, CONNECTICUT

If You Have a Tough Connector Problem, Ask

BREEZE

FOR THE ANSWER!

SPECIAL CONNECTORS

for advanced radar and electronic equipment

Where electrical connector requirements are strict, or the job specialized, take advantage of Breeze experience. Breeze has engineered such advantages as removable contacts for panel-type connectors. This exclusive feature greatly simplifies wiring and maintenance, and is typical of advanced Breeze design.



PRESSURE-SEALED
OR WATER-TIGHT CONNECTORS



Engineered to specification in aluminum, brass, or steel. All sizes, capacities. High voltage pulse type connectors. Also rotary shaft seals and allied equipment. Write for details.



BREEZE "Monobloc Miniatures" (above) come in 5, 10, 15, and 20 contact sizes or multiples thereof. Capacity—10 amperes with 7 millivolt drop; 500 volts DC or 275 volts AC.

REMOVABLE CONTACTS

Save Time, Trouble, Confusion

Simple tool (right) removes contacts for bench soldering. Production time reduced, close work eliminated, errors avoided. Contacts simply snap back into block.



Contact retained securely in block by two spring locks.

Tubular tool inserted from contact side to close springs.

Contact easily removed, but cannot come loose in service.

LOOK TO THE BREEZE MARK FOR QUALITY

Other Breeze Precision Products



ACTUATORS: All types, sizes. Complete control systems engineered to requirements. Above: Landing gear actuator, Fairchild Packet.

RADIO SHIELDING: For any type of high or low tension system. New type "unit leads" or re-wirable leads. Flexible shielded conduit.

"AERO-SEAL" Worm-Drive Hose Clamps. Vibration proof, uniform clamping, use again and again. Cadmium plated or stainless steel.

BREEZE CORPORATIONS, INC.

41-B South Sixth Street Newark 7, New Jersey

Vol. 51, No. 24

AVIATION WEEK

Dec. 12, 1949

1950 Air Force Plane Procurement

	President's Budget (48-group Air Force)	After Johnson Cut*
Grumman SA-16	30	11
Lockheed TF-80	110	80
North Amer. T-28	125	85
Convair T-29	39	12
Fairchild T-31	199	0
North Amer. F-86	300	250
Northrop F-89	38	27
Lockheed F-94	178	125
Convair B-36	51	47
Boeing B-47	75	75
Fairchild C-119	69	53
Boeing C-97	22	14
Douglas C-124A	54	36
Chase C-122 or Northrop C-125	25	0
Total	**1335**	**815**

** Number of planes cut from total: 520 ($300,000,000). Percentage of numerical cut: 38.9.*

Planes USAF to Buy in 1950

Budget cuts limit procurement to 815 aircraft at cost of $1.1 billion, although more money may be available.

USAF has settled on a minimum aircraft procurement program for fiscal 1950 of $1.1 billion, based on the heaviest cuts ordered by Defense Secretary Louis Johnson.

This compares with $1.4 billion authorized by the President's budget and with $1.9 billion voted by Congress in October. The extra $500 million voted by Congress was impounded by the President.

Size of the firm cut demanded by Johnson below the amount set in the President's budget still remains uncertain, and a moderate amount of additional funds may be available.

First indications were that another $300 million would be sliced but later reports indicated that the cut would be closer to $200 million. The following schedule is based on the $300 million cut and the aircraft procurement budget will be increased if Johnson does not stand firm on a cut of that size.

► **Planes Shrink**—The $1.1 billion of the USAF minimum fiscal 1950 aircraft procurement program would purchase only 815 planes in contrast to 1335 under the $1.4 billion program. An additional 474 planes were earmarked for the extra $500 million voted by Congress but impounded by the President. Thus aircraft procurement program has shrunk from the 1809 maximum voted by Congress to the 815 under the minimum Johnson plan.

Largely as a result of this tremendous cut imposed by the executive branch of the government, the Office of the Secretary of Defense has been blocking all efforts to release publicly fiscal 1950 military aircraft procurement schedules. Various devices are under consideration whereby the numbers would be camouflaged under total airframe pounds and no breakdown by companies be provided as was done last year.

► **Trainer Cut**—Bulk of the Johnson-ordered cut will be felt in the trainer category where the Fairchild T-31 primary trainer has been eliminated; the North American T-28 intermediary trainer cut from 125 to 85; the Lockheed TF-80 two seater jet trainer from 110 to 80 and the Convair T-29 twin engine navigational trainer slashed from 29 to 12.

Transports come in for a heavy reduction with Douglas taking a cut from 54 to 36 C-124As; Boeing drops from 22 to 14 C-97s; Fairchild from 69 to 53 C-119s and the light assault transport category in which Chase Aircraft Corp. and Northrop Aircraft Inc. were competing is eliminated.

► **Fighter Situation**—Jet night fighters also took a cut with both the Northrop twin jet F-89 (38 to 27) and the Lockheed two-seater F-94 (178 to 125) taking slashes. USAF is concentrating on the Lockheed night fighter because of its relatively low cost and long time value as a night fighter trainer after it becomes tactically obsolescent.

North American is getting all the day fighter business with a firm allocation of 250 F-86s compared to an original schedule for 300 under the 48-group program. Although USAF is still listing the North American fighter as the F-86 it is more than likely that part of this order will eventually be switched to the North American F-93 which is a faster and radically modified version of the F-86. The F-93 features a pointed nose, flush air inlets and will be powered by a Pratt & Whitney J-48 (better than 6000 lb. thrust) turbojet just going into production at the engine firm's East Hartford, Conn., plant. The J-48 will be equipped with an afterburner.

► **Two Bombers**—Bomber procurement is concentrated on the twin choices of Strategic Air Commander Lieut. Gen. Curtis E. LeMay—the Convair B-36D, of which 47 will be bought, compared to the 51 originally scheduled; and the Boeing six-jet B-47, which remains firm at 75 planes in both programs. The B-47 is being built in Boeing's Wichita plant.

Grumman will get another order for its twin-engine amphibian rescue plane being used by both the USAF and Navy. There is some additional procurement money not being allocated which will probably be used to procure helicopters for Arctic rescue work.

CAB Okays Coast-to-Coast Coach

American and TWA begin trans-continental flights this month with DC-4s; American can use DC-6s in April.

Air coach transportation this month received its biggest boost as the Civil Aeronautics Board opened the richest domestic long-haul route to scheduled, tourist-type operations at 4½-cents-a-mile fares.

American Airlines and TWA were given permission to start New York-Chicago-Los Angeles coach flights with 70- and 60-passenger DC-4 equipment, respectively, starting Dec. 27. More importantly, CAB authorized American to replace its DC-4s with 70-passenger DC-6s in April.

AA will thus become the first carrier to use high-speed postwar equipment for tourist-type service. Some industry observers believe TWA may be forced to convert some of its Constellations into high-density ships to meet American's competition.

AA already has solicited bids for modifying three of its 52-passenger DC-6s into 70-seat air coaches: work on the ships will start in January.

Both American and TWA plan to make one transcontinental roundtrip daily with coach equipment. Their $110 coast-to-coast fare compares with $88-$99 for major irregular operators, who are expected to suffer severely from the new scheduled competition (AVIATION WEEK, Nov. 7). Regular 6-cents-a-mile airline fare from New York to Los Angeles is $157.85.

▶ **UAL Gets Set**—With Northwest Airlines already offering 4-cents-a-mile DC-4 coach service between New York and Seattle, United Air Lines becomes the only certificated transcontinental carrier without a cut-rate coast-to-coast operation. And even UAL last week hoisted one foot on the low-fare bandwagon by proposing a reduced rate of 5 cents a mile on one DC-4 roundtrip daily over its Los Angeles-San Francisco-Portland-Seattle and Chicago-Omaha-Denver-Salt Lake City-Boise-Portland-Seattle Routes.

If CAB approves, the reduced UAL fares will become effective Jan. 16. The new United tariffs would go part way toward meeting the 4-cents-a-mile coach competition of Northwest between Chicago, Portland and Seattle; and of Western Air Lines along the Pacific coast.

▶ **Policy Departures**—The latest TWA and American tariffs differ in two respects from CAB's previous policy statements on air coach announced last September:

• **No limitations on departure** and arrival times were imposed. The Board indicated it had required such limits to confine coach operations to off-peak periods of the day or night. In transcontinental service, however, there appeared to be no well-defined traffic peaks.

Thus American's westbound coach flights will leave Newark at 9:30 p.m. and arrive at Los Angeles at 10:29 a.m. Eastbound coach will leave Los Angeles at 6:30 p.m. and arrive at Newark at 10:57 a.m.

• **Deadline was extended** for coach tariffs from June 30, 1950 to Dec. 31, 1950 for the new transcontinental service to give American a reasonable time to obtain experience with its high-density DC-6s. CAB indicated it would establish Dec. 31, 1950, as the deadline for other coach operations wholly or partly competitive with transcontinental tourist-type services of AA and TWA. The June 30 deadline will continue for remaining coach tariffs.

▶ **DC-6 Factors**—CAB said it permitted use of DC-6s in coach service because the planes will have a sufficient number of seats to allow gross revenues at lower rates to approximate the gross revenue from regular 52-seat flights at comparable load factors.

The Board recognized there is danger that a DC-6 coach operation may divert more traffic from first-class flights than DC-4s, but it indicated the threat was outweighed by operating and cost advantages and potential service improvements to the public. If, at the end of the experimental period, it appears that DC-6 coach operations create excessive diversion, CAB will require the faster coach service to be discontinued.

Coincidentally with its action on transcontinental service, CAB extended TWA's Kansas City-Los Angeles coach tariff until Mar. 1 to permit the carrier to replace its DC-3s with larger equipment. Earlier, however, the Board suspended West Coast-Hawaii tourist fares which Pan American Airways and Northwest Airlines had hoped to institute Dec. 1.

▶ **Capital Kick**—Capital Airlines had asked for suspension of both the AA and TWA transcontinental coach tariffs insofar as they applied to the New York-Chicago link, where it already operates reduced-rate service. It said use of luxury DC-6 equipment and the lack of restriction on departure time "violate fundamental principles on which CAB has established coach services."

According to Capital, AA's coach-type DC-6 service at 4½ cents a mile would be substantially more attractive than Capital's regular 6-cents-a-mile 50-passenger DC-4 operations. (Capital's New York-Chicago coach rate of $29.60 will be well under AA's $35 coach tariff.)



SWEDISH JET NOW IN PRODUCTION

Sweden's Saab 29 transonic jet fighter (AVIATION WEEK, July 12, 1948) is now in quantity production, after undergoing 12 months of flight testing. The pressurized interceptor is equipped with an ejection seat of Saab's own design. Three prototypes are equipped with British-built de Havilland Ghost jet engines of 5000 lb. static thrust; production models will have engines of the same type manufactured under license in Sweden. Saab claims the craft has reached its design Mach number.

TWA also attacked American's DC-6 coach proposal. Board Chairman Warren Lee Pierson wrote CAB members that TWA "is opposed to introduction at this time of DC-6 Stratocruiser or Constellation equipment into the air coach field, since we believe such action would constitute an indiscriminate entry into this market, resulting in a general debasement of the existing passenger fare level."

Baker's Views

G. T. Baker, president of National Airlines, last week strongly endorsed coach operations, pointing to his airline's successful experience. In a speech before the New York Society of Security Analysts, he gave this example:

At one time, the carrier had a flight that left New York at around midnight because of schedule balancing requirements. If 12 passengers were aboard, the company considered itself lucky. Now, with little difference in service but a lot of difference in price, 40 and 50 passengers are carried. The contrast was pointed up in carrying 10 passengers at $80 a head and 30 at $50 each as an indication of successful air coach economics.

▶ **Two Faults**—Baker asserted that there are two major faults with coach operations as presently regulated. These are the time and equipment restrictions. The public is inconvenienced when it is forced to fly at odd hours to save money. Neither is it logical to restrict an airline to DC-4 equipment in air coach service. More modern equipment, such as DC-6s, can be operated for considerably less per seat-mile than DC-4s.

U. S. Steps Into Canada-Colonial Fight

A U. S. State Department protest note to Canada last week questioned the right of the Dominion's Air Transport Board to revoke Colonial Airlines' license to operate between New York and Montreal.

The Department said it did not believe such action was contemplated by "any provision" of the U. S.-Canadian air agreement, thereby bringing to a diplomatic level latest developments in Colonial's efforts to prevent Trans-Canada Air Lines from starting competitive service between the two points.

The Canadian agency recently ordered Colonial to show cause why the license should not be revoked. Hearing on the order was set for today.

Colonial President Sigmund Janas told AVIATION WEEK that the Canadian board's action was not unexpected. "They (the board) have been trying to intimidate me for some time, and now they have come out in the open."

ASSISTANT SECNAVAIR

John F. Floberg, former wartime Navy gunnery officer, was named by President Truman as assistant Secretary of the Navy for Air, succeeding Dan A. Kimball, who was named undersecretary. Floberg, a recess appointee, took office last week.

The Canadian "show cause" order followed a decision by a special U.S. court in Washington telling CAB to suspend action on TCA's request for Montreal-New York operating rights until the Supreme Court had ruled on the legality of last June's U.S.-Canadian civil air agreement. This pact permitted Canada to designate a carrier to fly not only the Montreal-New York link but also routes through Florida to the Caribbean, and through Hawaii to Australia.

The U. S., in turn, was given traffic rights at Gander on the North Atlantic route and at Edmonton, Alberta. Colonial claimed its property rights in the New York-Montreal route were being taken away from it without due process of law by virtue of a CAB conspiracy.

Last month, the special U. S. court dismissed Colonial's suit which contested the constitutionality of the foreign air carrier permit sections of the Civil Aeronautics Act and charged that the U. S.-Canadian pact is invalid. But the court refused to lift the temporary injunction Colonial had obtained to prevent CAB from making any recommendations on the TCA case to President Truman, who must approve new foreign air carrier permits.

West Coast Visit

West Coast aviation manufacturers will have a discussion of renegotiation problems, with Frank L. Roberts, chairman of the Military Renegotiation Policy and Review Board, Thursday afternoon, Dec. 8 at the State Building in Los Angeles. A talk by Roberts on "Fundamentals of Statutory Renegotiation," will be followed by a forum discussion on specific manufacturers' problems.

General industry session follows a tour of individual conferences at aircraft plants, which started last week at the Seattle Boeing plant and included Lockheed and North American Aviation.

Scheduled visits include Convair at San Diego, Dec. 5, Northrop and subcontractors at Hawthorne, Dec. 6, and Douglas and subcontractors at Santa Monica, Dec. 7 and 8.

Touring group includes Barron Grier, counsel, MRPRB; Sumner Marcus, counsel, Navy division, and Thomas Coggeshall, Stuart Ross and Hayward L. Elliott, of Air Force division, Armed Services Renegotiation Board.

Study Made of Aircraft Labor

The master aircraft mechanic gets a wage which, over the country, averages $1.82 an hour. A janitor in the aircraft industry averages $1.12.

That is the range of average wages for 51 selected jobs in aircraft manufacturing based on a study by the Bureau of Labor Statistics covering last May and June. The survey covered 20 aircraft plants with 140,000 employes. Only one plant surveyed employed less than 500.

Most wages averaged between $1.50 and $1.70. Only janitors averaged below $1.24, which is the rate earned by Class C punch-press operators.

The greatest proportion of workers are assemblers, who earn $1.52 in Class A and $1.31 in Class B.

These are average wages for all 20 plants. Some plants pay more and some pay less. The figures do not include extra pay for overtime or night work.

▶ **Other Conditions**—Other results of the survey:

Workweek—All but one plant scheduled a 40-hr. week.

Second shifts—All but one plant scheduled second-shift work involving 22 percent of the plant workers.

Third shifts—Eleven plants had three-shift operations, but a small proportion of the employes worked on the third shift.

Shift premium—All plants pay a premium for work on second and third shifts.

Paid holidays—All but one plant give paid holidays. The number ranged from four to eight holidays.

Paid vacations—All give a paid vacation after one year on the job.

Pension plans—Seven plants have old-age retirement plans, three of which pay the entire cost.

Insurance—All plants have one or more types of insurance plans.

Constitution Use Poses Problems

CAA approval of craft for commercial operation might take a year or more—JATO use also must be cleared.

By Alexander McSurely

A Pan American World Airways bid to lease the two huge Navy Lockheed Constitution transports for 5 percent of the original Navy $27 million investment in the planes stands good chance of acceptance, Washington sources said last week.

A Navy spokesman said that if Pan Am had made such an offer it had no official status at this time since several factors would intervene before the transports would be open to lease to anybody. Presently the planes are being operated by the Navy and may continue in operation for several months. Before they are eligible for lease it must be established that the planes will not be required by the USAF and particularly Military Air Transport Service. Reports that neither MATS nor the Air Force is interested in the Constitutions have not been officially communicated to the Navy. Leasing the airplanes is seen as a final alternative before the process of deactivating the airplanes and putting them in cocoon storage at Litchfield, Ariz.

Pan Am and at least four other bidders—two airlines and two contract carriers—want the big Lockheed R-60s for high density air coach-type passenger transport. One suggested use is on Pan Am's New York-Puerto Rico run, where each plane might carry as many as 200 passengers. A one-stop transcontinental route with legs more evenly divided than the Navy's old transcontinental R-60 route (which stopped at Olathe, Kan.) is another good high density possibility, if one of the other lines gets the planes.

▶ **Certification Problem**—If Navy agrees to lease the planes, however, the successful bidder is up against a problem of getting them certificated for commercial operation by CAA, a problem which is serious enough to give several prospective bidders pause.

Started as a design for Pan American, designated Lockheed Model 89, the plane project was adopted by the Navy when problem of logistics in the Pacific resulted in a 1943 contract for 50 of the planes at a cost to the government of $111 million.

A VJ-Day cutback reduced this contract to two planes, and $27 million.

▶ **Pan Am Cancelled**—Five months before the first Constitution made its first flight in Nov. 1946, cancellation of conditional contracts for the big plane were announced by Pan Am and American Overseas Airlines. (Aviation News, June 24, 1946.)

At that time Lockheed expected the airlines to show renewed interest in a turbine-propeller powered version of the Constitution Model 189, which was then being developed. This development was later shelved.

▶ **6 Months Minimum**—CAA engineers estimate that certification of the big Constitution will take a minimum of six months and perhaps as much as a year, before the planes could go into commercial operation. While accurate estimates of certification costs are not available it is probable it would amount to at least as much as the certification cost for the Boeing Stratocruiser, reported at around $1 million.

In the Constitution's favor was the attempt of Pan Am and Lockheed to get the 156-ft.-long transport certificated as it was built by the Navy. CAA engineers supervised much of the construction of the plane, and consider it meets structural requirements of that time rather completely. It was designed to the old CAR 80 mph. maximum landing speed requirement, but later dropped to accommodate the Boeing Stratocruiser. But the Navy did not approve a full certification program. New CAB and CAA technical requirements which have been put on the books since, including such things as new fire protection provisions, will still have to be met, and the plane will have to be flight tested under CAA requirements.

▶ **14,000 Hp.**—The first Navy plane designed and built for its transport specification, the Constitution is powered with four Pratt & Whitney Wasp Major R-4360 engines rated at 3500 hp. each.

In addition it is equipped with six JATO units installed in the wings, which will give an added takeoff boost of 6000 thrust lb. for 15 sec. and cut takeoff run 25 percent. Navy used the JATO units as standard operating procedure in its takeoffs on the transcontinental run, but whether they would be allowed yet in commercial operation is another problem the successful lessor would have to solve. No other commercial airline JATO takeoffs have been approved.

▶ **Biggest Operating**—Biggest transport which has been regularly operated anywhere, the Constitution has a 189-ft. wingspan, and its single tailfin is 50 ft. 4½ in. high. Fuselage is a figure eight design with upper and lower compartments in equal diameters.

Decision to lease the planes by the Navy came after the economy program of Defense Secretary Johnson took them out of service, but not until the Navy had piled up valuable transport operational experience in hauling personnel and cargo with them. One example of this was a flight in which two AVIATION WEEK editors participated, last spring, when the Constitution carried the largest number of persons ever carried on a transcontinental flight in one plane from Moffett Field, Calif., to Washington National Airport, with a stop at Olathe. This flight carried 118 persons.

▶ **At Least 200**—Upper deck in the Navy passenger version is fitted to accommodate 92 passengers, while the lower deck alternately used for cargo, can be fitted to accommodate 76 more persons. However, under a high density seating arrangement it would be a simple modification to seat at least 200 in the plane without undue discomfort to the passengers.

Main drawback of the plane from an operational standpoint is that it is underpowered in comparison with smaller and speedier competitors which carry much smaller gross weight with the same four Wasp Major powerplants on the Constitution.

▶ **Performance Report** — Performance data quoted for the Constitution with its present powerplants includes 260 mph. cruising speed at 25,000 ft.; 78 mph. stalling speed; 303 mph. top speed; rate of climb of 700 ft./min. at normal gross; ceiling of 28,600 ft.; normal range of 5390 mi. and maximum range of 6700 mi.

In the transcontinental flight previously referred to, the Constitution actually cruised at slightly over 200 mph. at about 19,000 ft. with little aid or hindrance from the winds aloft.

▶ **Turbo-Prop Version**—Lockheed reported at the time it was discussing a turbine-propeller powered version, that such a plane would cruise at around 350 mph. with a top speed around 400 mph.

Presumably the plane could be fitted with four of the 5500 hp. Allison T-40 gas turbines with propellers, and get somewhere near that speed with such an installation, with relatively minor change in range.

Whether a lessor would want to undertake such a major powerplant change, without getting full title to the airplane, or whether it would be profitable, even so, to make the change for only two airplanes appears doubtful, particularly when the additional certification delays which would be involved are considered.

RADICAL FEATURES in helicopter design are shown in H-19: Clamshell doors for engine accessibility; large cabin below flight deck.

Sikorsky's Double-Deck Helicopter

New H-19, entrant in USAF rescue competition, has large cargo or passenger compartment below cockpit.

Sikorsky's entry in the USAF air rescue helicopter competition, the new H-19, was disclosed last week as a box-shaped utilitarian craft resembling the equally utilitarian fuselage of the Fairchild C-82 Packet, with a similar upper flight deck for the crew, and a large cargo compartment below.

With orders for five of the helicopters already received in a recent USAF procurement switch, Sikorsky expects to make its first military delivery in February. CAA certification is being pushed along with the military production work with hopes to get the new aircraft certificated as the commercial S-55, and possibly in trial operation early next summer.

▶ **Small Package**—Most surprising thing about the new H-19 is the smallness of the complete package in comparison to its capacity. Actually the rotor diameter is only 53 ft., 4 ft. greater than that of the H-5H Sikorsky; the length is 41 ft. 8½ in., only 2 ft. 2½ in. longer than the H-5H, and the overall height, 14 ft. 8 in. is only 2 ft. 4 in. greater.

The aircraft has a normal gross weight of approximately 7000 lb. and a military useful load of approximately 2800 lb.

The H-19's main compartment, for cargo or passengers, provides a box-shaped clear space 6 ft. high, 5 ft. 6 in. wide and 10 ft. long. In this, the Sikorsky designers find room for eight litters and one attendant, or 10 passengers plus crew of two on the flight deck. As a contrast, the slightly smaller H-5H space for only three litters or three passengers.

▶ **Move Engine**—The larger cabin was made possible by locating the 600 hp. Pratt & Whitney R-1340 radial engine in the nose of the aircraft, instead of behind the cabin, as in previous Sikorsky models. The new location makes it possible to use clam-shell doors around the engine compartment, giving unusual accessibility to the powerplant for maintenance and powerplant change if necessary. Sikorsky representatives estimate that a complete powerplant change including fan could be made in approximately 2 hr.

Prototype which made its first real flight Nov. 21, has been logging time in tiedown tests in a 10 percent overload condition and flights for sometime, to build up a total of about 70 hr.

▶ **Power Hoist**—Designed specifically for rescue work, the H-19 has a power hoist, which will permit it to make rescues while hovering in midair. Entrance in the main cabin or cargo compartment is through a door 4 ft. square.

As a commercial version it is believed the cabin could accommodate 12 persons. It is designed for 3 hr. range with 10 passengers, cruising at approximately 100 mph., in the 600 hp. version.

Like two other competitors in the new USAF rescue competition, Sikorsky has submitted an alternate proposal to fit an 800 hp. engine in the aircraft if desired. The H-19 has been engineered with such a change in mind, and would not need major modifications structurally to accommodate the bigger powerplant.

Radar Net Funds Allotted by USAF

Immediate construction of an aircraft warning network of radar stations across Alaska and continental U. S. will be started using $50 million allotted by the USAF, at the expense of cancelling or reducing other USAF projects in this amount, in the fiscal 1950 program.

Overall expenditure of $85.5 million for construction of the network has been approved by Congress of which not more than $50 million was authorized for fiscal 1950.

$31.2 million of the first year's total will be expended on the Alaskan stations in the aircraft control and warning chain, with the remainder to be used for facilities within the U. S. Most of the sites for stations in the net have already been chosen with rights of entry, property leases and construction plans completed.

Lt. Gen. E. C. Whitehead, commanding general of Continental Air Command, Mitchel Field, N. Y., and Brig. Gen. Frank A. Armstrong, Jr., commanding general of Alaskan Air Command, are in charge of the two segments of the network installation.

Existing World War II radar equipment which will be adapted to the network installation is valued at $42,250,000. Another $26 million will be needed for electronic equipment developed since the war, and $7 million is estimated as the cost of maintaining picket ships as part of the network.

The completed network, if funds are made available, will include two types of radar defense: a "two-notch" screen

with 300 mi. range around certain areas, and a 150 mi. range "one-notch" screen around other areas.

An Air Force spokesman said that the $50 million for the network had been taken from the 1950 schedule by an "across-the-board" cut on virtually every other USAF project, exempting only aircraft schedules and research and development funds.



ON GROUND, National Research Council glider shows off smooth construction . . .

IN FLIGHT craft reveals sweptback outer wing panels and unique separate cockpits.

Canada Testing Tailless Glider

Flight characteristics of all-wing configuration being evaluated by using heavily instrumented craft.

The Canadian government is conducting an extensive flight testing program with a tailless glider to gain more information on stability, control and general flight characteristics of tailless type aircraft.

Designed and built by the National Research Council, experiments with the glider are carried out jointly by NRC and the Winter Experimental Establishment of the Royal Canadian Air Force at Edmonton, Alberta, and Arnprior, Ontario.

▶ **Characteristics**—With a U-type planform and separate side-by-side cockpits for a pilot and engineer-observer, the craft has a 46-ft. wingspan and a length of about 18 ft. Maximum weight is 4150 lb., giving a wing loading of 10 lb./sq. ft. The glider is made entirely of wood and is said to have a remarkably smooth skin surface. Skin is relatively thick, molded plywood, and conventional ribs are used with a single laminated spar.

Fins and rudder combination is fitted to each wing tip. "Elevons"—combined elevators and ailerons—are utilized. An interesting feature is the movable wing tips, rotated by means of a jack, to provide a nose-up movement of the glider. The craft has conventional split flaps, and differential brakes. It also is equipped with retractable tricycle landing gear and, in addition, has retractable skids for emergency landings.

▶ **Heavily Instrumented**—The glider carries several hundred pounds of instrument, batteries and related equipment. It is provided with automatic recording cameras to photograph such data as time, airspeed, tip angle, flap angle, rate of yaw, controller hinge movements, rudder angle, outside temperature, etc.

The ground handling and flying characteristics of the craft are reported to be very good. Taxiing is said to be easy and takeoffs have been made at speeds of 70-90 mph. with ground runs ranging from 2600 to 3150 ft.

A 350 ft. nylon rope is used for towing by an RCAF Dakota with towing speeds ranging from 100 to 140 mph. In free flight, the glider has flown at speeds ranging from 55 to 150 mph. with the center of gravity at 50-55 percent of the center section chord.

Normally, the craft is carried to 6000-12,000 ft. altitude and then released for free flight. When it drops to 4000 ft., all testing is discontinued to prepare the craft for landing. Approach speed is about 85 mph. and normal landing speed is 60 mph. Landing approach is said to be simple and straightforward and spot landings can be made with errors of less than 200 ft.

Navy Cutback Hits Attack Planes

Navy recently reduced its combat air strength by 20 percent.

The cut was occasioned by fiscal 1950 budget cuts and budgetary planning for fiscal 1951 which will further reduce the size of the Naval air establishment.

Navy will decommission 470 out of a total strength of 2258 combat planes and eliminate four attack groups; five patrol squadrons and seven Marine fighter squadrons. Navy currently has a total air strength of about 7000 planes of all types including those in storage.

Meanwhile prospects looked dim for shifting elsewhere the major portion of a $203 million cut scheduled for Naval aircraft procurement's fiscal 1950 budget. Defense Secretary Louis Johnson indicated that part of the cut might be allocated elsewhere in the Navy but latest reports from the Pentagon indicate that the cuts will stand as ordered by the Navy. Bulk of the cut will be applied to new attack planes including the North American AJ-1, the Douglas AD series and the Grumman AF series. Navy is now scheduled to operate only eight large attack carriers in fiscal 1951.

Most 377s Completed

All but five 377 Stratocruisers have been completed of a 55-plane order, and employment at Seattle, Wash., plants of the Boeing Airplane Co. has dropped to 20,048 from a peak of about 26,000. The "decline will continue until new orders are received," the company has announced.

Last of the five Stratocruisers is scheduled to be out of the plant before Christmas, although some work still will remain to be done on the field before delivery. Pan American World Airways now has 19 of its 20 planes, Northwest 9 of 10 and American Overseas 7 of 8. Forty planes have been delivered and ten are still on the field.

FINANCIAL

Airline Dividends Seen Increasing

While only small lines paying on common this year, better earnings point to wider distribution in 1950.

The recent action of Mid-Continent Airlines in paying a second 25-cent-per-share dividend on its common stock this year points up the curious circumstance of disbursements on junior equities during 1949 being confined to a few of the smaller airlines. The "Big Four" and most of the secondary grouping of domestic airlines refrained from paying any dividends on their common stock. This pattern is the opposite of that prevailing in previous years and presents an interesting phenomena.

Nevertheless, in view of the sharp reversal of earnings evident for 1949, and with 1950 auguring well for further rehabilitation of finances for many carriers, the resumption of dividend payments next year by an increasing number of airlines appears likely.

► **Consistent Earnings**—A relatively small sectional carrier, Mid-Continent has shown an enviable record of earnings in recent years. The company has reported a net profit consistently from 1942 without interruption. While the carrier is highly dependent upon mail pay to maintain profitable operations, reliance from this source has been decreasing throughout the years.

For example, during 1942, 64.2 percent of its total revenues came from mail compensation. For 1948, this ratio was down to 17.5 percent. The company paid the first dividend in its history during 1948, when 25 cents per share was disbursed. During the second quarter of this year, Mid-Continent paid the same dividend. The recent action, bringing total dividend payments to 50 cents per share for the year, was somewhat of a pleasant surprise to holders of the company's outstanding 390,779 shares.

► **Other Dividends**—Earlier this year, Chicago & Southern Air Lines distributed 35 cents per share to its 509,326 capital shares outstanding. This carrier last paid a dividend in 1945 when 25 cents per share was disbursed. Following deficit operations of 1946 and 1947, earnings were restored during 1948 and have continued through 1949. Mail revenues have been an important factor in bolstering C&S's earnings. During 1948, almost 27 percent of the company's combined domestic and international revenues came from mail compensation.

Delta has demonstrated a desire to pay dividends when earnings permitted over a long range of years. Starting with 1938, Delta paid a dividend every year through the end of 1947, with the exception of 1941. In an apparent desire to husband its cash, the company omitted a dividend payment for its fiscal year ended June 30, 1948. However, with a dividend disbursement of 25 cents a share made earlier this year, Delta is once again in the dividend paying column. During 1948, Delta obtained 19.8 percent of its total revenues from mail compensation.

In the aggregate, dividend disbursements for Mid-Continent, Chicago & Southern and Delta amount to less than $450,000 for 1949. Accordingly, for substantial distributions of dividends it will become necessary for the larger airlines to make such disbursements.

► **Eastern's Position**—In many circles, for example, it was believed that Eastern in view of its healthy financial condition and continued good earnings, might be inclined to make a "token" disbursement this year. While action of this type might yet be forthcoming before the 1949 close, such prospects are beginning to fade as time elapses. In this instance a token disbursement of only 25 cents a share would amount to almost $575,000 on Eastern's capitalization, or more than the total distributed by the three smaller carriers mentioned.

American Airlines with its $40 million in 3½ percent preferred stock will have paid $1.4 million in dividends on this issue during 1949, the same as for 1948. American is also likely to resume dividends on its common stock late next year if the present trend of earnings continues.

► **American Advancing** – Significant progress is expected in the over-all American financial picture during 1950. Should the proposed acquisition of American Overseas by Pan American be approved by the CAB, American will receive about $10.8 million for its AOA stock. This will further augment its already mounting cash position and may permit anticipating the retirement of a large block of its outstanding debentures.

The credit of these debentures has been improving rather markedly during this year, with new highs being recorded on successive transactions. In June, 1946, $40 million of these 3 percent debentures were sold by an underwriting syndicate headed by Kidder, Peabody & Co. at a price of 102. A low of 70 was established for this issue during 1949 with recent quotations closer to 94. It is known that more than $30 million of these debentures are held by insurance and fiduciary interests.

Despite substantial losses during 1947 and 1948, American persistently maintained dividend payments on its preferred stock, establishing an unbroken record. It is logical to assume that any retirement of the company's debentures will tend to improve the position of the company's preferred shares and, to a lesser degree the common as well. There are 6,452,835 shares of common stock outstanding for American, the largest number for any company in the industry. A dividend of only 50 cents a share would represent the disbursement of some $3,226,418.

► **UAL Outlook**—United Air Lines has maintained an unbroken dividend record on its approximately 95,000 shares of 4½ percent preferred stock. This disbursement amounts to about $427,500 annually and continued payments in the face of temporary deficits has done much to improve the standing of this issue at the present time. As United continues to retire its outstanding debt and maintain its present trend of earnings, resumption of dividends on its common stock is possible during 1950. The company has more than 2 million shares of common stock outstanding.

Northwest Airlines with its 390,000 shares of 4.6 percent preference stock issued at $25 per share in April, 1947, has managed to maintain an unbroken record of dividend payments on this senior equity. With a $21 million loan, of which $12 million is guaranteed by the Reconstruction Finance Corp., resumption of dividend payments on the common stock appears unlikely for 1950. Permission of the RFC would be necessary for this action and this may not be forthcoming until a material reduction in debt is accomplished.

TWA has been demonstrating a remarkable recovery in earnings during 1949 with further improvement indicated for 1950. While the company has a heavy debt structure, rapid progress is being achieved in its reduction. It is known that one of President Ralph Damon's objectives is to place the company's common stock on a dividend paying basis as soon as financial and earnings conditions permit.

Regularity of dividend payments on airline common stocks will represent one manifestation of the industry's losing much of its speculative character and assuming greater stability.

—**Selig Altschul**

SALES & SERVICE

EXHAUST SILENCER under fuselage of Chrislea Skyjeep, British export lightplane.

British Bid in Lightplane Market

New "family-size" craft powered by 155-hp. engine is priced at about $5600 and aimed at export field.

A 155-hp. Chrislea Skyjeep, designed to carry four adults plus two children, or to serve as an ambulance or light cargo plane, has made its first test flights at Exeter Airport, and is being aimed by its British manufacturer at the export market in competition with American lightplanes.

Developed from the Chrislea Ace (AVIATION NEWS, May 20, 1946) the new plane is priced at "just over 2000 pounds" (about $5600) and has already been subject of inquiries reported from Australia, New Zealand and South America, where its principal markets are expected to be found.

▶**First Flight**—The Skyjeep was first shown at the recent Farnborough show of the Society of British Aircraft Constructors, prior to flight late in November. It is described by the manufacturer as the civil counterpart of its military kinsman, the Chrislea Series 3 ambulance aircraft.

The plane is an example of a return to more conventional engineering by a manufacturer, after a failure of the consumer to accept some of the interesting and apparently attractive innovations designed into the original Chrislea Ace.

▶**Conventional Gear**—Most obvious of the changes is the use of a conventional tailwheel landing gear, replacing the tricycle gear used by the Ace. The new undercarriage is designed for quick installation of Goodyear cross-wind swiveling wheels, but presumably crosswind gear could have been used also with the tricycle gear, if this had been desired.

Conventional dual stick and rudder controls are replacements for the wheel controls of the earlier plane. Original control of the Ace involved a three-way movement of the wheel control without rudder pedals. Ailerons were operated by turning the wheel, movement of control column to right or left actuated the rudder, and vertical movement of control column actuated elevators. Later the company added rudder pedals, after British pilots did not accept the unconventional control.

▶**Engine Change**—Single wing struts are used on the new version. From the 100-hp. engine originally planned for the Ace, the powerplants have been increased to the present engine, a Cirrus Major III, which provides 155 hp. at takeoff. Presumably American importers might import the airframe and install an American engine of similar dimensions and power, as has been suggested in other import proposals of foreign aircraft.

Although the Skyjeep has not completed its flight tests the following performance estimates under sea level conditions have been supplied by the manufacturer:

▶**Performance**—Maximum level speed, 130 mph.; cruising speed (2200 rpm.) 110 mph.; stalling speed with flaps 54 mph.; rate of climb (2500 lb. gross) 600 ft./min.; takeoff distance with 5-mi. wind, 150 yd.; landing run to rest, same condition, braked, 130 yd.; service ceiling, 14,000 ft.; range in still air, 530 mi.

▶**Specifications**—Span, 36 ft.; length, 21 ft. 6 in.; height, 7 ft. 3 in.; track, 6 ft. 3 in.; empty weight, including radio, starter, generator, battery, navigation lights, landing light, cockpit lights, wiring and full instruments, 1540 lb.; full gross weight, 2500 lb.; fuel capacity 39 gal. (carried in two "crash-proof" flexible cells in wingroots).

▶**Modifications**—Other modifications listed by the company from the earlier model include: Friese type ailerons; increased rudder area; enlarged cabin with seats moved rearward for more leg room and front seats adjustable; redesigned panel; exhaust silencer discharging aft of cabin, reducing cabin noise; hinged-top fuselage decking aft of cabin for stretcher or bulky freight; enlarged luggage compartment with 100 lb. capacity, useable alternately for two small children.

BRIEFING FOR DEALERS AND DISTRIBUTORS

▶**ADMA OFFICERS**—G. B. Van Dusen, president of Van Dusen Aircraft Supplies, Inc., Minneapolis, was elected president of the Aviation Distributors and Manufacturers Assn. at the recent French Lick, Ind., meeting, succeeding Richard Bomberger, vice president, Sensenich Corp., Lancaster, Pa. Vice presidents elected were: R. W. Richardson, aviation sales manager, Goodyear Tire & Rubber Co., Akron, for manufacturers, and George W. Jalonick, III, Southwest Airmotive Co., Dallas, for distributors.

Elected to board of directors were: John D. Harris, Pacific Airmotive Corp., Burbank; Frederick H. Lee Jr., R. M. Hollingshead Corp., Camden, N. J.; Arthur C. Harvey, Air Parts, Inc., Glendale, Calif.; A. E. R. Peterka, Lamson & Sessions Co., Cleveland; and Tom H. Davis, Piedmont Aviation, Inc., Winston-Salem, N. C.

▶**PROTEST BERGIN OUSTER**—Notwithstanding protests by Utah aviation leaders against the removal of Joe Bergin, as Utah Aeronautics Director after approximately 10 years in the post, the State Aeronautics Commission intends to see to it that the removal sticks.

O. H. Whittenburg, chairman of the commission, told delegates from approximately 20 aviation groups including operators and Flying Farmers, that he was responsible for relieving Bergin of his duties and for appointing Frank R. Murray, former airline employe, as his successor. Gov. J. B. Lee said he would not interfere in the matter.

Percent Electric Tachometers



Starters

Gravimetric Fuel Flow Totalizing Systems



Air Turbine Driven After-burner Fuel Pumps



Fuel Booster Pumps



Lubrication Pumps



Engine Control Equipment
Air Pumps
Engine Starting Equipment
Hydraulic Equipment
Ice Elimination Equipment
Power Supply Generating Equipment
Power Supply Regulating Equipment

★

Automatic Pilots
Flight Path Control Systems
Engine Instruments
Flight Instruments
Navigation Instruments

In the JET FIELD, Too—

FINE INSTRUMENTS AND ACCESSORIES MAINTAINING A TRADITION OF LEADERSHIP!

In the story of American aviation is the story of Eclipse-Pioneer. For that name has been synonymous with the growth and development of aviation in the highly specialized field of precision aircraft instruments and accessories for more than three decades. Now, that heritage of experience is proving itself in the field of jet aircraft. For today at Eclipse-Pioneer, development and production of instruments and accessories to meet the singular requirements of jet aircraft include such vital components as: Complete Fuel Control Systems • Gravimetric Fuel Flow Totalizing Systems • Engine Starting Equipment • Booster Coils • High Speed Generators • Lubrication Pumps • Fuel Booster Pumps • Air Turbine Driven After-burner Fuel Pumps • Autosyn* and Magnesyn* Fuel Pressure and Oil Pressure Indicating Systems • Electric Tachometer Systems. Detailed information about these components is available on request from responsible organizations.

*REGISTERED TRADE MARK OF THE BENDIX AVIATION CORPORATION

ECLIPSE-PIONEER A DIVISION OF
TETERBORO, NEW JERSEY

Bendix
AVIATION CORPORATION

Export Sales: Bendix International Division, 72 Fifth Avenue, New York 11, New York

Racing Man's Imagination to the Moon



No, the scene above isn't from a comic strip. More likely, it might be the illustration from a Pesco ad of 19XX . . . you insert your own guess as to the exact date.

Fantastic? No! The only thing that approaches the fantastic aviation-wise is the tremendous progress the industry is making. In a few short years, speeds surpassing sound and almost unbelievable heights have been reached.

Aviation's engineers and scientists have been hard put to keep pace with man's space-conquest imagination. But they are doing it. And since Pesco manufactured its first hydraulic pump 16 years ago, our engineers have worked side by side with aircraft engineers helping to create many of the vital accessories for jet and reciprocating engines and aircraft that are making faster speeds and greater heights attainable.

Reach the moon . . . reach other planets? It may not be long now!

Pesco PRODUCTS DIVISION
BORG-WARNER CORPORATION
11610 Euclid Ave. — Cleveland 6, Ohio

What Does Rain Do To Radar?

Theoretical calculations in problem of interference are supported by scattered test data. Noise level a factor.

By Robert McLarren

It has long been known that radar pulses can be reflected by raindrops, heavy fog, clouds, etc. and it is this fact that has permitted a rapid growth in the use of radar for storm detection. When used for this purpose, the attentuation of pulse radiation by moisture condensation is a beneficial characteristic that is proving of increasing value to aircraft navigation.

However, this characteristic is wholly undesirable in radars used for aircraft detection, such as in search, ground control approach, and identifications. Hence, it is important to examine the degree of attentuation of the radar signal by rain and to examine factors permitting reduction of such interference.

▶ **Data Required**—Numerous attempts have been made to measure the attenuation of radar signals by rainfall but most have not proved successful, because of insufficient rainfall, other than to provide data on the particular conditions examined. For such data to be useful they must include the widest possible range of conditions.

For example, information is needed on highly localized conditions, such as rainfall in the immediate vicinity of an airport utilizing GCA equipment. Data are needed on rainfall in the vicinity of the target, although the weather may be clear at the radar unit. Between these two extremes, data are needed on the effects of rainfall between the radar and the target, either a localized condition or a continuous rainfall across the intervening distance.

Theoretical considerations of the effect of rain and fog on the propagation of wave lengths below 10cm. are reported as early as 1930.[1] One of the early experimental tests of these theories in 1935 indicated that atmospheric attenuation of 9cm. waves over a line-of-sight distance of 16 mi. was negligible.[2] These tests revealed an attenuation of less than 0.1 decibel per mile in a heavy rain of cloudburst proportions.

▶ **Investigations**—Since theoretical studies indicate increasing attenuation with decreasing wave lengths, experimental tests using wave lengths in the 1cm. and 3cm. region were desirable and such trials were undertaken early in 1942 by scientists of the Bell Telephone Laboratories.[3] Although the tests were comparatively crude, they furnished the first useful experimental results in investigation of the problem. Two paths were used for the study—the 1.09cm. wavelength tests were made over a distance of 1260 ft., the 3.2cm. tests over a path of 900 ft.

The 1.09cm. equipment consisted of a CW generator feeding an electromagnetic horn radiator mounted 4½ ft. above the ground. A similar horn, mounted 21 ft. above the ground at the other end of the 1260-ft. path, supplied a double-detection receiver.

The 3.2cm. equipment utilized a CW signal generator supplying a 30-in. parabolic reflector through an open-end wave guide horn placed at the focus. The reflector was mounted 35 ft. above the ground. The receiver, 900 ft. away, was fed from an electromagnetic horn mounted 21 ft. above the ground.

Rainfall was measured at only one point, however, at one-minute intervals. Two heavy rainfalls were measured in this manner.

These early tests indicated that attenuation of the 3.2cm. signal was at the rate of approximately 0.05 db./mi./mm./hr., using Humphrey's[4] rainfall classification system.

The 1.09cm. signal was attenuated at the rate of approximately 0.3 db./mi./mm./hr.

▶ **Navy Participates**—The U. S. Navy Electronics Laboratory, San Diego, Calif., took an early active interest in this problem and sought to refine the data obtained previously.[5] The fluctuations in rainfall intensity with time and distance impairs much of the usefulness of results obtained over short path distances and using a single or only a few rainfall recording points.



After surveying numerous locales, it was decided to conduct the Navy tests near Hilo, Hawaii, which has an annual rainfall of more than 250 in. In these tests, 9 rain gages were installed along a 6400-ft. path. Readings were taken every 30 sec. and this time interval was correlated to ±2 sec. by a field telephone network.

The tests were conducted using 1.25cm. radiation. The transmitting 24-in. paraboloid was fed from a klystron tube modulated at 800 cps. Peak power output was about 50 milliwatts. The receiver was fed from a 24-in. paraboloid and used a superheterodyne with a klystron local oscillator driving a 30mc. IF amplifier.

Receiver calibration was provided before, during, and after rainfall using a klystron signal generator with two flap attenuators. The signal was fed to the dish through a small nozzle.

▶ **Results**—The accompanying graph shows the results of the tests and is a plot of signal attenuation in decibels per mile against millimeters of rainfall per hour. The curve has a mean slope of approximately 0.37 db./mi./mm./hr. Slope varies from about 0.50 at low intensities to 0.35 at high intensities.

These experimental data indicate much higher attenuation than that derived by J. W. Ryde on the basis of theoretical calculations.[6] Ryde obtained an attenuation of 0.25 db./mi./mm./hr.

There are numerous possible reasons for the discrepancy between the two figures but since the tests were obtained at only 30-sec. intervals and over 700-ft. distances, it can be assumed that the fluctuations in rainfall intensity were not adequately covered.

Application of these test data to operational equipment indicates that with moderate rainfall (5mm./hr.) over a 100-mi. path, the radiated power would have to be increased by 10^{20}, or 200 decibels to provide the same power received in clear weather.

▶ **CAA's Method**—A different approach was taken by the Civil Aeronautics Administration at its Indianapolis experiment station.[7] Tests were designed to evaluate the performance of S-band (3000mc.) and L-band (1300mc.) radars used to detect the presence of aircraft flying through rain or cloud formations. The trials were conducted to determine quantitatively the ratio of the received signals from aircraft to those from clouds or rain for each of the two frequencies. These tests, therefore, might be considered the reverse approach to those previously described.

The S-band radar was an AN/GPN-2 unit operating with a pulse rate of 2000 on a frequency of 1290mc. L-band radar was an AN/CPS-5 unit operating with a pulse rate of 2000 on a fre-


The Odds Are...
They Use PACIFIC-WESTERN
GEAR ENGINEERING
Virtually all manufacturers of commercial and military aircraft use Pacific-Western engineering or production services

A NATIONAL HEADQUARTERS Through the years, the Pacific-Western plants have become a national headquarters for designing and producing precision-quality aircraft mechanisms.

GEAR ENGINEERING What is the *minimum* weight for the *output* and *life* required? What type of gearing, switches, clutches, etc. will give the *exact* characteristics required of an assembly? These are the kinds of questions that Pacific-Western gear engineers work with daily. Their experience is at your service.

...THEN GEAR CUTTING Where can this type of gear be cut? Who can generate a tooth like this? How can a shape like that be machined? The answer is straightforward: bring your production problems to the Pacific-Western plants, where every known type of gear is produced—where design is not restricted by limited facilities.

CATALOGS AVAILABLE

For additional information, send for Aircraft Actuator Catalog 4811 and Aircraft Equipment Bulletin 4801.

ENGINEERING AND SERVICE FACILITIES IN PRINCIPAL CITIES:
Seattle 4, Washington; 417 9th Ave. S.
Portland 14, Oregon; 930 S. E. Oak St.
San Francisco 3, California; 1035 Folsom St.
Lynwood, California; Box 192
Houston 3, Texas; 117 North Palmer
Salt Lake City, Utah; P. O. Box 1251
Wilmington 99, Delaware; P. O. Box 1871

PACIFIC GEAR & TOOL WORKS ⚙ WESTERN GEAR WORKS

AGMA MEMBER

PACIFIC-WESTERN 4912

GEAR PRODUCTS

quency of 2990mc. Both units required modification so that they would have the same characteristics and differed only in the frequency of the transmitted signal.

Design and construction of antennas for both units having identical patterns were not undertaken because of time and cost involved. As an alternative, the target aircraft was flown into and around cloud formations as carefully as possible to keep within the vertical radiation patterns of the antennas.

▶ **CAA Findings**—Results of 15 separate flights by a Douglas DC-3 show an average improvement in signal strength of 11.7db. by use of the lower frequency band. (Four readings showing less than 10 db. improvement are believed to be due to errors in training the antennas directly on the target.)

The CAA concluded, on the basis of these results, that almost all cloud formations of sufficient density to be visible on the 1300mc. radar scope will completely mask out all targets when viewed on the 3000mc. scope. It was found that extremely heavy rain caused masking of the first 15 to 20 mi. of range on the L-band PPI presentation.

It follows that rain attenuation of microwaves has serious consequences when transmitted wavelengths are extremely small, rainfall is very heavy, or the target is either flying in heavy rain or cloud or is separated from the source by such moisture concentrations. Under this combination of conditions, the received signal strength (as a ratio of target to rain signal strength) can be quite low.

▶ **Detection**—Ability to detect low signal strength is obviously a prime requisite of radar equipment. Unfortunately, radar sensitivity cannot be measured in terms of antenna gain alone. If this were true, then receiver sensitivity would increase with frequency, since greater antenna gains can be realized at very short wavelengths.

Fundamental limit on the size of the weakest echo which can be detected is set by receiver output noise, which originates, for the most part, within the receiver itself. This noise is created by random voltage or current fluctuations, which tremendous research and development cannot eliminate. Basic problem is that many noise sources are amplified automatically as the received signal is amplified.

Among noise sources are those created by the random motion of molecules, atoms and free charges in a resistor; fluctuations in an electron emission, and antenna radiation resistance.

Noise level of a radar receiver may be calculated by this relationship:

$$F = \frac{P_n}{kT\Delta f}$$

in which F is noise figure; P_n, amount

Redesign with TRUARC cuts unit cost 42¢ saves 7½ minutes assembly time



SCREW AND WASHER HOLD FLOATING GEAR IN PLACE in old model newspaper facsimile recorder. Gear stud may rotate at pivoted end, making removal of screw difficult. Screw head takes up valuable space.



TRUARC RING REPLACES SCREW AND WASHER in this typical application. Truarc Ring saves space, makes assembly-disassembly quicker and easier No screw slots to get burred up.



Not only do 22 Truarc Rings save time and money in production for Times Facsimile Corporation, New York. They also make maintenance easier and faster—a basic advantage in a machine on duty 24 hours a day.

Redesign with Truarc Rings and you too will save! Wherever you use machined shoulders, nuts, bolts, screws, snap rings, cotter pins, there's a Truarc Ring that does a better job of holding parts together.

Find out what Truarc Rings can do for you. Send your blueprints to Waldes Truarc engineers for individual attention without obligation.

22 WALDES TRUARC RINGS GIVE THESE BIG ADVANTAGES:

- **½ inch space saving permits money-saving use of standard relay rack.**
- **7½ minutes assembly time saving.**
- **42¢ overall unit cost saving.**
- **Replace tapping with simple grooving operation.**
- **Speed maintenance because Truarc Rings are easy to assemble and disassemble... can be used over and over again.**



WALDES

TRUARC

REG. U. S. PAT. OFF.

RETAINING RINGS

WALDES KOHINOOR, INC., LONG ISLAND CITY 1, NEW YORK

WALDES TRUARC RETAINING RINGS ARE PROTECTED BY U. S. PATS. 2,382,948; 2,416,852; 2,420,921; 2,411,761 AND OTHER PATS. PEND.

Waldes Kohinoor, Inc., 47-16 Austel Place AW-12
Long Island City 1, N. Y.

Please send 28-page Data Book on Waldes Truarc Retaining Rings.

Name_____

Title_____

Company_____

Business Address_____

City_____ Zone____ State_____ ★

of noise power: k, 1.38 x 10^{-23} joules per degree Kelvin; T, temperature of resistor in degrees Kelvin; and Δf, bandwidth in cps.[8] Value P_n is the amount of noise power which, if applied at the receiver input, would give the actual noise in the output with no other source of noise present. Value F is usually expressed in decibels so that the number of decibels above $kT\Delta f$ is a good index to the receiver noise of a radar set.

▶ **Set Levels**—As an indication of the noise level of typical radar sets, the following are values of noise in decibels above $kT\Delta f$ for several units.[9]: AN/APS-10 (airborne search), 15; AN/APS-15 (airborne search), 18; AN/APG-5 (turret ranging), 13; SCR-717 (airborne surface search), 11-15; SCR-720 (air search), 11-15; and AN/APQ-7 (blind bombing), 15.

Obviously, as the power of the received signal falls to the vicinity of these values, a PPI or other presentation will become completely masked by the receiver noise and no usable signal presented. Degree to which the received signal remains recognizable depends greatly on the aptitude of the individual observer.

Therefore, it is not a question of whether rain or cloud fully attenuates a radar signal but whether such attenuation reduces the signal to the near-vicinity of the noise level of the receiver.

One solution to the problem lies in the fact that the receiver bandwidth is a rough measure of the range of frequencies amplified by the receiver, which, in turn, is a measure of the noise level of the receiver.

It would follow that reductions in bandwidth would permit reductions in noise level and, therefore, increased sensitivity to signals which are attenuated by rain.

Unfortunately, however, quality of reproduction decreases with decrease in bandwidth. Hence, the radar engineer is forced to compromise the conflicting requirements for high quality and low noise reception, to produce the most sensitive receiver.

References

1. Stratton, J. A.: Effect of Rain and Fog on the Propagation of Very Short Radio Waves. Proc. I.R.E., June, 1930.
2. Wolf, Irving and Linder, E. G.: Transmission of 9-centimeter Electromagnetic Waves. Broadcast News, December, 1935.
3. Robertson, Sloan D. and King, Archie P.: Effect of Rain upon the Propagation of Waves in the 1- and 3-Centimeter Regions. 2 Proc. I.R.E., April, 1946.
4. Humphrey, W. J.: Physics of the Air. McGraw-Hill Book Co., New York, N. Y., 1940.
5. Anderson, Lloyd J.; Day, John P.; Freres, Clemens H. and Stokes, Alfred P. D.: Attenuation of 1.25-Centimeter Radiation Through Rain. Proc. I.R.E., April, 1947.
6. Ryde, J. W.: Paper presented before Institution of Electrical Engineers Radiolocation Convention, London, March, 1946.
7. Randall, A. W.; Trout, C. C.; Herrmann, J. E. and Leake, Paul H.: Performance of S-Band and L-Band Surveillance Radars During Rain and Cloud Conditions. CAA Technical Development Report No. 92, April, 1949.
8. Staff, MIT Radar School: Principles of Radar. McGraw-Hill Book Co., New York, N. Y., 1946.
9. Airborne Radar Specifications. Electronics, February, 1947.

THESE

Aircraft Quality

U·S·S CARILLOY ALLOY STEELS

ARE NOW AVAILABLE FOR

immediate shipment:

4130—Rounds, flats, squares and hexagons to AN-QQ-S 684a as amended.

4130—Sheets and plates to AN-QQ-S 685 as amended.

4140—Rounds, flats and hexagons to AN-QQ-S 752a as amended.

4340—Rounds and flats to AN-QQ-S 756a as amended.

UNITED STATES STEEL SUPPLY COMPANY · USS · STEELS · SERVICE

Symbol of Service for Steel Users

● Now, from our conveniently located warehouses—coast-to-coast—you can get quick action on your orders for *Aircraft Quality* U·S·S Carilloy Alloy Steels. And when you place your order, you're sure of getting steels that measure up to the exacting requirements of your specifications for aircraft construction. For special care is given to every phase of manufacture. Carilloy Alloy Steels undergo very stringent examinations to prove their fitness for airplane parts, engines and accessories.

Telephone, wire or write our nearest warehouse or sales office for quick deliveries of *Aircraft Quality* U·S·S Carilloy Alloy Steels.

UNITED STATES STEEL SUPPLY COMPANY

USS

Warehouses: BALTIMORE · BOSTON · CHICAGO
CLEVELAND · LOS ANGELES · MILWAUKEE · MOLINE, ILL. · NEWARK · PITTSBURGH
PORTLAND, ORE. · SAN FRANCISCO · SEATTLE · ST. LOUIS · TWIN CITY (ST. PAUL)
Also Sales Offices at: KANSAS CITY, MO. · PHILADELPHIA · TOLEDO · TULSA · YOUNGSTOWN
Headquarters Offices: 208 S. La Salle St.—Chicago 4, Ill.

UNITED STATES STEEL

Position Indicators Announced by G E

Two new-type, d.c. selsyn instruments for indicating position of wheels, flaps, trim tabs, cowl flaps, and other airplane components, are announced by General Electric Co., Schenectady, N. Y.

Designed to latest Air Force and Navy specifications, both instrument models are hermetically sealed and one incorporates an adjustable scale plate. Model 8DJ51GAB landing gear position indicator has been developed to replace position lights now used in many aircraft. By changing scale plate, this device can be used for other switch-controlled indications when on-off function is desired.

Model 8DJ48AAD, a round-case instrument, indicates flap position regardless of degree of travel and can be modified for trim tabs and cowl tabs.

How Chromium Plate Affects Fatigue Limit

Studies at NBS yield information on steels used in aircraft. Factors of plate thickness, heating evaluated.

New data on the effect of chromium plating on the fatigue limit of aircraft steels are now available as a result of an extensive study conducted recently at the National Bureau of Standards by Hugh L. Logan.

In this investigation, sponsored by the Navy Bureau of Aeronautics, specimens about ¼-in. in diameter were machined from three lots of SAE X4130 rod and one lot of 6130 rod, whose compositions are shown in accompanying table. The X4130 steel was either normalized to a Rockwell hardness of 90-B or quenched and tempered to a hardness of about Rockwell 40-C, while the 6130 stock was quenched and tempered to a Rockwell hardness of 33-C.

After grinding, polishing, and chromium-plating, the specimens were subjected to fatigue tests in an R. R. Moore type of rotating-beam machine operating at 1800 or 3600 rpm. Eight or 10 specimens usually were required to obtain the fatigue limit for any one set of conditions.

► **General Relationships**—In all cases, chromium plating was found to reduce the fatigue limits of the steels studied, although the effect was less pronounced under some conditions than others.

In general, the reduction in fatigue limit increased with increased hardness of the steels. For material of a given hardness, the fatigue limit decreased with increased temperature of the plating bath.

While plate thickness appeared to have little effect on the fatigue limit of specimens plated in a bath at 55 C. and a current density of 350 amp. per sq. ft., no generalizations could be made regarding the effect of this factor at other current densities and temperatures (Fig. 1).

It was discovered that the fatigue limits of specimens plated and subsequently ground to remove a part of the plating were equal to or greater than those initially plated to the same thickness as the ground specimens and tested as plated.

Other experiments showed that interruptions of the plating process did not reduce the fatigue limit of the specimens provided proper precautions were taken for continuing the plating.

► **Effect of Heating**—Chromium-plated materials often are heated to temperatures between 90 and 200 C. to improve their mechanical properties by expelling the hydrogen deposited with the chromium. Hence, a systematic study was made of the effect of heating on the fatigue limit of chromium-plated steel.

Results showed that the fatigue limits of quenched and tempered specimens heated after plating decreased to a minimum value for some heating temperature between 100 and 300 C. and thereafter increased with increased heating temperatures (Fig. 2). Fatigue limits of specimens heated for 1 hour at 440 C. in some cases were 87.5 percent of that of the unplated steel, whereas fatigue limits of specimens plated but not heated, and of specimens heated 1 hour (in air) at 193 C., were only about 68 and 27 percent, respectively, of the unplated steel.

Composition of Steels Used in Studying Influence of Chromium Plating on Fatigue Limits

Element	SAE X4130 Steel Lot A	Lot B	Lot C	SAE 6130 Steel
Carbon	0.35%	0.29%	0.33%	0.30%
Manganese ...	.53	.47	.55	.61
Phosphorus ...	.01	.02	.03	.03
Sulphur	.02	.02	.01	.04
Silicon	.21	.25	.24	.25
Chromium ...	.95	.96	1.05	1.01
Molybdenum .	.19	.24	0.20	*
Vanadium	*	*	*	.22
Nickel	*	.15	.17	*

* Not determined.



Fig. 1. Relation between endurance limit and plate thickness of SAE X4130 and 6130 steels.

. . . and NOW it's *Official*



CONTINENTAL ENGINES

In authorizing the establishment of local passenger, mail and express air service by operators using Continental-powered single-engined planes, the Civil Aeronautics Board has taken official note of a fact known to pilots for years. That fact—the dependability of Continental power—is hammered home every so often by some record-breaking flight like the late Capt. Bill Odom's two long over-water hops, the six-week marathon of Barris and Riedel, or Jongeward's and Woodhouse's six weeks and four days non-stop. Under the exacting requirements of day-in-day-out use, it is being proved constantly by farmers, ranchers, and a growing list of business and industrial concerns, whose planes are business equipment and as such must more than earn their keep. These daily users' experience underscores the champions' advice: fly with Continental power.

CONTINENTAL SERVICE NEAR AS THE NEAREST AIRPORT

You're sure of getting there and back, when you fly with a Continental engine. Genuine Continental parts and factory-authorized service are available wherever you go. Continent-wide service backing is another of the reasons why Continental engines are fliers' first choice.

CONTINENTAL MOTORS — Powerful as the Nation — AMERICA'S STANDARD

Continental Motors Corporation

AIRCRAFT ENGINE DIVISION
MUSKEGON, MICHIGAN

► **Causes Considered**—Three possible causes for the adverse effect of chromium plating on the fatigue limits of the steels were embrittling effect of hydrogen deposited with the chromium, cracks in the chromium, and residual stresses in the chromium.

However, it was shown that there was no simple relationship between the fatigue limit and the amount of hydrogen remaining in the chromium after a baking treatment.

Further experimental evidence indicated that cracks present in the chromium were not the principal cause of the reduced fatigue limits of the plated steels.

It is generally agreed that residual stresses in a material markedly affect its fatigue limit. Thus, in steel, compressive stresses, such as are produced by shot peening, increase the fatigue limit; tensile stresses have the opposite effect.

► **Tubes "Tongued"**—To show the presence of tensile stresses in electrodeposited chromium and the effect of heat treatment on these stresses, thin-walled tubes of annealed steel were chromium-plated and subsequently heated to different temperatures.



Fig. 2. Effect of baking temperature on fatigue limit of SAE X4130 steels. Circles indicate specimens baked in air, crosses are for specimens baked in organic liquids.

"Tongues"—strips about ⅛-in. wide and 2 in. long, with one end left attached—were then cut in the tubing to permit a qualitative evaluation of stresses in the chromium plate.

Tongues cut in plated tubing that had not been heated were found to bend slightly outward from the surface of the tube, indicating the presence of residual tensile stresses in the plated layer.

Baking the plated tubes at temperatures around 200 C. was found to increase further the tensile stresses in the chromium, as evidenced by the greater bending of the tongue away from the tube surface.

► **Stress Action**—From these observations, it was concluded that the decreased fatigue limit accompanying the heating at 200 C. of the plated fatigue-test specimens was due to increased tensile stresses induced in the chromium plate.

This conclusion has been further substantiated by experiments showing that electrodeposited chromium subjected to a heating-and-cooling cycle increases in density and thereby contracts. Since no significant dimensional changes occur in the steel upon completion of the cycle, the steel tends to restrain the complete shrinkage of the chromium layer and thereby increases the tensile stresses in it.

If the chromium-plated steel is heated to a sufficiently high temperature (above 400 C.), the contractive forces in the chromium produce sufficient tensile stresses to cause plastic flow or rupture of the chromium plate, relieving the residual tensile stresses in it.

Thus, when the tubes were heated above 400 C. and the tongues cut, the free ends of the tongues were depressed below the surfaces of the tubes, indicating a release of the restraint in the steel initially caused by residual tensile stresses in the chromium.

This suggests that the increased fatigue limits produced in the fatigue specimens heated above 400 C. were caused by stress relief in the chromium plate accompanying its plastic flow or rupture.

New Quick-Disconnect For Ejection Seats

A "lap type" quick-disconnect boot which instantly frees the pilot from all connecting lines—oxygen, "mike" and receiving headset, anti-G suit, electrical heating, etc. when he is ejected from a high-speed fighter plane, has been developed at Chance Vought Aircraft.

Currently being evaluated by Navy and CV test pilots, the new quick-disconnect is similar to a Vought-developed unit now in use, in that it releases automatically from an attachment point on the left console of the cockpit and stays with the pilot as he catapults from the craft. But it differs from this point on.

As the free-falling pilot prepares to leave the ejection seat and take to his parachute, he releases his safety belt and disconnect boot—attached to belt buckle—in a single motion. Before, he had to perform two operations to accomplish this same result.

Chance Vought considers the new quick-disconnect a substantial advance in simplifying seat ejection procedures. The unit is more conveniently located on the pilot's lap to reduce the bulk of equipment on his chest and, with its hook-up to the safety belt, takes up less of the pilot's time and attention while he is falling—when time is short.

Flight Stability
Unimpaired by This ★



SINGLE ENGINE PERFORMANCE

Service Ceiling, Max. Continuous Power, Weight 33,500 lbs..11,150 ft
(R/c = 0.02 • V_{so}2 ft/ min)

Rate of Climb, Max. Continuous Power, Weight 33,500 lbs
Sea Level ..... 360 ft/min
5,000 ft Altitude..... 300 ft/min

Min. Runway Length, required by CAR
Take-off, Sea Level, Weight 35,000 lbs..... 3,986 ft
Landing, Sea Level, Weight 34,400 lbs..... 3,180 ft

Even if one engine becomes inoperative, the Scandia's stability and maneuvrability remain unimpaired. In fact the plane's single engine performance puts it in a class by itself. All pilots who have flown the Scandia are unanimous in praise of its remarkable flight characteristics.

Scandia

SVENSKA AEROPLAN AKTIEBOLAGET · SAAB AIRCRAFT COMPANY · SWEDEN

Liftmaster Has Self-Contained Freight Lift

ON special ramp-type adapter, Jeep goes up on platform trackage for trip . . .

UP to fuselage floor on electric-powered, 4000-lb.-capacity elevator, then drives . . .



INTO Liftmaster's cargo hold after trackage is rotated on elevator's platform.

Elevator attaches to front or rear door. Capacity is two tons.

Douglas Aircraft Co. Inc.'s new DC-6A Liftmaster, freighter version of the DC-6 passenger plane, carries along its own powered, loading elevator capable of hoisting 4000 lb. from approximately truckbed height to cabin floor level.

The elevator may be attached to either front or rear cargo door and can be folded and stowed within the fuselage, behind the rear door. The installation should offer distinct advantage for military and commercial operations at airports where ground freight-handling equipment is not available.

▶ **Elevator Operation**—Vertical component carrying the guide rails for the lifting platform is fastened to the bottom sill of the cargo door opening. Electric power for the motor operating the lift is supplied by an auxiliary gas engine coupled to a generator.

To handle small vehicles, the platform can be fitted with turntable trackage. A ramp-type adapter allows the vehicle to be driven up on the platform. When the platform is raised to fuselage floor level, the trackage can be rotated to permit the vehicle to enter the plane.

For stowage, the platform is lowered to the bottom of the guide rails and folded against the vertical component, whose fasteners are then released. Both are then pulled into the plane by electric power through a cable and pulley arrangement, and held behind the large aft section of the double rear door.

▶ **Production Model**—Automatically controlled cabin pressurization and air conditioning systems will permit high altitude transportation of perishable cargo. And leading edges of wing and tail have thermal anti-icing provisions incorporated.

Latest plans are to fit the production model with Pratt & Whitney R-2800-CB-17 engines rated at 2500 takeoff hp. with water-alcohol injection, and 1900 hp. maximum continuous cruise. Props will be Hamilton Standard or Curtiss high-activity units.

Takeoff at full gross weight of 100,000 lb. will be within 5050 ft. at sea level. Landing field length at 85,000 lb. is 5020 ft. Absolute range with 4700 gal. of fuel is 4475 mi.

Cargo volume is 5000 cu. ft. and the craft will carry 28,800 lb. payload over long distances at better than 315 mph.

THE
CONVAIR*
L-13

Versatility plus!

In addition to the usual gear for runway landings, the all-metal Convair* L-13 has, as alternate equipment, floats for operation on water, skis for snow areas, and double-wheel gear for desert missions. Folding wings and tail assure ease in towing, storage or concealing the plane. An aerial jack-of-all-trades, the L-13 is used for observation, communication, artillery spotting, supply dropping, cargo transport, evacuation, photographic and rescue operations. Ultra-brief take-off and landing runs add importantly to its value from any surface.

CONVAIR*

CONSOLIDATED VULTEE
AIRCRAFT CORPORATION

SAN DIEGO, CALIFORNIA
FORT WORTH, TEXAS

FEDERAL

LIGHT WEIGHT ALL-METAL SKIS

are in successful service with more operators than all other makes combined.

MASTER SKI BUILDERS SINCE 1925

C.A.A. approved skis for all makes of aircraft

Equip with **FEDERAL SKIS** *and Increase Airplane . . .*

Utility	*Range of Operation*
Revenue	*Flying Convenience*
Sales	*Student Training*
Rental	*Business Service*
Charter	*Sporting Pleasure*
Safety	*Landing Areas*

Federal Skis assure practical, safe, and efficient continuous operation of aircraft throughout the winter months. Through year around airplane operation which skis afford, airplane ownership is more fully justified and warranted.

FEDERAL presents the only complete line of skis available

Standard and custom-built models include

- **Fixed Position Wheel Replacement Types.** Standard models for Aeronca, Beaver, Bellanca, Cessna, Chipmunk, Fairchild, Fleet Canuck, Funk, Luscombe, Seabee, Skyranger. Stinson, Swift, Taylorcraft, and other popular makes.

  Note: An axle adapter arrangement and universal rigging permits interchangeability of various aeroplanes within the gross capacity of each ski model.

- **Tricycle Gear Types.** Standard models for Ercoupe. Custom-built models for Navion and others.

- **Combination Wheel-Skis.** Standard models for Cessna Model 170, Norseman, Stinson. Custom-built models for Aeronca, Anson, Cessna Model 195, Luscombe, Navion, Piper and others.

- **Retractable Wheel-Skis.** Custom-built models for Douglas DC-3, C-47, R4D, Dakota, Fairchild C-82, Northrop, and other transport aircraft.

- **Clamp-On Wheel Types.** For light planes equipped with 6.00 x 6 and 8.00 x 4 tires and wheels.

- **Shock Absorbing Pedestal Types.** Custom built fixed gear models for Bellanca, Beech, Beaver, Twin engine Cessna, Fairchild, Norseman, Waco and others.

FEDERAL AIRCRAFT IS PREPARED TO DESIGN, ENGINEER AND CUSTOM-BUILD SKIS FOR ANY SPECIFIC TYPE OF AIRCRAFT AND SKI OPERATING PROBLEM.

Standard ski models can be obtained promptly from Warehouse Stock of the leading Airplane Parts and Supplies Distributors, and your closest Airplane Distributor or Dealer.



FEDERAL
AIRCRAFT WORKS
3456 NORTH MISSISSIPPI DRIVE
MINNEAPOLIS 12, MINN.



Hypersonic speeds are attained by making slot (left) about as thin as this sheet of paper.



Schematic sketch shows Mach 10 tunnel details.

Caltech Tunnel Exceeds Mach 10

New facility will advance rocket and guided missile research. Believed to be world's fastest tunnel.

A hypersonic wind tunnel which can continually generate airflow speeds greater than 10 times that of sound at sea level has been developed at the California Institute of Technology under contract with the Army Ordnance Department.

Designed by Caltech's Dr. Allen E. Puckett to accelerate rocket and guided missile research, the new tunnel is said to exceed by a wide margin the speed of any other known tunnel. Previous record was about seven times the speed of sound, and that was in an intermittent type tunnel which could maintain the Mach 7 rate for only a few seconds.

Besides its use to gather basic experimental data on shock waves, boundary layer, and airflow at hypersonic speeds, the installation itself will be studied to obtain information on design, performance and instrumentation to be applied in the development of future extreme-speed tunnels.

The test housing of the new facility is 4 ft. long. It includes a region of acceleration downstream from the nozzle throat, followed by a 5 x 5-in. test section where the models are mounted, and finally a diffuser area where the air is slowed.

To accelerate in the expansion section, the air passes through an adjustable slot in the throat of a specially designed steel alloy nozzle. Size of the slot opening depends on the speed desired. For a Mach 10 rate, air is forced at great pressure through a tiny slit, approximately .006 in. wide. As it suddenly expands into the test section the temperature drops to about −430 F., while the pressure is reduced



Standard Equipment for the Beechcraft Bonanza

...the RCA One-Sixteen

The new Beechcraft Bonanza is delivered complete with the RCA ONE SIXTEEN as standard equipment.

In adapting the ONE SIXTEEN to the special performance requirements specified by Beechcraft for the Bonanza, RCA aviation radio engineers conducted exhaustive tests in collaboration with Beechcraft engineers. These tests resulted in an installation which makes the most efficient use of the best qualities of both the ONE SIXTEEN and the Bonanza—assures the ultimate owner of the airplane the maximum satisfaction with both the airplane and the radio.

This same engineering service is available to other aircraft manufacturers—and to individual plane owners who already have or contemplate making radio installations. Take advantage of RCA's expert counsel on antenna location, installation wiring, signal propagation, or any other problems of that nature.

EVERYTHING IN ONE PACKAGE

ENTERTAINMENT—Complete coverage of standard broadcast band.

FOUR-COURSE RANGES—Continuous tuning 200-400 kc. Built-in range filter.

MARKER BEACONS—75-mc marker signals received clearly while flying the beam, or direction finding.

TOWER COMMUNICATIONS—Covers 200-400 kc by manual tuning. Six VHF transmitter channels.

LOUDSPEAKER OUTPUT—For cabin loudspeaker: also headphone operation. Speaker switch on front panel.

INTERPHONE—For large cabins, or two cockpits.

LOOP DIRECTION-FINDING—Operates on either broadcast or beacon bands with any RCA loop.

THE ONE SIXTEEN *is available to private pilots through any one of RCA's nationwide organization of radio dealers and distributors. See the ONE SIXTEEN at your nearest distributor. Or send for the free descriptive bulletin; Dept. 9L, RCA Engineering Products, Camden, N. J.*

AVIATION SECTION

RADIO CORPORATION of AMERICA

ENGINEERING PRODUCTS DEPARTMENT, CAMDEN, N.J.

In Canada: RCA VICTOR Company Limited, Montreal

THEY'RE STRATOS-FIED

Day by day and flight by flight, the advantages of Stratos cabin pressuring and air conditioning installations are being proved—proved in military and commercial planes, fighters and bombers; jet and propeller-powered aircraft and in overseas passenger transports.

In them, Stratos equipment provides cabin pressurization and air conditioning so vital to Military operations, so essential to airline operating economy and passenger comfort. Rapidly varying conditions of altitude, solar radiation and frictional heat resulting from high speed present complex problems, solved only by precise engineering methods.

Stratos advantages have been achieved through the highest standards of design ingenuity, precision manufacturing techniques plus knowledge and experience—experience dating from the days when engine supercharging was in its infancy.

STRATOS Has These ADVANTAGES

Superchargers can be engine-mounted, take power directly from reciprocating engines.

Hydraulic coupling maintains constant air flow to the cabin independent of engine speed and altitude.



Light weight — the Banshee air conditioning unit weighs 14 pounds, the Constellation's less than 58.

Compactness. Dependability. Easy maintenance. Highest standards of performance.

Stratos Engineers will answer your inquiries Write to

STRATOS CORPORATION

Farmingdale, N. Y., or
1307 Westwood Boulevard, Los Angeles 24, California

A SUBSIDIARY OF

FAIRCHILD ENGINE AND AIRPLANE CORPORATION
HAGERSTOWN, MARYLAND

to 1/1000 of normal atmospheric.

Pressure is supplied by fifteen compressors, thirteen rotary vane units and two of the double acting reciprocating type. Through a piping system controlled by valves, twelve of the compressors can be operated in parallel, or all fifteen can be arranged in series to operate in six stages.

Air from the battery of compressors flows first into a large supply reservoir before entering the nozzle. The tank is 12 ft. long and 3 ft. in diameter, with steel walls varying in thickness from 1½ to 2½ in. It weighs about 6 tons. An hydraulically-operated plug blocks air from passing into the throat slot until the required pressure is built up in the tank.

Since the air must be free of moisture, it is processed by a drier before it enters the tunnel, which can be run 10-20 hr. before it is necessary to reactivate the drier. To prevent moisture condensation on the outside of the plate glass sides of the test section during the early part of a run, the installation has double windows with a special drying material between.

A schlieran optical system is used to photograph airflow past the model. This includes an arrangement of mirrors which pass parallel light through the glass windows of the test section. Shock waves act as miniature lenses to disturb the parallel beam, and the disturbance is recorded by a specially designed camera. This can photograph an 8-in. circular area at one time. The entire system can be moved along the tunnel on an overhead track to show what happens upstream and downstream of the model.

Operation of the tunnel is under the supervision of Dr. Henry T. Nagamatsu of the Caltech Guggenheim Aeronautics Laboratory.

Texas Tunnel

Another supersonic air duct capable of creating speeds from 5000-7500 mph. is nearing completion at the University of Texas.

Built under contract with the Navy for basic research into airflow problems related to guided missile development, the installation will have a large torpedo-type compressor to deliver air at 3000 psi., and a battery of high-vacuum pumps to provide motive power.

To operate the tunnel, an air charge first will be built up in a high pressure reservoir, while, at the same time, a low pressure tank on the opposite end of the duct will be evacuated. Then, by turning a quick-opening valve, the pent-up air in the reservoir will be released suddenly to blast through the duct into the vacuum chamber at speeds reaching 10 times the velocity of sound.

Century MODEL 406

RECORDING OSCILLOGRAPH

FOR

VIBRATION – TEMPERATURE

STRESS – STRAIN ANALYSIS

where any or all of the above information is an important factor.

FEATURES

1. 12—50 individual channel recording.
2. Continuous recording up to 200' without jamming.
3. Instantaneous changes of recording speeds up to 50" per second with automatic adjustment of lamp intensity.
4. Timing System — Discharge lamp controlled by temperature compensated tuning fork providing sharp .01 second with heavier .1 second timing lines. Conversion to .1 second lines only, by switching.
5. Independent optical system provides constant view of traces with optimum light intensity at all times.
6. Recording lamp under constant surveillance of external condition indicator lamps.
7. Galvanometers — with optional range of frequencies and sensitivities.
8. Electrical — Available for operation from option of 12 or 24 volts D.C., or 110 volts A.C.

OPTIONAL FEATURES

1. Trace identification by means of light interruption.
2. Trace scanning for observation of steady state phenomena.
3. Remote control unit.
4. Automatic record numbering system.
5. Automatic record length control.
6. Visual paper footage indicator.

For additional information write

Century GEOPHYSICAL CORPORATION

TULSA, OKLAHOMA

216 No. 12th Street
Philadelphia 7, Pa.

EXPORT:
149 Broadway, New York

FOR
ADDED PAINT LIFE
AND
EXTRA PROTECTION
ALODIZE
ALL ALUMINUM SURFACES
WITH

Alodine®

"Alodine", the new ACP protective coating chemical, forms a weather-resistant skin and durable paint bond on aluminum. It is quick, easy and economical to apply.

With Brush "Alodine", airplanes and other large aluminum structures can now be successfully treated in the field. Results compare favorably with those obtained in standard Dip or Spray "Alodine" installations.

For the convenience of users, "Alodine" Chemical Kit No. 1 is available. This kit contains sufficient cleaning and coating chemicals to Brush Alodize about 1,000 square feet of aluminum surface.

For further information, write to:

AMERICAN CHEMICAL PAINT CO.
AMBLER, PENNA.

LEWIS

THERMOCOUPLES

FOR ENGINE TEMPERATURES

We specialize in the manufacture of all types of aircraft thermocouples, lead wire, firewall blocks and lead-resistor blocks. We are equipped to fabricate jet engine thermocouple-harness assemblies, connecting-lead assemblies and special connector blocks to your specifications. Bring your temperature measuring problem to us, whether it is a new thermocouple, harness, or connecting lead, we are at your service.

THE LEWIS ENGINEERING CO.
CHURCH ST. • • • • NAUGATUCK, CONN

ENGINEERING FORUM

Disputes "G" Value

Your treatment of the National Air Races, in the Sept. 12 issue, was well presented. Coverage was adequate and informative, even to those who were there. Your editorial comment was both pointed and judicious.

Performance presented by the participating pilots was well nigh perfect and too much cannot be said for their skill and stamina. However, it only requires the application of a little basic physics to show that your Industry Observer was a bit overzealous in stating "North American F-86 fighters flew the jet division of the Thompson Trophy Race in a steady bank which held a constant 6-7G on its pilots. . . ."

To hold a steady acceleration the path must have had a constant curvature—a circle. From basic physics the centrifugal force is:

$$F = mr\omega^2$$

where F is centrifugal force; m, mass of the airplane; r, radius of turn; and ω, angular velocity.

Now,

$$m = W/g \text{ and } \omega = V/r$$

where W is weight of the aircraft; g, acceleration of gravity, 32.2 fps.^{2}; and V, linear velocity.

Substituting,

$F/W = V^2/gr = G_H$ = acceleration in the horizontal plane.

Resolving the horizontal acceleration, G_H, with the vertical acceleration, g, gives the G load on the pilot:

$$G = \sqrt{g^2 + G_H^2}$$

Solving for our particular case,

V = 586 mph. = 860 fps. (from AVIATION WEEK, Sept. 12, page 15)
$r = c/2\pi = 15/2\pi = 2.38$ mi. = 12,600 ft.
$G_H = 860^2/(32.2 \times 12{,}600) = 1.82$
$G = \sqrt{1^2 + (1.82)^2} = 2.08$

It may be argued that this represents the minimum steady G. Assuming that the statement on page 14 (Sept. 12) that ". . . the Sabres actually flew nearly 25 miles instead of 15 for each of the laps" is correct and that it was made at the maximum speed of 635 mph. (measured as though over a 15-mile course) we can repeat the calculation to get a maximum value of steady G:

$V = 635 \times (25/15) = 1060$ mph. = 1550 fps., a highly improbable speed, even for an F-86.

$r = 12{,}600 \times (25/15) = 21{,}000$ ft.
$G_H = 1550^2/(32.2 \times 21{,}000) = 3.56$
$G = \sqrt{1^2 + (3.56)^2} = 3.70$

which is still far short of 6-7G.

An easier way of visualizing the same result is to consider the angle of bank. The lift in the vertical direction must equal the weight of the airplane. The lift normal to the wing, which is the weight of the airplane times the number of Gs being pulled, must be sufficient that its vertical component equals the weight. Therefore,

$$W = L \cos \phi$$

where ϕ is the angle of bank,

or $L/W = G = 1/\cos \phi$

This assumes, of course, that the airplane maintains constant altitude, which was necessarily the case so near to the ground.

At $6G$, $\phi = \cos^{-1} 1/6 = 80\frac{1}{2}$ deg.
At $2G$, $\phi = \cos^{-1} 1/2 = 60$ deg.

It was obvious to the spectators that the angle of bank was nearer 60 than 80 deg.

JAMES K. MARSTILLER,
24 Acacia Drive,
Dayton 9, Ohio.

Slated for Turboprop

I would like to comment on the article "RAF Tests New Anti-Sub Planes" on page 16 of the Oct. 31 issue of your magazine.

The last paragraph of the article states that the exhaust outlets on both sides of the fuselage at the wing's mid-chord (of the Blackburn Y.A.5) could be adapted without change for gas turbine jets.

However, it is apparent that these outlets are already designed for gas turbine jets, since from a study of the photograph it can be seen that there are six individual exhaust stack stubs at the nose of the fuselage which would be required on both sides for a Rolls-Royce Griffon engine. There is no evidence of an exhaust collector tube, and if there were a collector tube, the skin could be faired over these stubs for aerodynamic considerations.

Also, from an elementary study of aircraft powerplants, the exhaust outlets at the wing mid-chord would be detrimental to both the performance of a reciprocating engine and from drag considerations of the airframe. Also, the ducting necessary to exhaust the Griffon engine at this point would be expensive in space and duct losses.

Therefore, it seems apparent that the Blackburn Y.A.5 has been designed for a turboprop and the present engine is substituted for test purposes.

However, I like your magazine very much and read it quite avidly.

BOHDAN I. WANDZURA
1138 Browning Blvd., Apt. 10
Los Angeles 37, Calif.

(Frederick R. Brewster, McGraw-Hill World News London bureau chief who sent in the story in question, writes:

"Reader Wandzura's sharp eyes have spotted an error, all right. The story should have made it clear that the large exhaust outlets in the Y.A.5's fuselage at the wing's midchord are intended for the turboprop engine which will be fitted shortly. The Y.A.5 was laid down with the intention of installing a double-turboprop engine initially —a double Naiad. But the single Naiad engine, which has been on bench-test for over a year now, as well as being flight-tested in the nose of an Avro Lincoln, has not developed anywhere near the expected 1500 s.h.p. Consequently, the Naiad has been dropped and the double Mamba tapped as the probable power unit for the Y.A.5. Installation of the Rolls-Royce Griffon piston engine, as pointed out in the article in AVIATION WEEK, is a temporary measure only."—Ed.)

Proved by 10 Years' Performance in Flight Operations!

KEEP LIGHT PLANE engines in *clean condition* for fine performance—*with Esso Aviation Oil!*

IT'S MADE FROM high quality base stock . . . and it's a detergent-dispersant type lubricant specifically designed for aviation use that performs a remarkable *cleaning action* as it lubricates. When oil is changed, suspended carbon and sludge *drains out of the engine!*

PROVED by tests run both in America's largest aviation petroleum laboratories and by a leading manufacturer of light plane engines—**as well as by years of actual use in gruelling operations, under extreme temperatures.**

NEXT TIME you change oil, change to the oil that helps improve the operating condition of light plane engines—ESSO AVIATION OIL! It's available in grades HD 55, HD 65, HD 80 at airports from Maine to Texas . . . wherever you see the famous Esso Winged Oval.

YOU CAN DEPEND ON



MICRO-SECTION of a pressure weld, showing lines of flow. Note absence of weld line.

Pressure Welding Being Studied

Piper investigating merits of new British-developed process offering production time-and-cost savings.

One aircraft manufacturer is wasting no time getting a license on a recently developed cold welding technique in which metals simply are forced together by skillfully applied pressure—replacing methods using rare gases and electricity. Already introduced in England by the developer, the General Electric Co., Ltd. (no relation to the American company), the process has been available to U. S. firms only a few weeks.

The aircraft company interested in using the process is Piper Aircraft Corp., Lock Haven, Pa. Piper currently is negotiating with the Koldweld Corp., New York City, which controls all licensing rights in this country.

▶ **Special Features**—Piper's desire to license the new welding process is explained by Koldweld's reports that:

- **No special skill** is required to operate welding equipment.
- **Low cost tools** make adoption of process feasible even to the smallest firms.
- **Less materials** handling is required, since welding equipment usually can be carried to any point on the production-line in man's pocket or small handbag.
- **It is faster** in some operations than other welding processes.
- **It is adaptable** for welding materials having wide range of thicknesses, from thin aluminum foil to heavy metals.
- **It is superior** to other welding processes in producing vacuum- or moisture-proof containers, since blow-holes, created by expansion and contraction of gases, are eliminated.
- **It eliminates** need for flux, cleaning joints after weld, and shielding masks.

According to William Dubilier, president of Koldweld and founder of Cornell-Dubilier Electric Corp., the new technique "will revolutionize industrial and job welding of many metals, particularly aluminum."

Besides its use with aluminum alloy, the process reportedly can be applied to such nonferrous metals as cadmium, lead, copper, zinc, nickel and silver—even to the extent of joining dissimilar metals. It is believed further developments will make possible its use with soft steel and other ferrous products. Currently, the maximum thickness which can welded by hand is about ¼ in. But this can be increased, the firm says, by making larger tools.

▶ **Principle**—Cold welding is based on the principle that sufficient pressure applied in a specific manner to two pieces of metal will cause them to flow together to become a single homogenous mass at the point where force is exerted. The pressure is stated to cause molecular fusion at this point.

Welding some types of joints is so simple that the only tool needed is a pair of small pliers incorporating special dies on the jaws. Pieces of aluminum foil, only .001-in. thick, have been welded with a center punch.

An important secret of the process, known only by Koldweld and the British firm, is the formula regulating the planform shape and depth of the dies used to make the pressure welding imprint in the metal. It is known, however, that die shapes vary, depending on the composition and thickness of the metal to be welded, and the type of joint to be made. Pressure varies, with a maximum of 20 tons psi. used to join the hardest aluminum-alloys. Force can be applied gradually or through impact.

A critical requirement of cold welding is removal of oxide film from surfaces before parts are joined. One method of accomplishing this is by polishing with a wire brush. Even contamination caused by handling material will prevent formation of a satisfactory weld. Once removed, the oxide film returns slowly, permitting welds to be made several hours after polishing.

▶ **Techniques Developed**—So far, three techniques have been evolved in the process, the straight, ring, and continuous seam welds. The straight weld can be used for box seams, sealing tube ends and for other forms of lapped joints. Important applications of the ring weld are sealing flanged tubes in fabrication of hermetically sealed containers, joining two disks together to form a pressure diaphragm, welding flanged tubes to plates for making hose connections, etc. The seam weld is especially useful in making conduit and other tubes. A machine has been developed which automatically polishes material to remove oxide, forms metal into tubing with seam, welds and then trims finished tube.

▶ **Improvement Seen**—By combining the Koldweld and argon weld processes Dubilier says its possible to produce rugged metal vacuum tubes for radios and other electronic equipment. Cold welding doesn't equal arc welding when it comes to producing strong joints, but the company believes its only a matter of time before this is possible.

For the present, it is recommended the process be used only on parts which are not primary load carrying structures. Dubilier thinks future developments will permit its use on aircraft skin—replacing rivets. Since flush-type seams can be made, it is possible the process even could be used for surfaces on supersonic aircraft.

▶ **Piper Program**—After receiving its license, Piper Aircraft plans to put cold welding through an extensive test pro-



Made to your order ...at savings to you!

FULTON SYLPHON STAINLESS STEEL BELLOWS ASSEMBLIES

YOU SAVE 3 ways when you order stainless steel bellows assemblies from Fulton Sylphon.

First, you save time—we can produce to meet your schedules. Secondly, you save worries . . . we make assemblies *exactly* to your specifications . . . take over all production problems. Third, you save extra overhead and production costs . . . because we have the trained personnel and complete equipment to handle orders in any volume.

No matter how complex an assembly you may require, you can be assured Fulton Sylphon will produce it just as you want it. For designing, developing and making bellows assemblies is a Fulton Sylphon specialty—has been for half-a-century.

And, we'll help you in confidential development work if you wish.

Fulton Sylphon bellows assemblies are used in many ways—in thermostatic devices, pressure controls, hydraulic mechanisms, valves, shaft seals, expansion chambers, recording instruments and other applications. They'll help you get finest performance from your products —save you money, too.

Send for free Bulletin XAW-1200 that gives you further information.

Temperature Controls • Bellows Devices • Bellows Assemblies

FULTON SYLPHON
DIVISION

FIRST WITH BELLOWS

ROBERTSHAW FULTON CONTROLS CO. KNOXVILLE 4, TENN.

Canadian Representatives, Darling Brothers, Montreal

gram of its own. Experimental parts will be subjected to actual flight conditions for long periods. The company wants to make certain that parts welded under this process are capable of standing up to vibration, handling, fatigue and other service requirements before it adapts the technique to its production-line.

August C. Esenwein, executive vice president and general manager of Piper, emphasizes that one feature of pressure welding—reduction in metal thickness at the joint caused by die imprint—will be given an especially thorough study to determine its effect on material strength.

If the process comes up to expectations, it first will be used in production of non-structural parts, with the possibility, after long observation of these parts in service and improvements in technique, that it eventually will have more widespread applications in airframe assembly of structural members.

Esenwein believes that in many applications cold welding could become the "logical substitute for riveting and spot welding." He sees the chance of large savings in fuel tank construction. Tanks now are formed in two sections on a hydraulic press, then joined by welding. It takes one man about ¾ hr. to gas weld a 9-ft. seam joining the sections. Esenwein thinks this operation could be cut down to 5-10 min. with cold welding.

▶ **License Program**—Tentative licensing plans are that the licensee will pay a fixed fee of about ¼ of 1 percent of the value of each unit produced under the process. Dubilier claims this charge is less than the cost of wrapping the part for shipment. The fee will not be based on the total value of a device incorporating several cold welded parts. It will effect only the units involved.

After a license is granted, Koldweld supplies the firm with all accumulated data on the process, including blueprints for tools, tables and formulas regulating die shape, pressure application, and welding procedures. Koldweld also plans to help firms adapt the process to their own particular production requirements and will supply the tools if the licensee doesn't care to make his own.

▶ **Lockheed Interested**—Lockheed Aircraft Corp., Burbank, Calif., is another firm which has shown more than casual interest in the Koldweld process. But it has no immediate plans for taking out a license. This company also is watching other welding developments at the Aluminum Co. of America. Alcoa is experimenting with pressure welding at both room and elevated temperatures. None of its developments in this field as yet are scheduled to be licensed out to other firms.

Latest Air Force Bid Awards

Air Materiel Command Procurement Division makes available to AVIATION WEEK the latest bid awards, shown on this page. Requests for further information should be addressed to Contracting Officer, AMC, Wright-Patterson AFB, Dayton, Ohio, attention: MCPPSX72.

ABSTRACTS

For cap assemblies (50-164):
Companies sharing—Tubing Seal Cap, Inc., Los Angeles, on a bid of $1341.44; Air Associates, Inc., Teterboro, on a bid of $193.50; Manhattan Lighting Equipment Co., New York, on a bid of $395, and Frank & Warren, Brooklyn, on a bid of $705.

For 42 demagnetizer assemblies (49-1074):
Companies sharing—Graybar Electric Co., Inc., Dayton, on a bid of $1220; Stanhope Products Co., Brookville, O., on a bid of $9572; Laboratory Equipment Corp., Mooresville, Ind., on a bid of $144.50, and Bendix Aviation Corp., Eclipse-Pioneer Division, Teterboro, on a bid of $79.96.

For welding power operated positioners (50-100):
U. S. Pipe & Mfg. Co., San Francisco, on a bid of $19,601.

For installation 250 volt d.c. switch gear assy. (50-137):
Hughes-Simonson Engr. Co., Dayton, on a bid of $4096.

For washers (50-141):
Companies sharing—L. J. Barwood Mfg. Co., Inc., Everett, Mass., on a bid of $20.65; Geo. K. Garrett Co., Inc., Philadelphia, on a bid of $2240; New Haven Clock & Watch Co., New Haven, on a bid of $4840, and Camloc Fastener Corp., New York, on a bid of $30.

For 2500 cones (50-147):
Abbot Machine Co., Milwaukee, on a bid of $11,450.

For 252,500 cowling assemblies (50-159):
Companies sharing—Dzus Fastener Co., Inc., Babylon, N. Y., on a bid of $4764.99, and Monadnock Mills, San Leandro, Calif., on a bid of $1048.

For turnbuckle assemblies (50-161):
Companies sharing—Aero Bolt & Screw Co., Inc., New York, on a bid of $721.25; American Chain & Cable Co., Inc., Automotive & Aircraft Div., Detroit, on a bid of $712.80; Aero Supply Mfg. Co., Inc., Corry, Pa., on a bid of $3041, and Ruland Mfg. Co., Watertown, Mass., on a bid of $1450.

For 20,000 pounds napthalene (50-162):
Koppers Co., Inc., New York, on a bid of $2563.

For silvercyanide and silver nitrate (50-166):
Goldsmith Brothers Smelting & Refining Co., Chicago, on a bid of $48,155.80.

For bushing assembly (50-170):
Companies sharing—Justrite Mfg. Co., Chicago, on a bid of $1729.14; Fuel City Metal Works, Inc., Clarksburg, W. Va., on a bid of $1435; V. L. Graf Co., New Baltimore, Mich., on a bid of $2940; Browning Brothers, Inc., New York, on a bid of $491.84, and Industrial Precision Products Co., Chicago, on a bid of $810.

For 1650 lamp assemblies (50-175):
Stewart R. Browne Mfg. Co., Inc., New York, on a bid of $45,787.50.

For 10,500 yards waterproof fabric (50-182):
American Finishing Co., Memphis, on a bid of $8478.75.

For 24 parachute drop test dummies (50-183):
Sweebrock Aviation Co., Inc., Fort Wayne, on a bid of $3318.

For 5402 rectifier bulbs (50-196):
Companies sharing—Westinghouse Electric Corp., Westinghouse Lamp Div., Pittsburgh, on a bid of $1147.80; General Electric Co., Land Equip. Div., Dayton, on a bid of $5916, and Radiant Lamp Corp., Newark, N. J., on a bid of $2439.60.

For 66,600 feet acetylence hose (50-198):
Companies sharing—Boston Woven Hose & Rubber Co., Cambridge, Mass., on a bid of $2489.94, and Goodyear Tire & Rubber Co., Inc., Akron, on a bid of $4341.60.

For 200,000 gallons fuel (50-205):
Phillips Petroleum Co., Bartlesville, Okla. on a bid of $22,000.

For 1500 parachute assemblies (50-219):
Pioneer Parachute Co., Inc., Manchester, Conn., on a bid of $177,060.

For 274 transformers (50-230):
Weston Electrical Instrument Corp., Newark, N. J., on a bid of $3633.24.

For adapter, apron etc. (50-96):
Companies sharing—Coogan Co., North Hollywood, Calif., on a bid of $1292.60; Hubbell & Miller Co., New Rochelle, N. Y., on a bid of $27,400; Semon Bache & Co., New York, on a bid of $107; Abrams Instrument Corp., Lansing, Mich., on a bid of $9318; Pako Corp., Minneapolis, on a bid of $9318; Eastman Kodak Co., Rochester, on a bid of $4064.35; Robinson Aviation, Inc., Teterboro, on a bid of $7815; Williams, Brown & Earle, Inc., Philadelphia, on a bid of $4121.30; Graflex, Inc., Rochester, on a bid of $23,385.16; Peck & Harvey, Chicago, on a bid of $462; Camera Equipment Co., New York, on a bid of $60.50; Columbian Enameling & Stamping Co., Terre Haute, on a bid of $263.25; Burke & James, Inc., Chicago, on a bid of $1550.80; Minnesota Mining & Manufacturing Co., St. Paul, on a bid of $3522.36; Morse Instrument Co., Hudson, Ohio, on a bid of $11,922.80; Seal, Inc., Shelton, Conn., on a bid of $4137; Penn Camera Exchange, Inc., New York, on a bid of $3427.40; Stephenson Film Corp., New York, on a bid of $4859.66 and Arel, Inc., St. Louis, on a bid of $14,795.18.

For 14,867 oxygen tubes (50-89):
Dayton Rubber Co., Dayton, on a bid of $48,236.93.

For 420 variacs—variable transformer (50-208):
Companies sharing—Standard Electrical Products Co., Dayton, on a bid of $10,185, and General Radio Co., Cambridge, Mass., on a bid of $1260.

For 2 flight equipment trainers (50-234):
Grand Central Airport Co., Glendale, on a bid of $3826.

For aircraft and airduct hose (50-214):
Companies sharing: B. F. Goodrich Co., Akron, O., on a bid of $2021; Aeroquip Corp., Jackson, Mich., on a bid of $54,762; Hewitt Rubber division, Hewitt-Robins Inc., Buffalo, N. Y., on a bid of $3728.40; United States Rubber Co., New York, N. Y., on a bid of $81,117.40; and Arrowhead Rubber Co., Vernon, Calif., on a bid of $7325.44.

For disconnector and plug assembly (50-254):
Aero-Motive Mfg. Co., Kalamazoo, Mich., on a bid of $3880.

For 4 trailers (50-257):
Stewart Truck Bodies, Inc., Brooklyn, N. Y., on a bid of $2800.

For bolts (50-264):
Companies sharing: Thompson Products, Inc. Bell, Calif., on a bid of $6327; Aircraft Hardware Mfg. Co., Inc., New York, N. Y., on a bid of $1427, and Lamson & Sessions Co., Cleveland, O., on a bid of $1364.20.

For 45,850 ft. cushion, extrusion (50-286):
Companies sharing: Los Angeles Standard Rubber, Inc., Los Angeles, Calif., on a bid of $6285.60, and Douglas Aircraft Co., Inc., Santa Monica, Calif., on a bid of $284.25.

For cord (50-278):
Companies sharing: Linen Thread Co., Inc., Paterson, N. J., on a bid of $34,260, and South Eastern Cordage, Cleveland, O., on a bid of $1400.40.

For 2478 tow targets and flag weights (50-88):
W. A. Apple Textile Mfg. Inc., Dayton, O., on a bid of $41,196.75.

For 8754 sheets glass sheet, laminated (50-224):
Pittsburgh Plate Glass Co., Pittsburgh, Pa., on a bid of $37,152.54.

For 1139 aircraft storage batteries (50-291):

TURBINE CONTROL designed, developed, and manufactured for the **NAVY BANSHEE** by



HOLLEY
Carburetor Co.
DETROIT, 4

FOR HALF-A-CENTURY—ORIGINAL EQUIPMENT MANUFACTURERS FOR THE AUTOMOTIVE INDUSTRY

Torrington Needle Bearings provide maximum capacity in compact designs in Hamilton Standard propellers



Propeller Synchronization and pitch change mechanisms must be compact, yet absolutely reliable. In several applications, Hamilton Standard Division of United Aircraft Corp. uses Torrington Needle Bearings to secure high capacity, anti-friction operation.



In Cam Roller Assemblies (arrow) of Hamilton Standard Hydromatic propellers, Needle Bearings reduce friction to a minimum. The full complement of Needle Rollers provides the high capacity necessary to carry the heavy loads involved.



A Needle Bearing is also used on the drive shaft of an electric stepmotor. Here, the Needle Bearing reduces wear and helps to maintain proper mesh between the motor shaft and gearing in an electric head which controls operation of a Hamilton Standard Hydromatic propeller governor.



Space Limitations in this compact gear pump housing of a Hamilton Standard integral oil control assembly are easily met by Needle Bearings. With internal clearances accurately controlled in fabricating housings and shafts, this precision bearing insures close tolerance alignment of the motor pinion gear.

To secure smooth anti-friction operation in compact, high-capacity designs, use Torrington Needle Bearings. Our engineers will gladly lend a hand in design analysis and bearing selection. Write us today. THE TORRINGTON COMPANY, Torrington, Conn., or South Bend 21, Ind. District offices and distributors in principal cities of United States and Canada.

TORRINGTON *NEEDLE* **BEARINGS**

Needle • Spherical Roller • Tapered Roller Straight Roller • Ball • Needle Rollers

Companies sharing: Auto-Lite Battery Corp., Toledo, O., on a bid of $31,857.24, and Reading Batteries, Inc., Reading, Pa., on a bid of $17,564.96.

For 6240 base adapter tubes (50-221):
Specialty Assembling & Packing Co., Inc., Brooklyn, N. Y., on a bid of $5304.

For 169,000 ft. elastic cord (50-246):
Russell Mfg. Co., Middletown, Conn., on a bid of $7127.60.

For 13,600 gal. oil (50-290):
Independent Mfg. Co., Philadelphia, Pa., on a bid of $12,104.

For 30,000 gal agent brightener (50-122):
Companies sharing: Wyandotte Chemicals Corp., Wyandotte, Mich., on a bid of $7350, and Sewall Paint & Varnish Co., Kansas City, Mo., on a bid of $8250.

For 2115 cable assemblies (50-176):
Mines Equipment Co., Div., Joy Mfg. Co., St. Louis, Mo., on a bid of $62,054.10.

For marker beacon receiving set (50-188):
Eltron, Inc., Jackson, Mich., on a bid of $17,077.30.

For 1,000,500v. bus bar supports (50-276):
Graybar Electric Co., Inc., Dayton, O., on a bid of $6270.

For lens assembly (50-280):
Line Material Co. of Pennsylvania, East Stroudsburg, Pa., on a bid of $2887.50.

For blackboards (50-151):
Companies sharing: Ohio Valley Slate Co., Cincinnati, O., on a bid of $8204.24; Bergsma Bros. Co., Grand Rapids, Mich., on a bid of $1742, and Roth Office Equipment Co., Dayton, O., on a bid of $651.

For booth (50-105):
Companies sharing: Binks Mfg. Co., Chicago, Ill., on a bid of $12,157, and Schmieg Industries Inc., Detroit, Mich., on a bid of $11,570.

For clamp, hose, (50-209):
Companies sharing: Breeze Corp., Inc., Newark, N. J., on a bid of $142,440, and Ideal Clamp Mfg. Co., Inc., Brooklyn, N. Y., on a bid of $132,075.

For fitting, access door, (50-210):
Companies sharing: Firestone Tire & Rubber Co., Los Angeles, Calif., on a bid of $5,497.50; United States Rubber Co., Mishawaka, Ind., on a bid of $63,056.40, and B. F. Goodrich Co., Akron, O., on a bid of $11,278.45.

For reflector, taxi strip (50-236):
Companies sharing—Minnesota Mining & Manufacturing Co., St. Paul, on a bid of $36,180 and A & Z Engineering Co., Covington, Kentucky, on a bid of $3796.40.

For screws and indicator assemblies (50-269):
Companies sharing—Dayton Wheel Co., Dayton, on a bid of $2458.40, and Revere Electric Mfg. Co., Chicago, on a bid of $217.40.

For 2000 wind indicators and hood assemblies (50-277):
Hawthorn Mfg. Co., Kansas City, Mo., on a bid of $2743.70.

For altimeters (49-2429):
Kollsman Instrument Div. of Square D. Co., Elmhurst, N. Y., on a bid of $328,427.86.

For alum. alloy—rolled shape (50-167):
Du Betta Metals Corp., Long Island City, N. Y., on a bid of $2743.

For light assemblies (50-173):
Grimes Mfg. Co., Urbana, O., on a bid of $8286.40.

For 10,000 adapter assemblies (50-199):
Companies sharing—Kings Electronics Co., Brooklyn, on a bid of $510; East Coast Electrical Supply Co., Inc., New York, on a bid of $108.80; and Deutsch Co., Los Angeles, on a bid of $1372.

For 42,735 mount insulators (50-212):
Companies sharing—Lord Mfg. Co., Erie, Pa., on a bid of $5504.30, and United States Rubber Co., New York, on a bid of $3710.99.

For clamp, clip (50-267):
Companies sharing—Breeze Corp., Inc., Newark, N. J., on a bid of $4720; Air Associates, Inc., Teterboro, on a bid of $354.05 and Adel Precision Products Corp., Huntington Division, Huntington, W. Va., on a bid of $612.51.

For transformer (50-259):
Sola Electric Co., Chicago, on a bid of $3930.

For switch generator control relay and tech. data (50-206):
Hartman Electrical Mfg. Co., Mansfield, Ohio, on a bid of $24,952.

when you're glad you have a

SPEEDS LANDING GEAR SERVICE...
and keeps 'em flying!

EXTRA powerful leverage . . . precision-built, reversible ratcheting mechanism . . . year-after-year dependability . . . these are the features you find in a Snap-on Heavy Duty Ratchet. It's husky enough to break loose the tightest of those large nuts and bolts . . . its efficient, smooth-working action helps cut "down-time" to a minimum.

When your "Snap-on man" calls with his complete line of quality tools for aviation maintenance, ask to see this ratchet and other Snap-on heavy duty tools. Available through a nationwide, direct-to-user tool service.



SNAP-ON TOOLS CORPORATION

8020-L 28th Avenue
Kenosha, Wisconsin

The Navy's AD-2 Skyraider
• The AD-2 Skyraider is the standard carrier-based attack airplane of the U. S. Navy. Now in production at Douglas Aircraft's El Segundo Plant, it is recognized as possessing the ideal characteristics for carrier operations.
...and its Oil Cooler

The Douglas AD-2 is another of the famous aircraft — both conventional and jet-propelled — which rely on Clifford Feather-Weight All-Aluminum Oil Coolers.

Superior strength-weight ratio derived from Clifford's patented method of brazing aluminum and accurate performance ratings obtained in the Clifford wind tunnel laboratory — largest and most modern in the aeronautical heat exchanger industry — account for the rapidly growing acceptance of Feather-Weight Oil Coolers.

Your inquiry is also invited. CLIFFORD MANUFACTURING COMPANY, 136 Grove St., Waltham 54, Mass. *Division of Standard-Thomson Corporation.* Offices in New York, Detroit, Chicago and Los Angeles.

CLIFFORD

HYDRON Metal Bellows

ALL-ALUMINUM OIL COOLERS
FOR AIRCRAFT ENGINES

HYDRAULICALLY-FORMED BELLOWS
AND BELLOWS ASSEMBLIES



NEW AVIATION PRODUCTS



Power Supply for Large Aircraft

Portable ground unit for Stratocruiser saves money and time and may set standard for other big planes.

A new device for big planes is solving an expensive, time-consuming problem in servicing Boeing Stratocruisers. After extensive testing, and expensive modification, it now shows promise of saving time and money for its present users —and of becoming the type of unit for any other airline using big planes.

The trend to larger aircraft over the years has been accompanied, almost unnoticed, by a proportionate growth in the size of ground power units used for line checks.

▶**Twice as Much**—But the largest capacity portable unit used until recently has generated about 1000 amps., and the Stratocruiser demands up to 2000. This brought about development of the Onan Energizer almost concurrent with first Stratocruiser operations. In effect, it is a grown-up, complex descendant of the simple, uncomplicated battery cart.

Made by D. W. Onan & Sons, Inc., Minneapolis, more than a score of these units have been bought by Pan American Airways and Northwest Airlines at a price of about $23,000 each. Despite the initial cost, Pan Am believes the trucks will be not long in paying for themselves in cutting to a minimum the time required to run major electrical system checks.

▶**First of Kind**—Since it is the first of its type and represents an almost radical departure from the typical electrical ground power unit, the Onan Energizer could reasonably be classed as an experimental model which, as experince in its use accumulates, will undergo broad modifications. Like new aircraft, it, also, has had its "bugs." But many of these already have been worked out, according to Pan Am engineers.

Reasoning that present large aircraft, such as the Stratocruiser, will become more common, and that future planes will place greater demands on ground power equipment, Pan Am believes oversize electrical power units like the Onan model are here to stay and, with improvement, will become standard fixtures at airports.

Pan American has pinpointed its Onan trucks at major terminals on its route pattern. Generally, it uses the 2000-amp. units only for servicing the Stratocruiser and Lockheed Constellation 749s. Intermediate points in the PAA system are equipped with smaller units, since extensive maintenance work is not ordinarily carried out at these places. Other Pan Am aircraft are serviced by portable power units in the 1000, 500, and 175 amp. class.

▶**Saving Time**—Since the Onan units are mobile, yet capable of delivering high amperage current, they remove the need for moving planes to maintenance docks to be serviced. And time and money are not wasted in setting up small ground units in parallel to produce the current needed.

Not only are aircraft kept out of the air longer when they are moved to a dock, but often the dock itself is not available. Pan Am, for instance, currently has only two docks for servicing its Stratocruisers at New York International Airport.

▶**Description**—The Onan truck, with a 140-hp. Hercules gasoline engine to drive two generators, one 50 kw., d.c., the other 15 kw., a.c., will supply sufficient power to the plane to start all engines, run all instruments and accessories, air-conditioning systems, the galley, heaters, interior lighting and communications system. The d.c. generator is rated at 1750 amp., 28.5v. at 1200 rmp., while the a.c. unit furnishes 60 cycle current, 120/208v. at 1800 rpm.

For continuous running, the Stratocruiser takes 1440 amp., while 1750 amp. are required when its engines are being started one at a time. Surge conditions of the plane's equipment demands 2800 amp. for momentary periods.

In addition to generators, the truck incorporates a compressed air system for inflating tires and other pressure needs, four large floodlights which fold into the roof when not in use, complete CO-2 fire extinguishing equipment, and a panel containing all meters and controls.

Machining Aid

Simple workshop unit for testing machinability of ferrous and non-ferrous metals is announced by **Vanton Equipment Corp.**, Empire State Building, New York City. Known as M.S.E. Schlesinger Machinability Tester, instrument investigates two basic characteristics of metals.

It measures "specfic cutting resistance" exerted by material against penetration of standardized kind and shape of cutting tool. This measurement is made for standardized chip area with result that unit's dial indicator reads directly in lb./.001 sq. in. Measurement of cutting resistance is a direct indication of tangential cutting force only, which, so far as power consumption of machine tool is concerned, is only force relevant.

Device also measures "abrasive effect" of same work material on hardened calibrator. This effect of abrasion is determined by measuring abraded flat on a standardized 10mm. test ball brought into contact with work material under known pressure and for given time. In this manner, actual wearing effect of work material on cutting tool is simulated on standard test ball.

"Machinability Index" is defined as machining effort, determined by multiplying measured specific cutting resistance by measured abrasion factor. These factors are reproducible under same general conditions.



Lockheed's new F-94 radar-eyed all-weather fighter is really a "double burner." In addition to the conventional jet engine, it is equipped with an auxiliary power device, the afterburner, by means of which fuel is injected into the after-section of the jet exhaust pipe where it is ignited to obtain greater thrust.

THERMOFLEX BLANKETS protect Lockheed's new F-94 "DOUBLE BURNER"

THERMOFLEX BLANKETS confine the intense heat generated within the engine cone and afterburner of the new F-94 fighter, designed by Lockheed for the U. S. Air Force.

Thermoflex Blankets were chosen because they are light in weight, are easily installed, have low thermal conductivity and high heat resistance. As used around the engine cone and afterburner of the F-94, Thermoflex Blankets are tailor-made for precision fit around controls and for mounting accessories, fuel and control lines.

One of the outstanding features of Thermoflex Blankets is that they will not "puff-up" during installation or when heat is applied. Improved production techniques now permit weights as low as 0.30 pounds per square foot and up. At 800 F mean temperature, conductivity of the Thermoflex Felt (4 lb. per cu. ft. density) is only 0.76, expressed in Btu in. per hr. per sq. ft. per degree F.

There are three basic types of Thermoflex Blankets available: (Type G) which is completely sealed in, and consists of layers of Monel screen, Inconel or stainless steel foil; (Type C) with a foil on one side only to guard against oil penetration from the cold face; and (Type CM) of a special design for guided missiles.

For additional information on Thermoflex Blankets, write Johns-Manville, Box 290, New York 16, N. Y.

Thermoflex is a Johns-Manville trademark



Type G, completely sealed, flexible Thermoflex Insulation Blanket being applied to a jet engine exhaust cone. The special grooving facilitates installation around cylindrical and conical surfaces without buckling of the inner foil.

Johns-Manville PRODUCTS for the AVIATION INDUSTRY

Packings and Gaskets • Friction Materials • Insulations • Asbestos Textiles
Transite Conduit • Transite Pipe • Industrial Building Materials



Plexiglas Reflectors

Navigation light reflectors, produced by **Southwest Airmotive Co.**, Dallas, Tex., project far enough above upper surfaces of wing tips to be easily seen from cockpit, enabling pilot to tell at quick glance whether his lights are working.

Located inboard of lights on same mount, Plexiglas units incorporate holes corresponding to those on standard wing-tip installations and can be used on several different types of aircraft. They are available in various shapes, depending on taste of individual pilot. Reflector (shown) is being installed on wing-tip of Beechcraft Bonanza.



Prop. Altitude Control

Development of Strato-Cruise control for Model F200 automatic variable-pitch propeller, suitable for aircraft powered by 65-165 hp. engines, is announced by **Aeromatic Propeller department of Koppers Co., Inc.**, Baltimore, Md.

CAA-approved device, similar to control for Aeromatic 220 prop placed on market earlier this year, enables pilot to override automatic operation of propeller and select engine speed desired for cruising at altitudes above those normally used. While also designed to supplement prop's automatic feature by assuring availability of rated rpm. of engine during takeoff and climb at any altitude up to service ceiling of aircraft, control still does not interfere with Aeromatic action at takeoff regardless of position of its cockpit control.

Device consists of cylinder housing hydraulically actuated piston which controls positioning of low pitch stop through linkage system coupled to piston and both prop blades. Installation requires use of propeller hydro-control—standard equipment on Lycoming 100 or 115 hp., and Franklin 165 hp. engines—to provide pressure oil for the system. Pilot operates unit through push-pull cable leading to cockpit knob.



Strain Recorder

Strip-chart strain recorder for use in stress analysis with SR-4 bonded resistance wire strain gages is announced by **Baldwin Locomotive Works,** Phila. 42, Pa. Features of device are easy readability with 9½-in.-wide chart scale, two chart speeds of 6 and 180 in./hr., and accommodations for a two-arm and four-arm strain bridge. Slowly varying strains can be recorded for as long as 10 days without changing chart.

Instrument is special adaptation of Leeds & Northrup Speedomax Type G, Model S recorder with simple adjustments for strain gage characteristics, strain ranges, and for Wheatstone bridge circuit. Basically, circuit is d.c. potentiometer type for measuring output of a strain gage bridge. D.C. power supply is built into recorder and voltage regulator is supplied separately.

Important feature of circuit is arrangement for directly standardizing potentiometer range in proportion to voltage which is supplied to strain gage bridge.

Circuit is adjusted by two-position bridge supply switch (3 or 6v.) and by a rheostat calibrated in gage resistance from 50 to 50 ohms. Microinch ranges of recorder are 1000, 2000, 5000, and 10,000 on 6v. bridge, and 2000, 4000, 10,000 and 20,000 on 3v. bridge. Continuous gage factor adjustment covers range from 1.7 to 2.2. Zero adjustment control and range extender switch provide approximately ±15,000 microinches per in. movement of balance point with 120-ohm gages.

Light Source

For super-brilliant light source in schlieren optical systems, shadowgraphs, interferometers, monochronometers, and high-speed photography, Ames Type-A mercury arc lamp, announced by **Huggins Laboratories,** 748 Hamilton Ave., Menlo Park, Calif., is reported to afford light intensities up to 90,000 candles per sq. cm. Shown in photo are lamp-holder with lamp extracted, and, in background, controllable a.c. power supply. Light output is 65 lumens per watt; power input 2 kw—1.2 amp. at 1750v.

Arc dimensions are 1.125 in. by 0.039 in. Cooling is accomplished with ordinary tap water (2½ gpm.). Alternately, closed-circuit distilled-water system can be used. Average life at rated maximum brilliance is 5 hr., appreciably more at reduced voltages.

Quartz accessories can be supplied for operation in ultraviolet region. Direct current, flash, and stroboscopic power supplies are under development for special applications.



Fast-Holding Light

"Self supporting" trouble light, "Henco Magnalume 300," is offered by **C. J. Hendry Co.**, Dept. AC, 27 Main St., San Francisco, Calif., for easing maintenance jobs on aircraft and in plants. Alnico V Magnet, molded into case, is deep-flux type capable of holding through thick paint and grease, with approximately 17 lb. grip.

Unit has enclosed switch, 25-ft. cord, and Neoprene rubber is used throughout to prevent deterioration in oil and grease.

Damon

TWA Says

TRANSACTION is a "sell-out." . . . conceived in secrecy and designed to further PAA's chosen instrument ambitions.

PAA IS "OPPOSED to private enterprise and the free and open competition that form the life blood of American industry."

A NEAR MONOPOLY would force TWA to the wall.

"WE ARE GOING TO WIN . . . because monopoly is not in the public interest."

Public Counsel Says

"THE FURTHER this deal goes, the worse it looks."

AOA ISN'T WEAK. There's no reason for pessimism about its future. Not necessary for AOA to sell out.

TRIPPE "is willing to go to extraordinary lengths to acquire AOA," but wasn't too enthusiastic about it last May.

TRIPPE OUT-TRADED C. R. Smith and the American board of directors in first agreement.

NOW that American's financial condition is improved, why is it staying with the deal? Is it because the directors don't want to lose face?

AA Says

CASH SALE is fresh proposition, free of any obligation to continue old contract. So contentions AA was stampeded into deal are irrelevant.

WANTED CASH all along, but Trippe still wanted to avoid cash deal when new pact was negotiated last summer. Smith insisted on "new deal."

"NO IMPELLING REASON" for AA to make bad trades with PAA, Smith told Trippe. AOA could be liquidated at a reasonable price.

HAD NO OBLIGATION to extend pact unless it was advantageous.



Trippe

PAA Says

CAB isn't a broker to get the best price. It should just see that negotiations are on the up-and-up.

AMERICAN will have no more interest in Pan American after merger than it now has. TWA will benefit by having a powerful competitor removed.

AOA STOCKHOLDERS would be more than $7 million ahead of the old arrangement . . . would get more than market price for their shares.

How Fair is PAA-AOA New Deal?

First birthday of trans-Atlantic merger case passes with TWA renewing attack on modified plan.

By Charles Adams

The "new deal" whereby Pan American Airways would purchase American Overseas Airlines' routes and assets for $17,450,000 in cash instead of nearly $19 million in PAA stock has failed to mollify bitter critics of the merger.

This month, as the so-called North Atlantic Route Transfer case became a year old, opponents of American Airlines' revised arrangement for disposing of AOA said the transaction was still a "sell-out," conceived in secrecy and designed to further PAA's chosen instrument ambitions. American and Pan American replied that their supplemental agreement (reached last September) eliminated principal objections to original pact signed Dec. 13, 1948.

▶**TWA to Win?**—TWA President Ralph S. Damon last week asserted that the near monopoly which would result from the proposed merger might easily force TWA to the wall. "But I think we are going to win this fight because monopoly is not in the public interest," Damon declared.

Coincidentally, Warren Lee Pierson, TWA board chairman, accused PAA of "being opposed to private enterprise and the free and open competition that form the life blood of American industry." Damon and Pierson made their attacks on Pan American as a Civil Aeronautics Board examiner was preparing to issue a report recommending approval or disapproval of the modified merger agreement.

▶**Stockholders Ahead**—Although AOA stockholders under the original merger pact would have received PAA stock of $18,845,000 book value, market value of the shares recently has been around $10 million. Thus the "new deal" would put AOA shareholders more than $7 million ahead of the old arrangement from a cash standpoint and would give them more than the market price for their shares.

This cash purchase price is fair to all parties concerned, Pan American declared in a supplemental brief filed with CAB. PAA added that it could consummate the transaction without adverse effect on its financial position.

▶**AOA a Loser**—According to Pan American, opposition arguments that the purchase price fails to assign any value to AOA's earning power should be discounted. AOA has not demon-

strated any ability to show earnings apart from government aid in the form of mail pay subsidy determined by the Civil Aeronautics Board, PAA declared.

Conceding that the purchase price does not take into account AOA's profits after last June, Pan American observed that this factor is balanced by omitting consideration of AOA's possible losses during the coming winter. Besides, PAA declared, it is not CAB's duty to act as a broker to secure for the seller the highest price justifiable. "The Board's responsibility is simply to see that the price was negotiated at arms' length and within the zone of reasonableness."

▶**AA Out of PAA**—Pan American emphasized that with the AOA deal now on a cash basis, American Airlines will not become a 15 percent owner of PAA stock as in the plan which was previously proposed.

TWA had objected that the stock arrangement would so join the interests of American and Pan American that they would try in every way possible to throw business to each other.

"With a cash deal, American will have no more interest in Pan American after the merger transaction is concluded than it has now," PAA declared. "TWA will thus secure from this agreement not merely the full advantage which would normally come from removal of a powerful competitor (AOA) but the special advantage of disappearance from trans-Atlantic service of the only other domestic airline (American) engaged in such operations."

▶**No Stampede**—Backing Pan American's arguments, American Airlines (62 percent owner of AOA) declared that signing of the new cash agreement in September made irrelevant contentions that AA has been "stampeded" into the original Dec. 13, 1948, pact by rumors that TWA was about to sell its trans-Atlantic routes to Pan American. Decision of American to negotiate a new AOA sale agreement on a cash basis was made as a fresh proposition free of any obligation to continue the old contract which expired in September, AA officials declared.

American said it wanted cash for AOA all along but indicated that a year ago banks were so cool toward airline loans that Pan American couldn't raise the money required. In negotiating the new pact last summer, PAA President Juan Trippe still wanted to avoid a cash deal; but American Airlines President C. R. Smith insisted on the "new deal."

Smith said he told Trippe: "We have no obligation to extend this transaction unless we think it to be advantageous to us and unless the price is a fair one. If we don't like the proposition you put forth for the extension, we (AOA) can remain in business and, I believe, do fairly well.

▶**No "Fire Sale"**—"If we want the AOA certificate extended after 1952, we will have a fair chance (of succeeding). If the certificate isn't extended after 1952, I think the company (AOA) could be liquidated at a reasonable price, so there is no impelling reason for us to make any bad trades with you."

CAB public counsel, who ripped into the original merger proposal (AVIATION WEEK, Aug. 15), also flayed the new agreement, declaring "the further this deal goes, the worse it looks." They said that Smith's blunt statement to Trippe last summer confirmed their findings that AOA is not a weak carrier; that there is no reason for pessimism about its future; and that it is not necessary for AOA to sell out to Pan American.

▶**Trippe So Willing**—"Trippe, who was portrayed in the first hearing (last May) as not very enthusiastic about acquiring AOA, is now revealed to be willing to go to extraordinary lengths to accomplish that objective. The fact that Trippe is ready to incur a substantial additional indebtedness to acquire AOA—an indebtedness that is bound to weaken his company—demonstrates again that he is motivated not by business considerations but by a desire to expand the power and influence of Pan American."

In the first agreement, Trippe badly out-traded Smith and the whole American board of directors, public counsel asserted. "AA, in a mood of panic, not only agreed to accept PAA stock but agreed to take it six points above the market.

▶**Passing Mood**—"A year later this mood had passed," public counsel continued. "American had earned $6 million on its domestic operations in the first nine months of 1949 and AOA's financial position improved. Why, then did American's directors decide to stay with the deal even on improved terms? Most likely explanation is that, convicted of bad judgment (in the first deal late in 1948), they felt they could not withdraw without losing face."

American Export Lines, founder of American Overseas and holder of 20 percent of its stock, believes that even under the new cash arrangement American Airlines is proposing to sell a going and profitable concern at a "distress price." The steamship operator accused Smith of acting "in breach of his duties and in violation of American Export's rights."

Echoing CAB public counsel, former CAB Chairman James M. Landis, representing a group of AOA employes, said the new cash agreement for selling AOA resulted because "the (C. R.) Smith of August, 1949, was not the frightened Smith of November and December, 1948, when he feared a TWA sell-out to PAA."

TWA asserted that the PAA-AOA agreement terms were modified because Pan American realized that the merger, as originally set up, would never be approved by CAB. "The change is a smokescreen to cover objections to the merger, which would place U. S. international air commerce in monopolistic hands."

Nonskeds After '50 Atlantic Traffic

Irregulars seek special exemptions to handle record boom forecast in flying student group and pilgrims.

Uncertificated carriers are making plans to tap the record passenger air traffic expected to cross the North Atlantic next year.

Barred from nonscheduled international passenger operations since September, 1947, the uncertificated lines hope the Civil Aeronautics Board will grant them special exemptions (similar to those issued last summer) authorizing carriage of students to Europe. They also want permission to fly groups of Holy Year pilgrims to Rome under contract.

Seaboard & Western Airlines has formally requested special exemptions for the 1950 flights from CAB. Transocean Air Lines and other carriers may follow suit. Certificated U. S. trans-Atlantic flag lines, which last summer opposed issuance of exemptions to the independent operators, probably will make a fight against the new applications.

CAB last June authorized S&W to make 35 roundtrips and Transocean 44 roundtrips between the U. S. and Europe, carrying student groups eastbound under contract with Youth Argosy, Inc., and displaced persons on many of the westbound flights. Other uncertificated companies, including Trans Caribbean Air Cargo Lines, Alaska Airlines, Coastal Air Lines and the Flying Tiger Line, were permitted to make passenger trips to Israel and Rome.

▶**Big Business Ahead**—Youth Argosy, Inc., a non-profit, educational group organized to further international goodwill by encouraging interchange of students, has already received over 17,000 requests for transportation to Europe next year. S&W, which flew about 2150 passengers between the U. S. and Europe under last summer's contract

with Youth Argosy, wants authority to carry a maximum of 10,000 persons each way in 1950.

Transocean and S&W this year offered Youth Argosy roundtrip U. S.-Europe transportation at between $300 and $315 per person. Regular roundtrip airline fare between New York and London is $630, although the scheduled carriers also have a 60-day roundtrip winter excursion at $466.70 and recently proposed a 15-day-limit, off-season rate of $385.

▶ **Nonskeds May Up Rates**—Rates offered by the uncertificated carriers next year may run slightly higher than in 1949, but they will still be under the regular flag carriers' least expensive excursions. S&W claims the scheduled operators will have all the traffic they can handle next year and will not be affected adversely by the Youth Argosy deal, especially since the students can't afford to travel by air at the higher regular rates.

The Youth Argosy program has received support from both the United Nations and Economic Cooperation Administration, according to S&W. DC-4 flights would originate in New York and go to Shannon, London, Paris, Brussels, Rotterdam, Geneva and Rome.

▶ **Pilgrimage Bonanza**—Seaboard & Western also wants CAB to grant an exemption permitting the carrier to contract with Holy Year Pilgrimages, Inc., and other Catholic organizations for transportation of pilgrims between the U. S. and Italy with a minimum frequency of one roundtrip every ten days. Holy Year Pilgrimages, Inc., is a nonprofit corporation formed for the primary purpose of arranging low-cost transportation to Rome.

Over a million persons are expected to travel between North America and Rome during 1950, according to Seaboard & Western. It told CAB that steamship transportation already is booked solidly to Europe through next summer.

TWA, only U. S. flag line certificated for regular service to Rome, takes an especially dim view of Seaboard & Western's Holy Year ambitions. This month TWA urged CAB to revoke the independent operator's letter of registration as a large irregular carrier for "deliberate and flagrant violations of the law."

CAB now has before it less severe examiners' recommendations that both S&W and Transocean be ordered to cease and desist from further illegal activity, including common carriage of passengers on international flights.

nearly all major airlines use EDISON Fire Detection

Edison Systems also approved by the U. S. Air Force and U. S. Navy, and conform with CAA requirements.

note to aircraft engineers

In addition to providing the ultimate user the utmost in simplicity and dependability, Edison Fire Detection offers definite advantages to the aircraft engineer. In proving prototype installations, for instance, the Edison System acts as its own instrumentation. Since the Edison Detectors are thermocouples, no test instrumentation need be mounted in the fire zones. Readings of thermocouple output under various temperature conditions in the fire zone during test flights or ground run-ups can be taken directly.

Edison offers the services of experienced field engineers for supervision of thorough prototype testing, to aircraft manufacturers, without charge.

Remember—an Edison Fire Detection System, properly installed, CANNOT false alarm.

180 LAKESIDE AVENUE, WEST ORANGE, NEW JERSEY

INSTRUMENT DIVISION
THOMAS A. EDISON,
INCORPORATED

Coast Tangle

Local and federal groups probe legality of coach services.

The stiff competition for air coach traffic over the busy Los Angeles-San Francisco route has wound up in a legal snarl.

Western Air Lines of California, Inc., a new corporation set up last August, is under especially severe attack for allegedly illegal activity. But other uncertificated carriers flying the link also are being investigated.

United Air Lines made the first public complaint against Western of California, charging that circumstances surrounding creation of the company indicate that it is "a mere agency or instrumentality of Western Air Lines." UAL said that Western thus may be violating the Civil Aeronautics Act by failing to seek approval of its relationship with the intrastate operator and failing to file reports, schedules and tariffs.

▶ **Injunction Asked**—Soon after the United protest, three uncertificated operators which had been in the Los Angeles-San Francisco coach business before Western of California, filed a complaint in Los Angeles County Superior Court. The complainants, California Central Airlines, Arrow Airways and Robin Airways, asked for a restraining

order and injunction against Western Air Lines and Western of California.

It was then learned that the Civil Aeronautics Board, which had been watching the situation closely for months, had stepped into the melee officially.

The federal agency, taking action independently, instituted four investigations to determine whether there are illegal relationships between Western Air Lines and Western Air Lines of California; between California Central Airlines and Airline Transport Carriers, Inc.; between California Arrow and Arrow Airways, Inc.; and between Robin Airways, Inc., and Robin Airlines, Inc.

Airline Transport Carriers, Arrow Airways and Robin Airlines are all large irregular carriers which have been active on the transcontinental route. CAB indicated that these companies, like Western Air Lines, may have violated the Civil Aeronautics Act by failing to file agreements made between the interstate carriers and their intrastate counterparts (if that is what they actually are), and by maintaining interlocking relationships and control arrangements without prior Board approval.

▶ **Company History**—Western Air Lines of California began Los Angeles (Burbank)-San Francisco (Oakland) flights last Aug. 19 operating 73-passenger DC-4s and charging $9.95 one way, about the same fare as the complaining independent intrastate carriers. Planes and facilities of WALC are leased from WAL, which also sells tickets for the intrastate line.

WAL refuses to comment officially on its corporate relationship with WALC. But WAL has announced that the intrastate operation has been a profitable one, carrying 40,000 persons between Los Angeles and San Francisco in the past three months with a better than 80 percent average load factor during this time.

▶ **Damage Alleged**—Hurt by WALC's competition, the three independent operators reportedly have filed suit for a total of $350,000 damages from Western and its alleged intrastate affiliate. The independents charge that WAL and WALC have violated California's Unfair Trade Practices Act and are engaging in a conspiracy to drive the smaller lines out of business in violation of the state's anti-trust laws.

Both United Air Lines and the independents allege, in effect, that Western of California is a paper organization set up by WAL and headed by a member of WAL's law firm.

Western of California operates three or four roundtrips daily between the Los Angeles and San Francisco areas at its $9.95 (three cents a mile) fare. Regular airline rate is $21.05.

Castings of Wright quality now available...

Wright Aeronautical offers manufacturers complete foundry facilities for producing Aluminum and Magnesium Castings

Wright Aeronautical now provides complete foundry facilities to manufacturers in need of high-quality aluminum and magnesium castings. This quality is assured because . . .
(1) Our foundry has specialized in the production of lightweight, top quality castings for aircraft engines for 27 years.
(2) Our skilled inspectors maintain a rigid control on quality through full metallurgical analysis and precision inspection of all casting fabrication.
This modern foundry has the capacity and equipment to make castings in almost any desired quantity, size, type or design, however intricate.

Wright Aeronautical Foundry Offers

1. A complete wood and metal pattern shop equipped to handle the most intricate foundry patterns.
2. A materials laboratory for testing and approving all materials used in casting fabrication.
3. Equipment for handling both *green* and *dry* sand castings.
4. Accurate temperature control during melting and pouring.
5. Precise dimensional and finish inspections, utilizing Fluoroscope, X-ray and other precision tools.
6. Complete equipment for heat-treating finished castings.
7. Facilities for all surface treatments—anodizing, dichromating, impregnating, and painting.
8. Prompt deliveries and competitive prices.

For further particulars, write Dept. AW4, Industrial Sales Department.

WRIGHT

A DIVISION OF CURTISS WRIGHT
FIRST IN FLIGHT
AERONAUTICAL CORPORATION
WOOD-RIDGE • NEW JERSEY

WORLD-WIDE distributors of multi-engine transport type aircraft, engines, their components and accessories.
Agent for WAR ASSETS ADMINISTRATION.
Write, wire or telephone your requirements.

EXPORTERS AIRCRAFT·ENGINES COMPONENTS
FRANK AMBROSE AVIATION COMPANY

General Offices and Export Department:
34-17 Lawrence Street, Flushing, L.I., N.Y.
West Coast Office: Oakland Municipal Airport, Oakland, Calif.
Canadian Office: Frank Ambrose Aviation (Canada) Ltd.,
Dorval, P.Q., Canada
Panama Office: Frank Ambrose Aviation, S.A.,
Calle Segunda No. 3, Panama City, R.P.
Established 1923 *Cable Address: AIRAMBROSE* *U.S. Export License No. 191*

FLEXLOC

SELF-LOCKING NUTS

FOR THE AIRCRAFT INDUSTRY



Pat'd & Pats. Pend.

Whether it's mass production of popular light planes, air transports, or building of experimental planes for the Army and Navy, reliability of construction is a must. FLEXLOC, with its resilient, flexible segments comprising the "self-locking" feature, won't shake loose even under the most chattering vibration. And FLEXLOC has unusually uniform torque—within a few "inch lbs.". Made in one solid piece, FLEXLOC is a stop, a lock and plain nut all in one, and is available in "thin" types as well as the "regular"—in NC and NF thread series.

ACCEPTANCES: FLEXLOC is officially approved and accepted by many U.S. departments, bureaus, agencies, and the CCA.

Write for your copy of the FLEXLOC Catalog.

SPS STANDARD PRESSED STEEL CO.

BOX 566, JENKINTOWN, PENNSYLVANIA

TO PILOTS OF TWO-PILOT AIRCRAFT, AND AIRCRAFT RADIO SYSTEM ENGINEERS



NEW FREEDOM OF CONTROL

LESS PILOT FATIGUE

with the Type F-11 Isolation Amplifier

CAATC No. 1R4-1

The new A.R.C. Isolation Amplifier performs two important radio control functions that have long presented problems. (1) Each pilot has **independent** selection of up to ten audio input channels in **any combination**—without cross-cockpit interference. Radio functions may be delegated so that each pilot works at peak efficiency in complex navigational and communication situations. (2) It operates individual cockpit speakers, with earphones instantly available if desired. Since the CAA no longer requires wearing of headphones when cockpit speakers are installed, the A.R.C. Isolation Amplifier relieves pilots of considerable discomfort and fatigue—particularly in hot weather and on long flights.


No cross-cockpit interference.
Selection of up to 10 channels for each pilot.
Earphones instantly available if desired.
Individual speaker operation for pilot and co-pilot.

Weight: 8 lbs. CAA Type-Certificated. Immediate delivery in 14 or 28 volt dc models. Complete technical details on request.

ARC Aircraft Radio Corporation

BOONTON, NEW JERSEY

DEPENDABLE ELECTRONIC EQUIPMENT SINCE 1928

Low Fare Encouraged At IATA Sessions

(*McGraw-Hill World News*)

MEXICO CITY—Two important changes in international airline rates and fares for 1950 were effected by the 15-day International Air-Transport Assn. traffic conference.

Special fares to promote off-season travel, including a special North Atlantic round-trip rate of $385 on traffic originating in North America, to be effective between Jan. 1 and Mar. 15. This is by far the lowest fare in history on the Atlantic air crossing.

Fares on flights in Europe and the sterling area generally will also fall to a new low level as the sterling area lines persisted in their refusal to raise rates to compensate for devaluation. Final solution of this problem called for only slight increases over the devaluation rate on all flights in areas devaluating. Flights in dollar territory will be raised to compensate for devaluation when fares are sold in devalued currency.

▶ **"Bold Experiment"**—E. C. Cocke, vice president of TWA and chairman of the conference called the new special off-season trans-Atlantic fare "a bold experiment to determine whether we can break the historical seasonal trend."

"This fare represents a determined effort on the part of the trans-Atlantic airlines to develop off-season tourist traffic to Europe," he said. "On the one hand we want to encourage the flow of hard dollars abroad. On the other hand, we think we have something unusually attractive for the wage-earner with the two weeks vacation."

The new winter trans-Atlantic rate is only one and one-tenth times the ordinary fare one way. The regular fare on the North Atlantic crossing is $350 while the special winter excursion fare will be only $385 for the round trip. This is for the New York–London flight, and will be in effect from Jan. 1 to Mar. 15. It will be good for only 15-day round trip flights, and departure from Europe must be made no later than Mar. 31. CAB announced it would approve the special excursion fare.

▶ **More Fares**—The IATA conference also approved special off-season fares over the South Atlantic, new fares from Australia and New Zealand to Singapore and Rome, and "early bird service" from Eire to the United Kingdom. Special discounts were also voted on inclusive tours within Europe.

The battle over fares in countries where devaluation had, in effect, given them a slash of 40 percent was won by the sterling countries who stood firm in their refusal to raise fares to compensate for this devaluation. They pointed

out that such increases would frustrate the aim of devaluation.

However, they agreed to slight increases to cover costs on purchases made in the dollar area, such as spare parts from U. S. manufacturers.

The agreement stated that fares for flights in dollar areas, if sold in devalued currencies, would be increased, while fares for flights in sterling areas would be allowed to stay at the new devaluation figures. U. S. airlines have to cut their fares on flights within Europe and the Middle East in terms of dollars. They will remain the same, with slight increases, in devalued currency.

CAB Reports on One Crash; Sifts Another

The Civil Aeronautics Board this month completed its report on the scheduled airlines' first fatal accident of 1949 but it was forced to keep its top investigators in the field probing the cause of the year's third major mishap —the American Airlines DC-6 crash at Dallas.

Confirming preliminary findings, CAB officially blamed the Navy pilot for the midair collision of a Grumman Hellcat fighter and an Eastern Air Lines DC-3 near Fort Dix, N. J., last July 30. The Board said the Navy pilot was guilty of reckless conduct in performing acrobatic maneuvers on a civil airway and of failing to notice the presence of the airline transport with which he collided.

All 15 occupants of the DC-3 and the F6F pilot were killed. Both aircraft were destroyed. Prior to the collision, the fighter "buzzed" a Piper Super Cruiser, coming within 100 ft. of the lightplane and sending it momentarily out of control.

▶ **Program Launched**—CAB noted that the Civil Air Regulations, which also apply to military aircraft, forbid acrobatics on any airway at any altitude. As a result of this accident and similar mishaps, CAB, CAA, the Navy, Air Force and other agencies have launched an intensive program for apprehension of Civil Air Regulation violators, particularly those guilty of buzzing and reckless flying.

American Airlines' Dallas accident resulted in 28 deaths, bringing total scheduled air carrier fatalities this year to 89 passengers and nine crew personnel. Last year, there were 83 passenger deaths in four fatal accidents; but because of increased traffic the 1949 fatality rate per 100 million passenger-miles flown may still be under that of 1948.

The AA DC-6, bound from New York City to Mexico, crashed while landing at Love Field, Dallas. It hit buildings at the edge of the field and burst into flame. Preliminary indications were that one engine went bad during the flight and a second quit during final approach.

O'Connell Decries Agency Merger Plan

Too many doctors are taking the pulse of the air transport industry, according to Civil Aeronautics Board Chairman Joseph J. O'Connell, Jr., who has warned against new plans to merge functions of his agency into an over-all federal transportation setup.

Failure to maintain, at least temporarily, the independence of aviation agencies might have tragic consequences for the future of aviation, O'Connell declared. "The inevitable result of merging aviation into a regulatory or promotional pattern with other forms of transportation would mean that the rate of aviation development and promotion would be seriously retarded."

▶ **Over-Conservatism Seen**—The CAB chairman said an overall transportation agency would be criticized brutally for any action it took to change the status quo.

He added that government officials heading an integrated transporta-

Hamilton

World's Largest Airline Tailors

OFFICIAL AIRLINE UNIFORMS

For Men and Women

Hamilton Airline Uniforms are custom tailored to individual measure to Airline specifications.

Hamilton Tailors are the accredited suppliers to:

AMERICAN AIRLINES
CAPITAL AIRLINES
CHICAGO & SOUTHERN AIRLINES
DELTA AIRLINES
EMPIRE AIRLINES
EASTERN AIRLINES
MIDCONTINENTAL AIRLINES
NORTHWEST AIRLINES
PHILIPPINE AIRLINES
PIEDMONT AIRLINES
TRANS WORLD AIRLINES
UNITED AIRLINES
and others

"If it's Hamilton-tailored you know it's right!"

THE Hamilton TAILORING CO.

Columbia Parkway at Pike • Cincinnati 2, Ohio

VHF COMMUNICATION and LF NAVIGATION SYSTEMS

meet every Operational Need

THE A.R.C. TYPE 11A

Meets basic needs by providing for VHF Transmission, LF Range Reception and Rotatable Loop Navigation.

THE A.R.C. TYPE 17

A 2-way VHF equipment, including a tunable VHF Receiver and a 5-channel, crystal controlled VHF Transmitter.



THE A.R.C. TYPE 12 (Above)

Combines the advantages of the Type 11A and the Type 17, offering 2-way VHF, together with LF Range Reception and Rotatable Loop Navigation.

All units of these systems have been Type-Certificated by the CAA. For the highest standards of design and manufacture and the finest in radio equipment, specify A.R.C.

ARC Aircraft Radio Corporation

BOONTON, NEW JERSEY

DEPENDABLE ELECTRONIC EQUIPMENT SINCE 1928

tion setup would thus be inclined to steer clear of moves (however beneficial) that threaten existing investments and markets.

O'Connell emphasized that in the not too distant future air transportation must exist entirely on its own abilities without benefit of direct or indirect governmental support. "But to attempt to bring this situation about at the present time would mean a long delay in the full realization of a new resource."

▶ **Report to Truman**—The CAB chairman said he was not attempting to second-guess the Commerce Department, which is preparing a report to the President on transportation policy. The report is expected to recommend establishment of a central policy board to coordinate federal programs affecting air, rail, water and highway transport.

O'Connell conceded that it might be advisable to set up a government committee which would be a forum for the periodic interchange of views on various broad policy questions affecting more than one type of transportation. He said, however, that he did not think such a committee should attempt to be an arbiter between the various forms of transportation on questions involving major policy conflicts since that is in the province of Congress and the President.

ALSSA Pay Upped

Air Line Stewards and Stewardesses Assn. reports it has established the highest wage scales for hostesses and pursers in the industry through a new agreement with TWA covering 550 employes.

Revised wage scale for hostesses flying in the U.S. ranges from $185 monthly to start to $265 after seven years service. International hostesses will go from $200 to $295 monthly over a seven-year period; while flight pursers will earn $55 monthly to start and $355 after four years.

Average wage increase in all categories is about four percent. ALSSA is an affiliate of the Air Line Pilots Assn. (AFL).

Seek Wage Hike

The CIO Transport Workers Union has launched its 1950 contract drive by asking Pan American Airways and American Airlines for 20-cents-an-hour pay increases for 9000 ground employes.

TWU officials said present wages of the American Airlines workers average $1.72 hourly; while PAA ground employes receive about $1.65 an hour. Besides the wage hike, TWU wants new contracts starting Jan. 1 to include: a reduction in the work week from 40 to 35 hr.; improved pensions; three weeks vacation after five years service and four weeks after ten years; and increased pay differentials for the swing and midnight shifts.

LAA Cargo Zooms

Los Angeles Airways, the nation's first certificated helicopter mail carrier, flew sharply-increased loads during its second full year of operations ending Oct. 1.

Pound-miles jumped from 40,983,528 the first year to 83,840,073 in the second—a 105 percent gain. Pounds carried increased from 1,864,904 to 4,116,704—up 121 percent; and letters handled soared from 65 million to 145 million.

Operating five Sikorsky S-51 heli-



Where to Buy
PRODUCTS - SERVICES
ACCESSORIES

AVIATION INSURANCE
BROKERS: We invite your inquiries.
AIRCRAFT OWNERS or OPERATORS: Have the Broker or Agent of your choice contact us regarding your insurance problems, or write direct to us. No risk too large, none too small.
SOUTHEASTERN AVIATION UNDERWRITERS, INC.
308 Trust Co. of Ga. Bldg., Atlanta 3, Ga.

copters, LAA during the year ended Oct. 1, 1949, flew 5676 hr. and 355,024 mi. with an average schedule completion of 96.15 percent. Aircraft utilization averaged 101.2 hr. monthly.

SHORTLINES

▶ **Bonanza**—Hopes to start regular DC-3 feeder service between Reno, Nev., and Phoenix, Ariz., via Las Vegas and other points around Dec. 16.

▶ **Colonial**—Is considering acquisition of an all-cargo plane because of rapidly increasing freight traffic which rose 279 percent in the first nine months of this year over the same 1948 period. Company officials say rail freight rate increases helped spur air cargo volume.

▶ **Compania Cubana de Aviacion**—The Cuban company has asked CAB for a foreign air carrier permit to operate between Havana and New York via Washington.

▶ **Helicopter Air Service**—CAB has proposed a mail rate of $1.35 a plane-mile for the company's Chicago area operations between Aug. 20, 1949, and Feb. 28, 1950; and $1.15 a plane-mile for operations starting next Mar. 1.

▶ **Island Air Ferries**—The Bohemia, Long Island, N. Y., company has asked CAB for a certificate to carry passengers, property and mail between Miami and Grand Bahama Island, British West Indies, via West Palm Beach. Firm owns two DC-3s, according to Frederick H. Smith, president. A similar application has been made by Imperial Airways, Miami, which proposes using C-46s for the run. Imperial is headed by Arthur S. Clark, Jr., but Hugh Fenwick owns all of the company's stock.

▶ **Lineas Aereas Costarricenses**—The Costa Rican carrier has asked CAB for a foreign air carrier permit to operate between San Jose and Miami. Company's capital stock is owned 60 percent by citizens and government of Costa Rica and 40 percent by Pan American Airways. Costa Rican government has designated the company as the national flag carrier for operations to Miami. Use of DC-3 and C-46 equipment is contemplated.

▶ **Mid-Continent**—Reports a $44,536 net profit in October against $28,342 profit in the same month last year. Operating revenues increased five percent.

▶ **Pan American**—Travelers from Latin America flying to Europe via PAA may now stay overnight in New York as guests of the carrier before continuing their trip. . . . Company has inaugurated thrice-weekly service between New York and Nice, France. . . . PAA flew 17,000 passengers in its Stratocruisers during the planes' first six months of service ending Dec. 2. The Boeings are on Pan Am's New York-London-Frankfurt and New York-Bermuda links.

▶ **Showalter Corp.**—The Winter Park, Fla., fixed base operator has asked CAB for a certificate to conduct scheduled service from Orlando to Jacksonville, Tallahassee, Tampa and Palm Beach via intermediate points.

▶ **South Central Air Transport**—Raymond J. Ellis, president of the Fayetteville, Ark., company, has asked CAB for a certificate to operate feeder routes between Tulsa and Memphis; Joplin, Mo., and Dallas; Oklahoma City and Memphis; and Springfield, Mo., and Jackson, Miss., via intermediate points.

▶ **Trans Caribbean Air Cargo Lines**—Has been ordered by CAB to show cause why its letter of registration as a large irregular carrier shouldn't be revoked for knowing and wilful violations of the Civil Aeronautics Act. Board enforcement attorneys claim Trans Caribbean has been operating with excessive frequency and regularity from New York to Miami and Puerto Rico despite a cease and desist order issued in March, 1947.

▶ **United**—Has started a newspaper advertising campaign comparing the economy of air travel with newly-increased Eastern railroad fares. . . . UAL predicts the heaviest Christmas cargo traffic in history and will have 610,000 lb. of daily lift capacity available to handle it.

▶ **U. S. Airlines**—Eastern Air Lines has complained to CAB that the certificated all-cargo carrier is inviting a freight rate war by proposing new rates averaging 17 cents a ton-mile. EAL said U. S. had operating expenses of 62.3 cents a revenue ton-mile and revenues of only 18.4 cents in the third quarter of 1949.

CAB SCHEDULE

Dec. 12—Hearing in Western-Inland mail rate case. (Docket 2870)

Dec. 19—Hearing in Florida Airways mail rate case. (Docket 3695)

Jan. 4—Hearing on renewal of Trans-Texas Airways' feeder certificate. Postponed from Dec. 6. (Docket 3720)

Jan. 4—Hearing on transcontinental coach service. Postponed from Nov. 28. (Docket 3397 et al)

Jan. 9—Hearing in New York area helicopter case. (Docket 946 et al)

Jan. 9—Hearing on air freight accumulation, assembly and distribution tariffs. (Docket 1705 et al)

Jan. 9—Hearing in Cuba-Florida foreign air carrier permit case. (Docket 3717 et al)

Jan. 17—Hearing in National Airlines route transfer case. Postponed from Jan. 4. (Docket 3500)

Jan. 24—Hearing on CAB's enforcement action against Meteor Air Transport. (Docket 4100)

Feb. 6—Hearing in Colonial Airlines mail rate case. (Docket 2724)

Feb. 13—Hearing in West Coast Airlines' certificate renewal case. (Docket 3966)

SEARCHLIGHT SECTION

(Classified Advertising)

EMPLOYMENT • BUSINESS EQUIPMENT — USED OR RESALE OPPORTUNITIES

UNDISPLAYED RATE

90¢ a Line, minimum 4 lines. In making advance payment, count 5 average words as a line.

Individual Employment Wanted—Advertising rate is ½ the above rates payable in advance.

Box Numbers—Care of publication, New York, Chicago or San Francisco offices count as one line additional.

Discount of 10% if full payment is made in advance for 4 consecutive insertions.

DISPLAYED RATE

Individual Spaces with border rules for prominent display advertisements.

The advertising rate is $10.00 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

An advertising inch is measured ⅞" vertically on one column, 3 columns—30 inches—to a page.

HELICOPTER PILOTS

United Helicopters, Inc., can place several helicopter pilots in both foreign and domestic service with our distributors and customers. Pilots must have excess of 100 hours helicopter time. Applicants contact

UNITED HELICOPTERS, INC.
1350 Willow Road Palo Alto, Calif.

REPLIES (Box. No.): Address to office nearest you
NEW YORK: 330 W. 42nd St. (18)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITION VACANT

WANTED AN Experienced Sales Manager for accessory manufacturer in Middle West. Excellent opportunity for right man with sales engineering experience. Initiative and ability to sell of paramount importance. Our employees know of this ad. Complete details of experience required. P-1656, Aviation Week.

POSITIONS WANTED

PILOT-SALESMAN, 19 years diversified aeronautical experience. Commercial S.E. & M.E. land, sea, instructor and instrument ratings. 5700 hours accident free. 7 years Senior Pilot, U.S.A.F., Domestic & Foreign flying. 1 year Military Test Pilot. 3 years Aircraft Sales Manager, 2 years Chief Pilot, Domestic-Flying Airline, 6 years Charter, Instruction flying. Desire position with a future utilizing sales and flying experience, or flying exclusively. Excellent references. Complete resume sent to interested parties. PW-1573, Aviation Week.

AERONAUTICAL ENGINEERING Student available after Graduation, Dec. 16, wishes to obtain experience with research or design group. Will consider all offers. PW-1634, Aviation Week.

PILOT-ENGINEER with airline-airport engineer administrative, construction, and general aviation experience totalling 14 yrs. wishes position in aviation field where piloting and engineering experience helpful. Aircraft operations, administration, airline or sales considered. PW-1574, Aviation Week.

A AND E Mechanic licensed 18 years with over 20 years experience as flight engineer, mechanic and supervisor in overhaul, maintenance and service of U. S. aircraft in foreign operation desires position as co-pilot mechanic on executive or prive transport. Recent commercial pilot's license. Age 36, well educated, tetralingual and with unusual background of successful foreign personnel relations. Free to travel and will go anywhere. Additional information furnished on request. PW-1627, Aviation Week.

AIR PILOT, 35, 10 years military and airline flying. Currently employed major airline but desire work as Company pilot. PW-1576, Aviation Week.

BUSINESS OPPORTUNITY

New Design

One Piece Lock Nut available for manufacture by hot forging process. Nut is light weight, heat resistant, suitable for aircraft use. F. H. Goosmann, M. R. 60, Box 139, Hamilton, Ohio.

FOR SALE

Hoving and Lapping Machine

Vacuum and hydraulic pump test stand. Both factory new. Boxed for export. Immediate delivery. FS-1633, Aviation Week.

GIGANTIC BID SALE

LARGEST OF ITS KIND—OPEN TO THE PUBLIC
TRAINLOAD W.A.A. RELEASED SURPLUS
AIRCRAFT COMPONENTS—MATERIAL—EQUIPMENT—ENGINES
MORE THAN 200 LOTS

Douglas C-47, C-54 and B-25 components and airframe parts. Also, components and airframe parts for twin and stagger-wing Beechs, twin Cessnas and other aircraft

✦ ALSO ✦

Wheels—Landing Gears—Brake Assemblies—Hamilton Standard and Curtiss Electric Propellers and miscellaneous parts

✦ ALSO ✦

Generators—Starters—Voltage Regulators—Relays—Switches—Armatures—Carburetors—Magnetos—Ignition Harness—Sparkplugs—Pumps—Valves—Bearings—Instruments—Instrument parts—Testing Equipment—Special Aircraft Tools—Special Engine Tools—Pratt and Whitney Engine Tools—Wright Engine Tools—Hangar Equipment

✦ ALSO ✦

Pratt and Whitney—Wright—Continental and Jacobs Engine Parts—and many other items

✦ ALSO ✦

LOTS CONSISTING OF THE FOLLOWING AIRCRAFT ENGINES

PRATT AND WHITNEY		WRIGHT	LYCOMING
R-985	R-1830-90C	R-1820-71	O-235-2
R-1340	R-1830-90D	R-1820-87	R-680-8
R-1830-43	R-1830-92	R-1820-97	R-680-9
R-1830-65	R-1830-94	R-1820-G205	R-680-13
R-1830-82	R-2800-8, -10, -43, -51 and -75-	R-2600-8	R-680-17
R-1830-90B			

CONTINENTAL: R-670-5, R-670-11
JACOBS: R-755-9 AND OTHERS

FURTHER ANNOUNCEMENTS WILL FOLLOW • WRITE FOR BROCHURES
BIDS WILL BE OPENED 10:00 A.M., JANUARY 24, 1950

PAGE AIRCRAFT INDUSTRIES
CIMARRON FIELD (20 Miles West Oklahoma City)
P. O. Box 535 Phone 9-7388 Oklahoma City, Oklahoma

AIRCRAFT & ELECTRONIC EQUIPMENT

As a leading supplier we offer a complete line of

BRAND NEW INSTRUMENTS

- FLIGHT & NAVIGATION INSTRUMENTS
- ENGINE INSTRUMENTS
- AUTOMATIC PILOTS
- INVERTERS
- AUTOSYNS
- PRECISION AUTOSYNS
- RATE GENERATORS
- SYNCHROS
- ALNCO FIELD MOTORS
- GYROS
- A.C. MOTORS
- D.C. MOTORS
- SERVO MOTORS
- TORQUE UNITS
- TORQUE AMPLIFIERS
- FREQUENCY METERS
- BLOWER ASSEMBLIES

Write for complete listings
All Instruments May Be Purchased C.A.A. Certified
U. S. Export License-2140

WUX Great Neck, N. Y.
INSTRUMENT ASSOCIATES
37 E. Bayview Ave., Great Neck, N. Y.
Tele: IM perial 7-1147

WAR SURPLUS SALE

• By Competitive Bid • Mostly New • Approx. $4,000,000.00 Govt. Cost • Approx. 30 Carloads • No Restriction as to Use

DOUGLAS AIRFRAME PARTS—C47, C53, C54.
ENGINE PARTS & TOOLS—P & W, Wright, Lycoming, etc.
PROPELLERS, GOVERNORS, & PTS. — Ham. Std., Curtiss, AN, etc.
STARTERS, GENERATORS, REGULATORS, & PTS.—Eclipse, J&H, G.E., L.N., etc.
MAGS, HARNESS, DISTRIBUTOR, & PTS.—Scintilla, Am. Bosch, Titeflex, Breeze.
CARBURETORS & PTS.—Stromberg, Holley; INSTRUMENTS—Engine, Flight, Nav.
PUMPS & PTS.—Fuel, Hyd., Vac., Prop Feathering, Anti Icer, etc.
MISCELLANEOUS — Unserviceable Parachutes, Jacks, Heaters, etc.

To insure your receiving Sales Brochure & Bid Forms contact:

MAXWELL ASSOCIATES, INC.
230 West "A" Street Wilmington (Los Angeles Co.), Calif.
BIDS WILL BE PUBLICLY OPENED DEC. 27, 1949.
P.S. We're not quitting business; we're just tightening our belts.

TEMPLATES

Are your template costs too high?
Try us—We'll Cut Them
Templates Are Our Specialty
G&T ENGINEERING CO.
P. O. Box 913 Bridgeport, Conn.

WANTED

• FOR SALE •

130
BRAND NEW
BC 733D
LOCALIZER RECEIVERS

ELECTRO IMPULSE LABORATORY
P. O. Box 250 Red Bank, N. J.
Eatontown 3-0768

R-985-AN 14 B

No Time Since CAA Overhaul

LBS AIRCRAFT CORP.
P.O. Box 1255
Miami Springs, Fla.
Hangar #2 — International Airport

AIRCRAFT MATERIAL WANTED

R2000 & R2800 P&W engine parts & accessories Douglas C47, C54 & A26 airframe parts; Curtiss C46, Beech AT11 & NAA AT6 & P51 parts; Generators, starters, instruments, landing gear assys., AN fittings & hardware, electrical items, valves, spark plugs, gas caps, bearings, pulleys, etc.
COLLINS ENGINEERING COMPANY
9054 Washington Blvd. Culver City, Calif.

SCHOOLS

Rising Sun *SCHOOL OF AERONAUTICS*
ESTABLISHED 1930
"Built Upon the Success of Its Graduates"
GOVT. C. A. A. and VETERANS APPROVED
ENROLL NOW FOR NEXT CLASS
Write for Illustrated Catalog.
2206-16 E. HUNTINGDON ST., PHILA., PA.

FOR SALE
Master Controls for 3350 engines—Condition New
Carburetor Parts for PR 58 models & others
Fuel Injection Pump Calibration Test Machine—by Eclipse.
A & E ACCESSORIES ENGG.
55 Maple Ave. Sea Cliff, L. I., N. Y.

LOCKHEED LODESTAR

Cargo Version
two 1820-87 engines
Low Time
With $250,000.00
inventory of spare
Lockheed parts

$9900.00 at Honolulu

M. P. WOOLLEY—Pier 12
Honolulu, T. H. 5-9427

EXECUTIVE BONANZA

Serial No. 1275—NC 4459V—Total time aircraft 500 hrs. Zero time engine with new type starter. Complete NARCO Omni Directional VHF Flares. Directional Gyro. New plastic prop. Curtains, slip covers, all bulletins complied with. Used as demonstrator only. **PRICE $7,500.00**
WINGS, INC. **AMBLER, PA.**
Call: Guy Miller Telephone: Ambler 1800

new and used DC-3 and DC-4 parts, equipment and accessories at below cost!

For DC-3, DC-4 and P. & W. R-1830 and P. & W. R-2000 parts, accessories and components, contact:

Surplus Sales Representative,
Stores Dept.
United Air Lines Maintenance Base,
Bayshore Highway,
South San Francisco, Calif.
Telephone JUno 8-2424

Items are available for your inspection at the above address. Prompt delivery. Guaranteed to be as represented.

UNITED AIR LINES



CLETRAC TRACTORS

Complete with Garwood winch, 6 cyl. Hercules engine. G.E. 110 volt electric light plant. Ingersoll Rand Air Compressor, 2000 lb. Cap. Cost government approx. $19,000 ea.

OUR PRICE $1000.00 each

Consolidated Industries
Dover, Delaware

These Special Engines will increase the Performance

of your

DC-3 C-47

- Shorter takeoff run
- Faster cruising speed
- Higher single engine ceiling
- Improved normal rate of climb

Your Douglas can be given greater safety and increased performance by a REMMERT-WERNER installation of new PRATT & WHITNEY R-1830-75 engines—a quick surprisingly inexpensive modification that will pay big dividends to your flying pleasure and peace of mind.

We will convert your P&W R1830-92 Douglas to P&W R1830-75 operation $10,000 complete

Individual power package units for your own installation

P&W R1830-75 Engines new and modified.....each	$3,500.00
Propellors (optional) 23E50-6565A-18 for P&W R1830-75 .....each	$600.00
Modification kit, with drawings, to modernize P&W R1830-75 .....each	$500.00
(additional kits, less drawings).....each	$300.00

ALSO AVAILABLE

DOUGLAS P&W R1830-92 engines....	$2,385.00
Propellors new.....	500.00
BEECHCRAFT P&W R985 engines.... (drilled for hydromatic)	1,650.00

Engines no time since first overhaul—100 hour guarantee allowance for old engine—Installation $200.00

REMMERT-WERNER, INC.

Lambert Field St. Louis 21, Missouri

C.A.A. Repair Station #3919

P & W ENGINE PARTS

FOR ALL ENGINES—BRAND NEW

AT 50% DISCOUNT

OF WAR ASSETS LIST PRICE

COMPLETE STOCKS AVAILABLE

SEND YOUR INQUIRIES IMMEDIATELY

GENERAL MATERIALS CO.

8 Water Street Brooklyn 1, N. Y.

Tel: Main 4-8580

WESTERN UNION, "WUXNY" CABLE ADDRESS "GENEMATER"

STRICTLY PERSONAL

ANOTHER BUST ON US—An anonymous note from the staid headquarters of the Institute of the Aeronautical Sciences here in New York, asks "Where, Oh Where, Is that Navion?" Says our mysterious correspondent: "According to AVIATION WEEK report, Ryan Navion equipped with JATO Junior unit gets a boost of 250-lb. thrust for 12 MINUTES from the small 50-lb. installation. 'Climbs fast,' comment the blase editors."

* * *

THE FAMOUS MITTY REPORT—We have received several copies of the famous autobiographical report by the mythical character Walter Mitty, allegedly written in 1947, and still making the rounds of our more serious brethren in aviation. It is a classic of engineering gibble-gabble-gobble-degook and we enrich the literature of American aviation by quoting it here. This version comes from **Harold Hoekstra** of CAA. Here goes:

THROUGH THE SONIC WALL

We were slipping smoothly through the air at 540 mph. I'd always liked the little XP-AZ5601-NG because of her simple controls and that Prandtl-Reynolds meter tucked away in the upper right corner of the panel. I checked over the gages. Water, fuel, rpm., Carnot efficiency, groundspeed, enthalpy. All OK. Course 270°. Combustion efficiency normal at 23 percent. The good old turbojet was rumbling along as smoothly as always and Tony's teeth were barely clattering from the 17 buckets she'd thrown over Schenectady. Only a small stream of oil was leaking from the engine. This was the life.

I knew the engine in my ship was good for more speed than we'd ever tried. The weather was so fair, the sky so blue, the air so smooth, I couldn't resist letting her out a little. I inched the throttle forward a notch. The regulator only hunted a trifle and everything was steady after five minutes or so. 590 mph. I pushed the throttle again. Only two nozzles clogged up. I pushed the small-slot cleaner. Open again. 640 mph. Smooth. The tailpipe was hardly buckled at all—there were still several square inches open on one side. My fingers were itching on the throttle and I pushed it again. She worked up to 690 mph., passing through the shaft critical without breaking a single window in the ship. It was getting warm in the cockpit so I gave the vertex refrigerator a little more air. Mach 0.9! I'd never been that fast before. I could see a little shocklet outside the port window so I adjusted the wing shape and it disappeared.

Tony was dozing now and I missed the smoke from his pipe. I couldn't resist letting the ship out another notch. In ten minutes flat we leveled off at Mach .95. Back in the combustion chambers the total pressure was falling like hell. This was the life! The Karman indicator showed red but I didn't care. Tony's candle was still burning. I knew gamma was down but I didn't give a damn.

I was dizzy with the thrill. Just a little more! I put my hand on the throttle but just at that moment Tony stretched and his knee struck my arm. The throttle jumped up a full ten degrees! Crash! The little ship shuddered from stem to stern and Tony and I were thrown into the panel by the terrific deceleration. We seemed to have struck a solid brick wall! I could see the nose of the ship was crushed. I looked at the Mach meter and froze. 1.00! My God, I thought in a flash, we're on the peak! If I don't get her slowed down before she slips over, we'll be caught in the decreasing drag! I was too late. Mach 1.01! 1.02! 1.03! 1.04! 1.06 1.09! 1.13! 1.18! I was desperate but Tony knew what to do. In a flash he threw the engine into reverse! Hot air rushed into the tailpipe, was compressed in the turbine, debusted in the chambers, expanded out the compressor. Kerosene began flowing into the tanks. The entropy meter swung full negative. Mach 1.20! 1.19! 1.18! 1.17! We were saved. She crept back, she inched back, as Tony and I prayed the flow divider wouldn't stick. 1.10! 1.08! 1.05! crash! We had struck the other side of the wall! Trapped! Not enough negative thrust to break back through! As we cringed against the wall, the tail of the little ship crushed, Tony shouted, "Fire the JATO units!" But they were turned the wrong way! Tony thrust his arm out and swung them forward, the Mach lines streaming from his fingers. I fired them! The shock was stunning. We blacked out.

I came to as our gallant little ship, ragged from stem to stern, was just passing through Mach zero. I pulled Tony out and we slumped to the ground. The ship decelerated off to the east. A few seconds later we heard the crash as she hit the other wall.

They never found a single screw. Tony took up basket weaving and I went to MIT.

—R. H. W.

WHAT'S NEW

New Books

"Principles of Aircraft Propulsion Machinery," by Israel Katz, thoroughly covers the fundamental aspects and nature of modern aircraft powerplants; piston, turbojet, propjet, ramjet, and rocket motors. Especially interesting is the author's evaluation of existing equipment in light of historical data and developments yet under investigation. At the end of each chapter problems of a leading nature are posed to illustrate points often beyond the scope of the text. Engineering students should find these particularly advantageous, while graduate engineers would find much of the material valuable as an outline for further study. Illustrations cover the most modern types of powerplants and their components. Published by Pitman Publishing Co., 2 W. 45 St., New York 19, N. Y., 477 pages, price $6.50.

"National Air Race Sketchbook 1930-1949" by Fred W. Buehl and Harry S. Gann. Foreword by Tony LeVier. Profusely illustrated history of the air races from their advent. Account of each year includes sketches of outstanding entries, and given are data tables of entrants in each event, listing place taken, pilot, plane racing and license numbers, engine and displacement, speed, and prize money won. There are three-view aspect drawings of Thompson Trophy winners. Accurate and thorough compilation of data is noteworthy. Published by Floyd Clymer, 1268 So. Alvarado St., Los Angeles 6, Calif., 84 pages, price $2.00.

"Aviation Study Manual," vol. 1, book 2, and **"Instructor's Manual,"** vol. 1, book 3, are new textbooks prepared for the Civil Air Patrol cadet program, and designed for use in secondary schools. Book 2 is intended as a guide for teaching approximately 190 hr. of aviation material, which constitutes minimum requirements for the cadets. Book 3 is the manual for aiding instructors and CAP personnel in teaching the material contained in the former volume.

The comprehensive nature of these volumes and the clear-cut manner in which the lessons are scheduled make them valuable assets for any aviation study program. At present, the Government Printing Office turns out these manuals and CAP is responsible for distributing them within its organization. It is intended that extra copies will be made available through the printing office to accommodate requests from other organizations or interested individuals.

ADVERTISERS IN THIS ISSUE

AVIATION WEEK—DECEMBER 12, 1949

Aircraft Radio Corp. 50, 51
Agency—Burke Dowling Adams, Inc.
Allison Division, G.M.C. ..... Fourth Cover
Agency—Kudner Agency, Inc.
Ambrose Aviation Co., Frank 49
American Chemical Paint Co. 34
Agency—May Advertising Co.
Bendix Products Div. of Bendix Aviation Corp. ..... Third Cover
Agency—MacManus, John & Adams, Inc.
B. H. Aircraft Co., Inc. 52
Agency—Harold Marshall Adv. Co.
Breeze Corporation, Inc. 10
Agency—Burke Dowling Adams, Inc.
Century Geophysical Corp. 33
Agency—Gibbons Adv. Agency, Inc.
Clifford Manufacturing Co. 42
Agency—James Thomas Chirurg Co.
Consolidated Vultee Aircraft Corp. 29
Agency—Buchanan & Co., Inc.
Continental Motors Corp. 26
Agency—Cummings & Hopkins Adv.
Edison, Inc., Thomas A. 48
Agency—The Schuyler Hopper Co.
Eclipse-Pioneer Div. of Bendix Aviation Corp. 19
Agency—MacManus, John & Adams, Inc.
Esso Std. Oil Company 35
Agency—McCann-Erickson, Inc.
Fairchild Engine & Airplane Corp. 32
Agency—Cecil & Presbrey, Inc.
Federal Aircraft Works 30
Agency—Dwyer & Devoy Adv.
Fulton-Sylphon Div., Robertshaw-Fulton Controls Co. 37
Agency—The Griswold-Eshleman Co.
Garrett Corporation, The 5
Agency—J. Walter Thompson Co.
General Electric Company 4
Agency—G. M. Basford Company
Goodyear Tire & Rubber Co., Inc. ..... Front Cover
Agency—Kudner Agency, Inc.
Hamilton Tailoring Co., The 51
Agency—L. F. McCarty & Co.
Holley Carburetor Company 39
Agency—Holden-Clifford-Flint, Inc.
Indiana Gear Works 57
Agency—A. L. Perkins & Co.
Johns-Manville Corp. 44
Agency—J. Walter Thompson Co.
Lavelle Aircraft Corp. 8
Agency—Broomfield-Podmore Adv.
Lewis Engineering Co., The 34
Minneapolis Honeywell Regulator Co. ..... Second Cover
Agency—Addison, Lewis & Associates
New Departure Div., G.M.C. 3
Agency—J. M. Hickerson, Inc.
Pacific Airmotive Corp. 8
Agency—Walter McCreery, Inc.
Pesco Products Company 20
Agency—Fuller & Smith & Ross, Inc.
Radio Corp. of America 31
Agency—J. Walter Thompson Co.
Revere Corp. of America 9
Saab Aircraft Co., The 27
Agency—Allmanna Annonsbyran A.B.
Searchlight Section 52, 53, 54, 55
Snap-On Tools Corp. 41
Agency—Scott, Incorporated
Southeastern Aviation Underwriters, Inc. 52
Sperry Gyroscope Company 6
Agency—Chas. Dallas Reach Co., Inc.
Standard Pressed Steel Co. 50
Agency—R. E. Lovekin Corp.
Stratos Corporation 32
Agency—Cecil & Presbrey, Inc.
Torrington Co., The 40
Agency—Hazard Adv. Co.
United States Steel Supply Co. 24
Agency—Batten, Barton, Durstine & Osborn, Inc.
Waldes Kohinoor, Inc. 23
Agency—Grey Adv. Agency, Inc.
Western Gear Works 22
Agency—West-Marquis, Inc.
Wright Aeronautical Corp. 49
Agency—Chas. Dallas Reach Co., Inc.

PORTRAIT OF A *P.A.*

It is obvious that the P.A. we are talking about is not worrying about his gear problems . . . he has turned them over to IGW. We recommend that you investigate the specialized services of the Indiana Gear Works.



Left: An internal gear tooth grinding operation . . . one of many interesting and unusual operations performed by Indiana Gear Works to obtain character and precision in their products.

Indiana GEARS

GEARS • CAMS • INTRICATE AND PRECISE MACHINE PARTS

INDIANA GEAR WORKS • INDIANAPOLIS 7, IND.

LETTERS

MATS Reserve

I thought you might be interested to know that the basic concept of MATS has been extended into reserve activities. Under Lt. Gen. Harold L. George, a group of volunteers have formed the nation's first joint Air Force-Navy reserve project. The group is composed largely of air transport specialists, who with Maj. Gen. Lawrence Kuter's approval, have established a Western Experimental Division for MATS. (At Los Angeles Airport—Ed.)

All of us who are connected with the Western Experimental Division feel that the project is highly significant as the nation's first demonstration of successful Air Force-Navy unification on a reserve level by civilians. Moreover, it points up a new and very practical way in which reservists in commercial aviation can utilize their cumulative experience to serve national defense.

The fine, cooperative spirit shown by the Air Force and Navy reserve personnel in the new division, and the effective way in which they are working together, forecast the success of this project and add new evidence that the unification principle is sound and practical.

BERT D. LYNN
1452 North Seward St.
Los Angeles 28, Calif.

Early Coach Support

We read your splendid editorial, "The Trend to Mass Air Travel," and your very objective report of Capital's experience with the air coach.

Needless to say, we are most appreciative of AVIATION WEEK's support, which began when there was a very large question mark hanging over the air coach concept.

HAYES DEVER
Secretary and Director of Public Relations
Capital Airlines
Washington, D. C.

Beech Dividends

I have just read an article by Selig Altschul in AVIATION WEEK, Nov. 14, concerning dividends of aircraft companies. Mr. Altschul states that Beech, Cessna, North American, Fairchild, and Ryan have paid "token dividends" during 1949.

During our fiscal year of 1949, Beech paid four dividends of 25 cents per share, making a total of $1 per share distributed for the year. This is equal to the highest dividend rate that has ever been paid on Beech stock, and was paid on the increased volume of stock of 600,000 shares as compared with the original volume of stock of 400,000 shares which existed during the entire war period and for a couple of years thereafter, until the 50 percent stock dividend was issued.

Six hundred thousand dollars distributed to stockholders may be a "token" to Mr. Altschul, but our idea of a token is very substantially different from his, because we think that $600,000 is difficult enough to earn to remove it from the "token" class.

JOHN P. GATY
Vice President and General Manager
Beech Aircraft Corp.
Wichita, Kans.

Praises CAA

Your Oct. 17 issue with the comment regarding the CAA certification argument which was set off by Dr. Bollinger and the Helioplane project causes us to wonder just what goes. We have been working closely with CAA during the development of the Aerocar and we can assure you that we have not had the slightest difficulty in any regard on the certification requirements of CAA. We have found that instead of being a hindrance, as some people have claimed, CAA has been more than cooperative, and have done everything they could to assist us. If there was anything further they could do to be of assistance, I am sure they would do it.

As for the arguments against the certification, all we can say is that we are of the opinion that we would want to do everything CAA requires for our own information even if CAA didn't exist. The requirements of O4 are intended as a guide and a minimum requirement as far as we are concerned, and I am sure that without them it would be very easy to go off the deep end and get into trouble. Now maybe this isn't the situation in all CAA regions, but the 7th Region personnel and directors are certainly bending over backward to help us get the Aerocar into production, and the Washington office has made many special considerations which the unique nature of our machine has made necessary. We are pleased with their answers, and in every case where there has been any question, they have given our ideas every consideration.

Of course, we are comparatively inexperienced in aircraft production, and the benefit of manufacturing inspection by the same inspector who inspects the Boeing Stratocruiser has proved a great aid to us, you can be sure. His suggestions and recommendations only serve to make the Aerocar the sort of a product we want to produce. As far as cost is concerned, I would estimate that the requirements of CAA have not added $1000 to our cost in building the Aerocar, certainly not an excessive cost when you consider the satisfaction of having their experienced approval of our efforts.

We have approached the aircraft problem with no pre-conceived ideas, and we are finding that the "flying automobile" is opening an entirely new field of aviation. Even CAA is considering the Aerocar as different from conventional aircraft as the helicopter. Perhaps the difficulty with the Helioplane and some of the other more conventional planes is their conventionality.

Anyway, we can't see the point of people like Mr. Loening and Dr. Bollinger on this CAA-development question, and as soon as we fly the Aerocar and demonstrate that a little company can produce a new development even with CAA's aid, I am sure the critics are going to have to find something new to blame for their problems.

MOULTON B. TAYLOR, President
Aerocar
Longview, Wash.

Airport Service

I would like to make the point in connection with airline charters and airline special flights that when airlines make trips away from their regular scheduled routes and airports, they invariably expect service from other airlines, which means that the airport service operators or fixed base operators do not always get the business of gassing and servicing these chartered planes. Here again the airlines are competing with non-scheduled aviation, and frankly, we don't like it.

My interest in this matter is as a fixed base operator offering airport services at four airports, and not as that of a charter operator of large planes.

BEVERLY HOWARD, President
Hawthorne Flying Service
Charleston, S. C.

No Guns

In your column, Industry Observer, AVIATION WEEK, Sept. 12, 1949, your observer has been misinformed. The Spitfire which competed in the Tinnerman Trophy Race was not, repeat, not "one fully-equipped military aircraft."

I, personally, saw the guns removed here at Edmonton and armament consisted of two (2) .50 calibre machine guns, I agree the configuration was not changed but certainly the "fully-equipped military aircraft" description is not based on fact.

I would like to see a correction on this. I have a color photograph to prove my point.

MAJOR MIKE M. KOVACEVICH, USAF
P. O. Box 426
Edmonton, Alberta, Canada

(Maj. Kovacevich is correct. The Spitfire carried no guns, as was apparent to AVIATION WEEK staff members at Cleveland who examined the plane and interviewed its pilot, J. G. McArthur. The writer of the Industry Observer note considered it obvious, however that the armament of any combat plane must be removed before sale to a civilian pilot, and believed his reference to "factory-delivered" indicated an absence of armament.—Ed.)

(Kenneth Fletcher of TWA, whose letter appeared in AVIATION WEEK Nov. 21, is the carrier's Manager, Public Relations, at San Francisco. He was incorrectly identified as TWA's Director of Public Relations.—Ed.)

Bendix Products Division

FIRST IN FUEL METERING

From the Fastest to the Largest!

The outstanding ability of Bendix Products in keeping pace with aviation progress is graphically demonstrated in the scope of its accomplishments.

Bendix fuel metering systems on the latest and fastest jets, for example, are meeting conditions undreamed of a few years ago. Today the world's largest land plane is brought to a smoother sure stop with Bendix landing gear.

The fact that the experience and skill of Bendix Products are constantly utilized in record breaking achievements is ample evidence of its capacity to serve the practical needs of engine builders and airplane manufacturers.

Why not let this combination of engineering experience and manufacturing know-how help solve your fuel metering and landing gear problems.

LEADER IN LANDING GEAR


Fuel Metering Unit for jet engines
Stromberg* Injection Carburetors
Speed-Density Fuel Metering Unit
Pneudraulic* Shock Absorbing Struts
Landing Gear Wheels for all types of airplanes
Segmented Rotor Brakes

*REG. U. S. PAT. OFF.

BENDIX PRODUCTS DIVISION of
SOUTH BEND 20, INDIANA
AVIATION CORPORATION

Export Sales: Bendix International Division, 72 Fifth Ave., New York 11, N.Y.

2,000% MORE OPERATING TIME !

Allison aircraft turbine engines provide more time in the air, less time on the ground. Allison developments have increased the time between overhaul from 15 hours to 300 hours.



J33-A-23 Turbo-Jet

Allison

Builder of axial and centrifugal flow turbine engines

DIVISION OF GM GENERAL MOTORS Indianapolis, Indiana

Allison jet-powered airplanes:

Lockheed F-80 and TF-80 Shooting Star
Republic F-84 Thunderjet
Grumman F9F-3 Panther
Northrop F-89A Scorpion
North American FJ-1 Fury
Lockheed F-94
Consolidated XP5Y
Northrop RB-35B Flying Wing
Martin P4M-1 Mercator
North American AJ-1